

IFI/RPZ Report | April 2007 to March 2008 Inclusive

for the licensed companies:

EDF Energy Networks (EPN) plc EDF Energy Networks (LPN) plc EDF Energy Networks (SPN) plc



Foreword	4
1. Introduction	5
1.1 Context	5
1.2 IFI	5
1.3 RPZ	6
1.4 This Report	7
1.5 Company Structure	7
1.6 Strategy and Portfolio Management	
1.7 Project Partners	
2. Summary of IFI Project Activities	
2.1 Number of Active IFI Projects	11
2.2 Net Present Value (NPV) of Costs and Anticipated Benefits from Committed IFI Projects	
2.3 Summary of Other Benefits Anticipated from Active IFI Projects	
2.4 Total Expenditure to Date on IFI Projects	
2.5 Benefits Actually Achieved from IFI Projects to Date	
2.6 Tabular Summary	
2.7 Registered Power Zones	
2.8 Highlighted Project	
3. Completed IFI Projects Delivering Benefits	
3.1 DG Planning Software	
3.2 GenAVC Assessment Tool	
3.3 Battery Asset Management	
3.4 Transformer Damping	
3.5 Evaluation of the Characteristics of Alternative Oils	
3.6 Domestic Cut-Out Temp Indicators	
3.7 Power Factor Analysis	
3.8 Primary SCADA Communications IP Upgrade	
4. Individual IFI Projects	
4.1 On-line condition monitoring	
4.2 Vulnerable Customers UPS	
4.3 Bankside Heat Transfer	
4.4 Improved Fluid-Filled Cable Leak Location System	
4.5 AURA NMS – Autonomous Regional Active Network Management System	
4.6 Transformer Design for FR3	
4.7 Vacuum Tap Changer	
4.8 Vegetation Management	
4.9 Distribution System State Estimation	
4.10 DG Connection Planner	
4.11 Flexible Electricity Networks to Integrate the expected 'energy evolution' FENIX	
4.12 Optimal Transformer Utilisation Model	
4.13 Impact of Climate Change on the UK Energy Industry	
4.14 RTU Local Display Facility	
4.15 Condition Monitoring of Composite Insulators	
4.16 Improvements in Overhead Line Performance	
4.17 Application of Storage and Demand Side Management	
4.18 Network Risk Management	
4.19 Supergen V - AMPerES	
4.20 Wood pole disposal	
4.21 LV Underground Cable Fault Management	
4.22 33kV Voltage Control	
4.23 Collaborative ENA R&D Programme	
4.24 Activ Project	
4.25 Recycling Excavated Material	
4.26 Grid Transformer Monitoring	



4.27 Earthing Information System	94
4.28 Electrical Energy Harvesting from Vibrations	
4.29 Transformer Temperature Fibre Optic Monitoring	
4.30 Power Networks Research Academy	
4.31 Supergen I – FlexNet	
4.32 Strategic Technology Programme Overhead Network N	
4.33 Strategic Technology Programme Cable Networks Mod	dule106
4.34 Strategic Technology Programme Substation Module	109
4.35 Strategic Technology Programme Networks for Distrib	uted Energy Resources Module112
5. Steyning Primary RPZ	115



Foreword



Welcome to EDF Energy Networks' Innovation Funding Incentive (IFI) activity report for the regulatory year 2007/08. I am pleased to report that we have been able to show our continued commitment to the Innovation Funding Incentive to encourage increased activity in research development and demonstration by utilising our allowance completely. I believe we have spent the allowance wisely and effectively over a portfolio of projects. Section 1.6 describes the portfolio.

This year has seen EDF Energy publish its Climate and Social Commitments. These documents can be viewed on the EDF Energy website. The Climate Commitments impact all areas of our company business. Some of the technologies within our IFI portfolio will help us achieve these targets. The document specifically mentions the fluid-filled cable leak location technique which is already delivering measurable benefits (see section 4.4).

In its Social Commitments EDF Energy has made a pledge that "We will lead the industry in protecting vulnerable customers from the adverse effects of power cuts". A good example of our efforts towards this is our work with Ceres Power to develop a hybrid fuel-cell UPS device to help vulnerable customers from being affected when power failures occur, by providing an emergency light and power for essential medical equipment.

We have been instrumental in establishing a collaborative framework with the Engineering and Physical Sciences Research Council to increase the number of researchers and teachers at UK universities. The Power Networks Research Academy complements the IET Power Academy in attracting students to carry out research in power engineering.

The Energy Technology Institute (ETI) has been established to demonstrate the necessary technologies required to deliver a sustainable future. EDF Energy Networks is working with many other companies to ensure the UK remains at the forefront of research and development within the power industry.

EDF Energy Networks has continued to be involved in the European Commission Framework projects. Preparations are being finalised to engage in Project ADDRESS, to understand how distributed generation and demand side management can assist in the management of distribution networks.

After three years of building the IFI project portfolio there are several projects now being actively demonstrated, proving new technologies and realising the business benefits that we expected to see at their inception. The focus in the coming year is to increase the realisation of such benefits from these and new projects.

Barry Hatton Director of Capital Programme EDF Energy Networks



1. Introduction

During the development of the Distribution Price Control Review (DPCR) that took effect on 1 April 2005, Ofgem proposed two new incentives: the Innovation Funding Incentive (IFI) and Registered Power Zones (RPZs).

1.1 Context

As part of the DPCR and TPCR, Ofgem has introduced the IFI mechanism. IFI was consulted on as an integral part of the DPCR and TPCR proposals and was widely supported by a large majority of consultees. The primary aim of the incentive is to encourage the network operators to apply innovation in the technical development of their networks. Ofgem recognises that innovation has a different risk/reward balance compared with a network operator's core business. The incentives provided by the IFI mechanism are designed to create a risk/reward balance that is consistent with research, development, demonstration and deployment.

The IFI is intended to provide funding for projects primarily focused on the technical development of the networks, to deliver value (e.g. financial, quality of supply, environmental, safety) to end consumers.

The detail of the DNO IFI mechanism is set out in the Special Licence Condition C3 and Standard Licence Condition 46. It can be summarised as follows:

- A network operator is allowed to spend up to 0.5% of its combined distribution network revenue or its combined transmission network revenue (subject to a minimum of £500,000), as the case may be on eligible IFI projects. The good practice guide provides guidance on the required characteristics of such projects;
- network operator IFI expenditure, that is internal expenditure, will be allowed as part of the total IFI expenditure accrued by the network operator;
- the network operator is allowed to recover 80% of its eligible project expenditure via the IFI mechanism within the network operator's licence;
- Ofgem will not approve IFI projects but network operators will have to openly report their IFI
 activities on an annual basis. These reports will be published on the Ofgem website; and
- Ofgem reserves the right to audit IFI activities if this is judged to be necessary in the interests of customers.

In Ofgem's review of IFI and subsequent open letter response of 14th February 2007, the Authority agreed:

- A commitment to extend the DPCR4 IFI scheme until the end of DPCR5 with a flat pass through rate of 80%;
- The removal of the 15% cap on internal IFI expenditure for both distribution and transmission licences when requested to do so by a licensee; and
- To work with the industry to review and revise the guidance documents by means of which IFI is controlled and managed.

1.2 IFI

Projects will be judged as eligible within the IFI provided that:

- The project satisfies the eligibility criteria described in the ENA Engineering Recommendation G85, Issue 2, Innovation Good Practice Guide for Energy Networks;
- The project has been well managed; and
- Reporting requirements have been met.

Work that has been approved within an industry recognised (or national/governmental) programme (e.g. Department for Business Enterprise and Regulatory Reform (BERR) or European Commission Funding under R, D, D&D Frameworks), whose terms of reference clearly address innovation in the



networks may be considered eligible within IFI if it meets the defined criteria. Co-operation between network operators and other organisations to pursue IFI projects is encouraged. In such cases the overall project would be expected to meet the IFI eligibility criteria; it would then be acceptable for each participating network operator to use the eligibility case for the overall project. IFI projects that secure additional funding from outside agencies, such as BERR or the European Commission, will not trigger any clawback of IFI funding by Ofgem. Engagement with industry engineering committees is not considered eligible as this does not constitute a project with a specific target or deliverable.

In the event that a network operator provides resources to contribute to an eligible IFI project which is led or managed by a third party then those costs incurred by the network operator, that are not recovered from the third party will be considered to be eligible IFI expenditure. Where supporting such projects results in a net cost to the network operator, the network operator should demonstrate, at a level appropriate to the costs involved, that the expected benefits to the network operator exceed the costs involved.

IFI projects, by their nature, involve risk. It is understood, therefore, that not all IFI projects will meet their aims and objectives and deliver net benefits. However, it is expected that the benefits from those that do succeed will significantly exceed the overall costs of a network operator's IFI programme.

1.3 RPZ

An RPZ is a zone of network where innovative practices, that allow distributed generation to connect more easily, are demonstrated. RPZs are intended to encourage DNOs to develop and demonstrate new, more cost-effective ways of connecting and operating generation that will deliver specific benefits to new distributed generators (DG) and broader benefits to consumers generally. A DNO will receive additional income (over and above the main DPCR4 DG incentive) which will be recovered by the Generator Distribution Use of System (GDUoS) charge. The DNO must demonstrate that an innovative solution could offer material advantages to DG customers compared to a conventional solution.

Although an RPZ requires the connection of a new generator, RPZs are not restricted to greenfield sites. The RPZ may contain existing generators, although only new generators will attract the RPZ premium. Where an RPZ is commissioned in stages, the DNO's entitlement to the five-year period of the RPZ premium will be triggered by the commissioning date of each generating unit. The total MW of installed capacity cannot exceed the registered capacity. An individual generating unit forming part of staged development of an RPZ must be commissioned by 31 March 2012 to qualify for the RPZ premium.

Each RPZ is defined as a collection of contiguously connected distribution system assets (i.e. which provide an electrical path for the distribution of electrical energy) having one or more terminal points which together describe in full the RPZ's boundary with the total system. These terminal points will be selected such that any system components or connected customers (existing demand and generation) that may be affected by the RPZ project are included within them.

The definition of an RPZ allows flexibility and will need to be applied differently depending on the project. For example, if a number of small generators are involved, it may be useful to define the limits of the RPZ in terms of geography as well as electrically, as this will be a boundary that the stakeholders can identify. On the other hand, if an RPZ involves, for example, the innovative connection of a wind farm in a remote area, defining the boundary in terms of a circuit may be



sufficient. The boundary may need to be adjusted if new DG is connected on the edge of an RPZ, provided that it is judged appropriate to include the new DG in the demonstration of innovative practices.

1.4 This Report

This report contains a summary of EDF Energy Networks' IFI activities for the period April 2007 to March 2008 inclusive. Following the publication of the ENA Engineering Recommendation G85 Innovation Good Practice Guide for Energy Networks, issue 2, December 2007 this IFI activity report uses the new individual project report template. Additional information includes the project collaborators and research providers. The guide also introduces a measure of a project's benefits rating, project's residual risk and an overall project score. These measures have been calculated using the guidance for new projects that started during this reporting period. The measures are blank for existing projects.

EDF Energy Networks withdrew one RPZ from the EPN network during the period covered by this report, namely the Martham Primary RPZ in North Norfolk.

The GenAVC voltage control system that was being trialled at Martham has been removed in preparation for the installation of an electrical energy storage device at Hemsby. As part of the Aura NMS project (section 4.5) we will install a storage device at a normal open point between Martham and Ormesby Primary substations. The power electronic interface for the storage device could conflict with the GenAVC in attempting to control the voltage profiles of the 11kV feeders supplied from Martham. Once the electrical energy storage device has been installed it is our intention to reregister Martham Primary as an RPZ.

1.5 Company Structure

EDF Energy owns and operates the licensed distribution networks serving the East of England, London and the South East of England. The licensees managed by EDF Energy Networks Ltd are:

- EDF Energy Networks (EPN) plc for the East of England, referred to as 'EPN' in the rest of this report:
- EDF Energy Networks (LPN) plc for London, referred to as 'LPN' in the rest of this report; and
- EDF Energy Networks (SPN) plc for the South East of England, referred to as 'SPN' in the rest of this report.

These licensed areas are shown in the map overleaf.

Research, Development and Demonstration activities are conducted by EDF Energy Networks for the benefit of our customers on behalf of the three licensed network operators named above. This year (as with last year), we have continued to allocate expenditure to each licensed network in proportion to the major asset associated with each individual project. Section 2.4 provides a tabulated summary of expenditure and a graphical representation comparing expenditure with the IFI allowance.






Figure 1 Licensed areas of EDF Energy Networks



1.6 Strategy and Portfolio Management

In the 2006/07 IFI activity report our strategy was described detailing the four work programmes namely, Sustainability and Environment, Network Operations, Asset Management and Future Networks. This report contains an explanation of how some of our IFI projects link together in those work programmes to deliver the strategy. This is more easily represented by the diagram below, which shows how many projects overlap between the different work programmes.




Figure 2 Diagram showing how some IFI projects map to the work programmes

"Smartgrids" is an international theme, both in Europe and the US. EDF Energy Networks has continued to participate in the work carried out in the UK, by the Electricity Networks Strategy Group (ENSG) and the Centre for Sustainable Electricity and Distributed Generation (SEDG). FENIX is a European FP6 project (section 4.11) that will allow distributed generation (DG) to be integrated into the networks of the future. AURA NMS (section 4.5) seeks to improve the security of supply of both load and generation customers. The output of the two projects will contribute to a new FP7 EU funded project called ADDRESS which seeks to integrate all customers in providing ancillary services to network operators. These projects will require smart meters with functionality to provide customers with necessary information to decide when they use their electricity. Together they form part of the Future Networks work programme.

Asset management continues to be increasingly important in attempting to extend the life of assets and in prioritising their replacement. The fluid-filled cable leak location system (section 4.4) has developed a method to find leaks in fluid-filled cables, allowing the worst leaking cables to be replaced first. Various condition monitoring projects relating to power transformers, cables and switchgear (section 4.1) are ongoing. They will help reduce the risk of managing the network and improve security of supply.



The Integration of DG is related to the Future Networks programme, but the outputs will deliver benefits in the near future. The DG connection planner application (section 4.10) will allow DG developers to use a web-based tool to consider a number of potential sites before contacting EDF Energy Networks for a formal quote. The DG planning software (section 3.1), as a proof of concept, has allowed network planners to study the impact of a DG connection proposal by more efficiently importing network data to build network models. The GenAVC assessment tool project (section 3.2) has shown it can allow additional DG to be connected without network reinforcement. FENIX will deliver the control system applications to manage network constraints which may be due to power flow, voltage rise or fault level contribution. The 08/09 portfolio will include a project to develop DG technology for networks with little or no fault level headroom. Voltage control strategies are also being investigated and may be deployed as future RPZs. Within AURA NMS, an electrical energy storage device is being connected to the 11kV distribution network. The output of the Application of Storage and Demand Side Management (DSM) project (section 4.17) will be verified using this device. The Distribution System State Estimation project (section 4.9) will contribute to the AURA NMS decentralised control system, where each controller will have a situational awareness of the network.

The customer remains the focus of our IFI portfolio. The development of a proof of concept hybrid fuel cell UPS device (section 4.2) is receiving great interest from individuals and organisations representing vulnerable customers who are dependent on an electrical supply for their medical equipment. Other projects that will reduce the impact of supply interruptions include the on-line condition monitoring of assets and the Network Risk Management project (section 4.18). Both projects may influence the network investment required to build a sustainable future. All network operators and most supply businesses participated in the Met Office Impact of Climate Change project (section 4.13). The results will inform the way we design our future networks. A number of projects have already delivered benefits (section 3) e.g. as part of a trial of a Climate Control Device (section 3.3), the life span of batteries in hot substation environments are being significantly extended.

With regard to future projects that meet the IFI criteria, EDF Energy Networks is drafting a number of proposals. These include an assessment of the benefits of the Common Information Model (CIM), a strategy for the reduction of losses, the benefits and risks of using superconducting cables in high load areas and the opportunities that smart metering could deliver to a network operator.

1.7 Project Partners

In this report each individual project report details the research and collaborative partners. In previous years' activity reports, EDF Energy Networks would not report the names of project partners until a report, paper or publication was in the public domain.



2. Summary of IFI Project Activities

2.1 Number of Active IFI Projects

There are a total of 35 active IFI projects. Eight new projects were started this year and seven were closed. The closed projects are reported in section 3 providing details on the next steps and the benefits being realised. The four EA Technology Ltd (EATL) Strategic Technology Programme (STP) modules are also reported.

2.2 Net Present Value (NPV) of Costs and Anticipated Benefits from Committed IFI Projects

It is estimated that the current EDF Energy Networks' IFI portfolio will deliver benefits of £26.7M. The Project NPV benefit of each project in the IFI Programme is calculated by taking the present value of the estimated benefits and applying a probability of success. Estimated costs are netted off the anticipated year of occurrence. A discount rate of 6.9% has been used.

A number of overhead line performance improvement projects fall below the de-minimis level set in the Good Practice Guide. These have been grouped together to form a programme. The benefits of this programme are estimated to be in the order of £1.0M.

Each project undertaken in a STP module falls below the de-minimis level set in the Good Practice Guide. It is recognised that, as each project has variable benefits and different start/completion timeframes, it is not possible to give a specific figure for the benefits achieved against a given financial year. The benefits will be across a range of areas including construction, maintenance, refurbishment and operation.

2.3 Summary of Other Benefits Anticipated from Active IFI Projects

Other benefits anticipated from active IFI projects include:

- An improvement in the security of supply and quality of service received by our customers;
- A reduction in the cost of DG connections; and
- Environmental and safety benefits.

2.4 Total Expenditure to Date on IFI Projects

Regulatory year	Total expenditure
This regulatory year 07/08	£4,993.5k
Regulatory year 06/07	£3,575.8k
Regulatory year 05/06	£2,570.9k
Early start report 04/05	£ 275.8k
Total	£11,416.0k






Figure 3 IFI Expenditure



2.5 Benefits Actually Achieved from IFI Projects to Date

During this regulatory year EDF Energy Networks has completed eight projects. Section 3 explains the benefits we have obtained and what still needs to be done to integrate the concepts into the business. A summary of some of the benefits being realised is detailed below.

The **DG Planning Software** project delivered a proof of concept solution. It demonstrated the potential to significantly reduce the engineering time taken to create the network analysis models, required to support the DG connection request process. The proof of concept tool has been used by planners and has reduced the preparation time to carry out studies. The total annual benefit is expected to be approximately £300k.

The **GenAVC Assessment Tool** project delivered:

- A tool that is able to assess whether voltage rise issues, associated with additional generation, can be overcome by installing GenAVC;
- A cost efficient connection for DG developer allowing additional generation to be installed; and
- Avoidance of nuisance trips at times of high volts are avoided by the generator.

EDF Energy Networks' planners now use the tool to determine whether GenAVC can resolve DG connection voltage problems rather than expensive network reinforcement.



Figure 4 GenAVC RTU installed at Horton Quarry, Steyning

The **Battery Asset Management** project developed a new range of innovative, sustainable, low power, localised air conditioning units that can be applied to sensitive pieces of equipment; in this instance, RTU batteries in distribution substations. These batteries form the power source for automatic remote control equipment in the network and are subject to thermal degradation which leads to increased CIs and CMLs. The successful implementation of the concept in RTUs has led to the introduction of the concept for other applications such as:

- Battery cabinets in substations;
- Auto reclosers (e.g. the NULEC); and
- Any other device which uses batteries and could be exposed to high temperatures.



Figure 5 The 4Energy Midi BAC (right) with a London distribution substation Remsdaq RTU



The **Domestic Cut-out Temperature Indicators** project investigated the use of low cost, thermally sensitive labels to give a meter inspector an indication of whether a domestic cut-out has been overheating.

The project showed that the most appropriate temperature sensors were the circular type (clock indicators, range 2 – RS code: 285-970). The best locations were found to be the top and bottom of the fuse carrier. A range of temperature from 60°C to 82°C appears to be most appropriate for this application.




Figure 6 Domestic Cut-out showing the temperature sensitive labels under test.

The **Primary Scada Communications IP Upgrade** project allows the use of independent communications infrastructures and dual routes to the RTU. The link between the RTU and the control centre chooses the best link available e.g. satellite or GSM/GPRS. The IP protocol has allowed rapid deployment of different communications infrastructures and has facilitated the smooth introduction of ENMAC to control the SPN network. The satellite link has proven reliable even during storms.

Implementing the communications network via satellite was essential as it enabled immediate coverage across the SPN network while giving the option to extend the SCADA network to the EPN network. The technology deployed uses a TDMA (Time-Division Multiple Access) access scheme, which shares the available bandwidth across hundreds and potentially thousands of sites, thereby giving a cost-effective solution. Satellite communications are highly scalable, allowing for growth in both number of sites and bandwidth.



Figure 7 Earth Station at Fore Hamlet




Other projects that are still in the demonstration or verification stages are also starting to deliver benefits.

On-line condition monitoring: The number of feeders monitored (including cable and switchgear) has increased during the last year. Below is a summary of what has been delivered so far as part of the IFI project.

Equipment developed:







Several versions of the monitoring equipment are now available:

The fixed equipment can be used to monitor a large number of assets (cable or switchgear) whilst the portable equipment can be deployed and re-deployed at short notice to investigate problems for a limited period of time.

Figure 9 Portable Equipment

Sensor developed:





A variety of sensors can be attached to the online monitoring equipment to monitor incipient faults in cable and switchgear.

Figure 10 Switchgear monitoring Figure 11 Cable monitoring

Web-based interface developed:


The web analysis interface provides an easy way to analyse the data and prioritise assets requiring further investigations.



Figure 12 The web analysis interface



The technology developed to date has enabled EDF Energy Networks to capture a number of network events (examples below).






Figure 13 Increase discharge activity

Figure 14 Joint failure

This information is helping EDF Energy Networks understand the behaviour of incipient defects, anticipate the impact of a fault, and will help reduce the number of customer interruptions.

Project benefits:

Although research work is still on-going, EDF Energy Networks is already able to:

Detect, locate and repair incipient cable faults before they occur;

- Target and prioritise cable replacements;
- Remotely monitor substations and receive automatic alarms;
- carry out remote partial discharge and safety checks before an employee enters a substation; and
- Move from reactive to proactive fault management.

Once the project is completed and the technology deployed, EDF Energy Networks expects to gain the following additional benefits:

- Improvement of quality of supply (CI, CML); and
- Reduction in Operational expenditure.



Fluid-Filled Cable Leak Location System trials have generated interest from ERDF (French DNO) and ESKOM in South Africa. Representatives from these companies attended site when the Leak Location System was being demonstrated.

During the trials, eight leaks have been found and repaired successfully, involving only nine excavations. This project also showed that the typical cost of finding a leak has reduced from approximately £40k to £5k.




Figure 15 Schematic diagram of the leak location system

The traditional freezing technique usually requires two or more excavations in the highway and can only find one leak at a time. The circuit needs to be switched out and allowed to cool down (typically for several days) before a freeze can be applied. Freezing also has a detrimental effect on the lead cable sheath.

The new system offers several benefits:

- It allows multiple leaks to be found at the same time;
- It allows leak repairs to be prioritised;
- Customers' security of supply is only reduced for the time it takes to carry out the repair; and




Figure 16 Aerial photograph with FFC and leak locations identified

Not only does this system allow leaks to be found more quickly while the circuit remains in service, it allows the leak location team to move on to repair other circuits. On one occasion, three leaks were found and repaired in a week, compared with an estimated three weeks using the traditional method.



2.6 Tabular Summary

	EPN	LPN	SPN	TOTAL
IFI carry forward from 06/07 (£k)	£0	£514.8k	£181.5k	£696.3k
Eligible IFI expenditure 07/08	£1,918.3k	£1,894.3k	£1,181.0k	£4,993.6k
Eligible IFI internal expenditure 07/08	£203.0k	£185.1k	£123.3k	£511.4k
Combined distribution network				
revenue (£m)	£384.6M	£278.8M	£201.9M	£865.3M
The IFI carry forward to 2008/09	£4.7k	£0	£0	£4.7k

2.7 Registered Power Zones

RPZ Name	Steyning Primary RPZ
RPZ DG Capacity (MW)	1.5MW
RPZ starting year	06/07

See RPZ report in Section 5.

2.8 Highlighted Project

In last year's report, we highlighted a number of projects that would be of interest to readers of the report. The following article "Cable fluid leaks located without digging" is taken from an internal company magazine.



Cable fluid leaks located without digging

EDF Energy Networks has made great progress towards the deployment of new technology to assist in the timely location of leaks on its extensive network of fluid filled cables.



Test van



R.E.A.D. sensor unit

The most important aspect of new technology is the development and field trials of a system which uses minute quantities (a few parts per million) of a Perfluorocarbon Tracer (PFT) – a chemical tag added to replacement cable fluid. When the tagged fluid reaches the site of a leak its volatile nature means that it quickly appears on the surface as minute wisps of gas.

A technology called R.E.A.D. (Random Electron Attachment Device) is used to detect the presence of PFT. This was developed in conjunction with the manufacturer, Femtotrace, Inc. and scientists at the NASA Jet Propulsion Laboratories in Pasadena, California.

The technology is similar to that used on deep space exploration craft for analysing the atmospheres of planets and the solar system. The high sensitivity of the device means that it can be fitted into a vehicle and driven along the route of a

leaking cable circuit. The site of a leak can be established without even stopping the vehicle.

The work carried out by Asset Optimisation and Technology and Customer Operations (EHV Cables Department), has led to the successful location of several cable leaks without the need for a single excavation. This provides the following advantages:

- Only one excavation is required to repair the cable, so customers suffer less disruption;
- In the long term, the amount of cable fluid leaked will be significantly reduced, which protects the environment:
- The whole process is carried out with the circuit in service which reduces the risk of supply interruptions
- Leaks can be located at significantly lower cost than existing methods; and
- Reduction in the amount of waste materials which need specialist disposal.

We plan to put this technology into full scale use in the whole of EDF Energy Networks by the end of 2007.

The versatility of the technology means that it can be used for other important analytical tasks. Work is now underway to identify and develop further uses for the device, which should greatly enhance the effective management and maintenance of EDF Energy Network's network.



Sample trace – the higher the peak, the closer the leak!

This project is part of our Transformation programme. Transformation is about making us more efficient through achieving productivity improvements and increasing income as well as making savings and improving the service we give our customers.



3. Completed IFI Projects Delivering Benefits

(Projects ordered by Expenditure)

- DG Planning Software
- GenAVC Assessment Tool
- Battery Asset Management
- Evaluation of the characteristics of Alternative Oil
- Transformer Damping
- Domestic Cut-out Temperature Indicators
- Power Factor Analysis
- Primary Scada Communications IP Upgrade



3.1 DG Planning Software

3.1 DG Planning S	oftware					
	The purpose of this project was to investigate how to model distributed generation, by using automated interfaces to pass data between the existing EDF Energy Networks' Smallworld/Netmap GIS system and a next generation network modelling/analysis tool called DigSilent PowerFactory. The project identified two candidate interface technologies – one					
	produced by Mett enabled data trar	enm Isfer	eier, and the o between Netm	ther prod ap and P	uced by lī owerFacto	rs. These ry. A proof of
Description of Completed Project	concept application was developed using both candidate interfaces. The project discovered that by using this technology, the work of analysing the impact of attaching distributed generation to the networ could be much quicker than the current processes used to perform the analysis. It is enabling planners to perform many more analyses and tralternative connection approaches in the same time period. The project also discovered that the Mettenmeier interface was technically superior for this application than the ITS interface. A prototype demonstrator was developed during the project which is used to demonstrate the concept to EDF Energy Networks and external stakeholders.					
Expenditure for		EPI	N	LPN		SPN
financial year	External		£167,608		£66,345	£115,231
	Internal	£21,857		£8,652	£15,027	
	Total	tal £189,465 £74,997 £130,2 5				£130,258
	The costs have be distributed gener		•	portion t	o the amo	unt of connected
Expenditure in	External	£1:	28,658			
previous (IFI) financial	Internal	£ 1	16,934			
years	Total	£14	45,592			
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 400,000					
Technological area and/or issue addressed by project	To provide a mechanism to develop a DG connection strategy focussed on ease of use.					
Expected Timescale to adoption	During 2008 Duration of benefit once achieved 15 years			i		
Probability of Success	Proof of concept delivered. Project NPV (Present Benefits – Present Costs) x Probability of Success ### 4360,000				00	
Benefits Achieved	The project delivered: A proof of concept solution demonstrating that there is the potential to significantly reduce the engineering time taken to create the network					



analysis models that are needed to support the DG connection request process.

The primary business benefits, once the final product is deployed, will include:

- Improved customer service;
- Increased process efficiency; and
- Cost savings.

Utilising Netmap as the enterprise wide data repository for connection analysis models also potentially provides the following benefits:

- Common process across EDF Energy Networks' regions;
- Identification of other connection requests that are in the same area and are still in the planning stage;
- Provision of audit/tracking functionality and supporting evidence to defend decisions made;
- Models are easily regenerated later;
- The ability to more easily manage enquiries at multiple offices/locations; and
- The opportunity to more easily identify deep reinforcement requirements arising from multiple connection enquiries and other planned schemes, which could also be managed through this system.

A significant cost benefit is achievable from the reduction in skilled staff time and effort through the automation of study file creation. Typically, the current five or more days of skilled staff effort in modelling and analysing an HV network feeder can be reduced to one, or possibly two, days through the use of the tools developed.

In some cases, studies are currently contracted out to third-party consultants. It is expected that the increase in internal productivity will mean that these external costs can be reduced.

Ofgem has recently introduced a new standard licence condition (formerly known as SLC 4F but now known as SLC15) with obligations to meet target response rates and to audit and report on achievements each year. These standards/measures can be better managed via a deployment of the Netmap design/planning environment.

There are further incremental benefits that arise from the provision of a study file management system in Netmap. Studies can be more easily tracked, shared and retrieved at a later date.

The project has also demonstrated the potential benefits of an integrated GIS and analysis engine solution for answering DG connection requests, and its applicability to more general HV network planning and design.

The way forward is based on the current availability of vectorised data in



	Netmap for SPN. This provides a suitable platform for the development and implementation of the DG connection tools at SPN, prior to roll-out in EPN and LPN which will follow the completion of network digitisation in those regions.				
Project Progress March 2008	 During the project. a three-stage approach was followed: Requirements workshop; Initial development phase followed by a workshop (Iteration 1); and Second development phase followed by a final workshop (Iteration 2). The project team consisted of staff from EDF Energy Networks, GE Energy and Realworld who collaborated to ensure that the project included 'domain expertise' (EDF Energy Networks and GE Energy), business analyst and software programmers (Realworld) as well as project control (EDF Energy Networks, Realworld and GE Energy). The project included two iterations, enabling the EDF Energy Networks team to see an intermediate solution (Iteration 1) and reprioritise the 				
	requirements for the Iteration 2 system development. The final summary report was produced in November 2007. The recommendations are being addressed.				
Collaborative Partners					
R&D Provider	GE Energy Realworld (GE Energy's software delivery partner)				



3.2 GenAVC Assessment Tool

3.2 GenAVC Assessment Tool							
Description of Completed Project	GenAVC has been developed by Econnect Ventures Ltd to manage voltage rise issues associated with the connection of distributed generation (DG) into 11kV networks. This system had achieved satisfactory operation in a trial at Martham Primary substation. The trial demonstrated that principles of voltage control could be applied in order to reduce the target busbar voltage and minimise network constraints. At Horton Quarry, a landfill gas generator experiences nuisance trips during times of low demand. This project proposed to produce a generic tool to assess the benefits of the GenAVC solution. A comparison of the output of this assessment tool, with traditional methods of solving voltage rise issues, was carried out. The tool showed that GenAVC was a solution, and a commercial grade GenAVC was installed at Steyning primary: To validate the management of the voltage rise issues; Avoid the occasional disconnections of the generator; and Demonstrate that GenAVC provides the least-cost connection for DG when additional generation capacity is sought.						
Expenditure for		EP	N	LPN		SPN	
financial year	External	-	9,886	£0		£41,153	
,	Internal		5,512	£0		f 7,991	
	Total		5,398	£0		£49,144	
	The costs have be distributed generated			proportion t	o the am	ount of connected	
Expenditure in	External	£2	8,900				
previous (IFI) financial	Internal	£1	4,027				
years	Total	£4	2,927				
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 315,000 This project is complete.						
Technological area and/or issue addressed by project	A generic assessment tool to assess the benefits of the GenAVC solution.						
		Proj		Project Re	sidual	Overall Project	
Type(s) of innovation involved	Incremental Ben		efits Rating	Risk		Score	
Expected Timescale to adoption	Year 2008 Duration of benefit once achieved 20 years					rs	
Probability of Success	Delivering bene	Project NPV (Present Benefits – Present Costs) x Probability of Success F 290k					



Benefits Achieved	 The project delivered: An assessment tool that is able to assess whether voltage rise issues, associated with additional generation, can be overcome by installing GenAVC; A cost efficient connection for Horton Quarry allowing additional generation to be installed; and Nuisance trips at times of high voltage are avoided by the generator.
Project Progress March 2008	The GenAVC Assessment tool was developed by Econnect Ventures Ltd. Using this tool, EDF Energy Networks carried out an assessment for Horton Quarry to determine the suitability of GenAVC as a voltage control solution. The results showed that a GenAVC controller could be offered as a connection solution. A GenAVC controller was installed and commissioned to verify the results of the assessment tool. Horton Quarry has installed additional plant and is generating power onto the Steyning network without high volts causing nuisance trips. The Registered Power Zone at Steyning Primary has had additional generation connected without the need for traditional network reinforcement. See section 5.
Collaborative Partners	
R&D Provider	Econnect Ventures Ltd



3.3 Battery Asset Management

	Management					
Description of Completed Project	This project developed a range of innovative, sustainable, low power localised air conditioning that can be applied to sensitive pieces of equipment – in this instance, RTU batteries in distribution substations. These batteries form the power source for automatic remote control equipment in the network and are subject to thermal degradation which leads to CIs and CMLs on the network. The successful implementation of the concept in RTUs has led to the introduction of the concept for other applications such as: • Battery cabinets in substations; • Auto reclosers (e.g. the NULEC); and • Any other device which uses batteries and could be exposed to high temperatures.					
Expenditure for		EPI	V	LPN		SPN
financial year	External		£47,49	7	£55,808	£15,436
,	Internal		£6,16	1	£7,240	
	Total		£53,65		£63,048	
	The costs have been allocated in proportion to the number of remote terminal units.					
Expenditure in	External	£14	45,543			
previous (IFI) financial	Internal	£ 1	17,547			
years	Total		63,090			
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 300,000 This project is complete.					
Technological area and/or issue addressed by project	Extending the life of batteries by creating a cool 'thermal zone' in hot basement substations.					
			Project	Project Re	esidual	Overall Project
Type(s) of innovation	Significant Ber		Benefits Rating Risl		k	Score
involved	2.0					
Expected Timescale to adoption	During 2008	Duration of benefit once achieved 20 years				S
Probability of Success	Delivering benef	its	Project NPV (Present Benefits – Present Costs) x Probability of Success f150k			



Benefits Achieved	The device has been installed for the last six months in an extended 50 site trial in London, where batteries were failing frequently. This trial successfully demonstrated the effectiveness of the equipment in maintaining batteries at lower than 20°C, in ambient temperatures of up to 45°C. It also ensured that all engineering constraints have been addressed, that the equipment fits in most sites, is easy to install and interfaces seamlessly with existing RTU equipment. Cool 'thermal zones' do extend the life of batteries in hot substations and have improved the reliability of remote control switching and automatic restoration of customer supplies.
	A smaller RTU battery device has also been trialled in a pavement mounted cubicle where a battery is used to improve the communications of a fluid-filled cable pressure monitoring system.
	The extended trial in the 50 London substations has met thermal specifications, has been developed to satisfy engineering requirements and is ready for deployment.
Project Progress	The equipment has already been with no difficulty by over 10 different installers, following a 60 minute classroom training session.
March 2008	One of the sites chosen for the trial is Lancaster Gate Hotel, effectively creating a cool 'thermal zone' in this hot substation. In parallel, the passive cooling of "City Centre Substations" is providing thermal protection for the remaining equipment without the use of large "forced convection" or "vapour compression" air conditioning systems.
Collaborative Partners	Central Networks and ScottishPower Energy Networks
R&D Provider	4Energy



3.4 Transformer Damping

5.4 Hallstoffliel D	This project sets	out t	o determine	methods to	reduce n	oise nuisance	
Description of project	resulting from v	ibratio	ns due to 10	00Hz.			
Expenditure for		EPI	V	LPN		SPN	
financial year	External		£16,403			£10,819	
	Internal	£2,415			£1,130	£1,593	
	Total	£18,818				£12,412	
		its have been allocated in proportion to the number of greed distribution transformers.					
Expenditure in	External	£8	,625				
previous (IFI) financial	Internal	£	672				
years	Total	£9	,297				
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 50,000	Projected 2008/09 External £ 0 costs for Internal £ 0 EDF Energy Networks Total £ 0			£0		
Technological area and/or issue addressed by project	Methods to reduinstallation.	Methods to reduce sound radiation from an electrical transformer installation.					
Type(s) of innovation involved	Significant		Project Project Re Benefits Rating Risk			Overall Project Score	
Expected Timescale to adoption	Year 2010		Duration of benefit once achieved			20 years	
Probability of Success	25%		Project NPV (Present Benefits – Present Costs) x Probability of Success				
Benefits Achieved	The project is completed and a report has been issued describing methods for future noise and vibration damping systems. A future project is proposed to demonstrate these suggested systems.						
Project Progress March 2008	The research suggested that there could be a positive expectation that the noise level and vibration from distribution transformers could be reduced by the use of novel systems as well as by the use of appropriate anti-vibration pads installed in the correct position.						
R&D Provider	University of So	University of Southampton					



3.5 Evaluation of the Characteristics of Alternative Oils for Retro-Filling Power Transformers and for Use in New Transformers

ioi ketio-rittii	ig Power Transi							
	This project assessed various alternative materials that could be used as							
Description of project	the insulating medium of power transformers undertook electrical tests							
	on insulation materials and attempted to verify the claimed adva							
Expenditure for		EPN LPN				SPN		
financial year	External		£2,15	8	£0	£0		
	Internal		£8,87	0	£0	£0		
	Total		£11,02	8	£0	£0		
	The costs have been allocated to EPN as the alternative oil transformer							
	will be trialled in the EPN licence area.							
Expenditure in	External £19,041							
previous (IFI) financial	Internal	£ 2	£ 2,797					
years	Total	£2	£21,838					
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 350,000		Projected 2 costs for EDF Energy		External £20,000 Internal £ 1,900 Total £21,900			
Technological area and/or issue addressed by project	Evaluation of the characteristics of alternative oils for retro-filling power transformers and for use in new transformers.							
- () ()			Project Project		esidual	Overall Project		
Type(s) of innovation		Ben	efits Rating	Ris	k	Score		
involved	substitution							
Expected Benefits of Project	The benefits of using alternative oils in transformers are based around two main points: • Safety/environment; and • Lifetime ageing performance.							
Expected Timescale to adoption	Year 2014	Year 2014 Duration of benefit once achieved 20 years						
Probability of Success	Project NPV (Prese Benefits – Present Costs) x Probability of Success			Present obability	£ 50,000			
Benefits Achieved	The project has ended and a report has been produced. The report concluded that further work was required and a second phase is planned							
Project Progress March 2008	The second phase has been defined, including the goals to be achieved. Areas of uncertainty uncovered during the first phase are to be reexamined and additional areas, such as the performance of the fluids with large oil gaps, are to be analysed.							
Collaborative Partners		Areva T&D, M&I Materials, National Grid, Electricity North West, ScottishPower Energy Networks.						
R&D Provider	University of Manchester							



3.6 Domestic Cut-Out Temp Indicators

Description of Completed Project	This project investigated the use of low cost, thermally sensitive labels to give a meter inspector an indication whether a domestic cut-out has been overheating and further investigation is required.						
Expenditure for		EPN LPI				SPN	
financial year	External		£3,56		£2,268	£2,268	
,	Internal		£1,50		£955	£955	
	Total		£5,06	1	£3,223	£3,223	
	The costs have be customers.		ber of connected				
Expenditure in	External	£0					
previous (IFI) financial	Internal	£43	31				
years	Total	£4:	31				
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 10,000						
Technological area and/or issue addressed by project	Thermal monitoring of domestic cut-outs.						
Type(s) of innovation involved	Incremental				esidual Overall Proje k Score		
Expected Timescale to adoption	During 2008	Duration of bonce achieve			1 20 years		
Probability of Success	Successful Project NPV (Present Benefits – Present Costs) x Probability of Success £2.28				£2.2M		
Benefits Achieved	 This project has delivered: An early warning system for detecting thermal problems in cutouts due to customers' load; A method to help prevent fire damage to customers' premises; and Improved customer safety. The deployment of the "clock indicator" type temperature sensors to all domestic cut-outs throughout the EDF Energy Networks will prove most challenging. 						



Project Progress March 2008	Thermal rise tests were carried out on "Single Service Supplies" and "Looped Services" configurations. One of the pinching screws was undone from the chosen cut-outs, to simulate a bad resistance contact and to cause subsequent temperature increase, (as would be seen in this type of failure mode). In both configurations, the current was increased progressively after undoing the pinching screws in order to accelerate the increase in temperature of the cut-outs. This allowed the temperature indicator's response to be monitored. It was shown that the most appropriate temperature sensors were the circular type (clock indicators, range 2 – RS code: 285-970). The best locations were determined to be the top and bottom of the fuse carrier. A range of temperature from 60°C to 82°C appears to be most appropriate for this application.
Collaborative Partners	
R&D Provider	Tyco Electronics, Witham



3.7 Power Factor Analysis

3.7 Power Factor A	<u> Inalysis</u>							
Description of project	This project was prompted by the observation that a correlation exists between temperature and power factor. Whilst some of this may be attributable to air conditioning load in urban areas, this cannot be said of typical, rural locations. This project examined the sources of such reactive loads to better understand the reactive compensation needs of the network. This may lead to installation of power factor correction plant (or otherwise) to increase the efficiency of the distribution network.							
Expenditure for	EPN LPN SPN							
financial year	External £0 £0 £0							
,	Internal		£338		139	£186		
	Total		£338		139	£186		
	The costs have to distributed general		llocated in p			ount of connected		
Expenditure in	External	£0						
previous (IFI) financial	Internal	£1,	534					
years	Total	£1,	534					
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 27,500 This project is complete.							
Technological area and/or issue addressed by project	Reactive compensation needs of distribution networks							
Type(s) of innovation involved	Incremental		Project Re Benefits Rating Risk			Overall Project Score		
Expected Benefits of Project	The expected benefits are: • An improvement of power factor from 0.8 to unity can provide alternative to increases in transformer size and cable capacity; and • A reduction in distribution plant losses.							
Expected Timescale to adoption	Year 2014	Duration of benefit once achieved			20 yeai	20 years		
Probability of Success	25%		Project NPV (Pre Benefits – Prese Costs) x Probab of Success		£200k			
Benefits Achieved	The project results show that there is a need to carry out further work to identify which methods are most appropriate to improve power factor measured on a distribution network.							



This work looked at computer power supplies which are a major source of low power factor (In 2006, 65% of households owned a PC and this number is growing rapidly).
Of the total US electricity consumption, about 1% was attributable to domestic IT equipment in 2005. Again the PC has the largest contribution to the demand total, requiring around 50% of the electricity

domestic IT equipment in 2005. Again the PC has the largest contribution to the demand total, requiring around 50% of the electricity. The most surprising discovery is that the majority of the residential PC's energy consumption (53%) occurs when it is active but not in use. These statistics are of importance because in a PC, the power factor can vary from 0.5 with no power factor correction, to between 0.9-1.0 with active power factor correction. Passive correction increases the power factor to between 0.7-0.8. Studies have shown that poor power factor affects the efficiency of the PC and perhaps more surprisingly experiments have shown that loading affects the power factor. This is of great concern considering 53% of the energy is spent whilst not in use.

Such an experiment was performed and it was discovered that from about 25% load, the power factor approaches its maximum value.

Between 25% and full load, the power factor seemed to vary by between 5 and 10% of its maximum value.

Project Progress March 2008

Data analysis of recorded substation power factors was also performed as part of this work. The power factor and temperature correlation coefficients were calculated for each station and the results indicated a range of correlations from moderate to very strong. Best fit lines were calculated and it was found that second order polynomial equations best described the relationship. When the results of all the substations were combined, the correlation was much weaker because the characteristic curves of each station were different.

Current and temperature correlation was investigated and found to be weaker than power factor and temperature. The relationship was best described by a second order polynomial equation. The most interesting result was that the Leicester Square substation showed a trend of increasing current with temperature. This was in contrast with the negative correlation results of all the other substations.

The average weekday power factor and current profiles were plotted for all stations excluding Leicester Square. In all cases a dip in power factor was visible during working hours which coincided with an increase in current. The summer and winter profiles of Bourn substation were also examined and contrasts discussed.

Collaborative Partners

R&D Provider

Cambridge University



3.8 Primary SCADA Communications IP Upgrade

3.6 Filliary SCADI						
Description of Completed Project	This project demonstrated that IP protocols can be used securely to provide the necessary primary substation SCADA communications used in distribution networks.					
Expenditure in	External £202,262					
previous (IFI) financial						
years	Total £253,125					
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 253,125 This project is complete.					
Technological area and/or issue addressed by project	The use of IP to provide Primary SCADA communications (satellite) and to control the changeover to a back-up communications system (GPRS).					
Type(s) of innovation involved	Radical		Project Project Resi efits Rating Risk			Overall Project Score
Expected Timescale to adoption	Year 2008		Duration of benefit once achieved 20 years			rs
Probability of Success	25%		Project NPV (Present Benefits – Present Costs) x Probability of Success			
Benefits Achieved	Benefits have been realised for the SPN Primary SCADA system. The new IP communications solution went live in September 2007. Availability of the RTU is now typically 99.9%. With the capability to configure real-time use of either Main or GPRS back-up communications, service can be maintained without the requirement for immediate, on site intervention. The whole system is also mains independent and will therefore function during a Black Start. The previous system was subject to outages caused by faults in the BT network. With this new system communications can be restored remotely within minutes. The installation of this communications system facilitated the cut-over from the Schneider NMS system to the GE Energy ENMAC control system.					
Project Progress March 2008	All Primary RTUs in SPN are connected to the new ENMAC control system. 385 RTUs via satellite VSATs and 15 RTUs use terrestrial broadband due to problems obtaining satellite line of sight (LOS). These LOS issues will be pursued over the coming months and VSATs will be installed wherever possible. Both satellite and terrestrial broadband have a GPRS back up system. The satellite hub is located at the EDF Energy Networks' control centre at					



	Fore Hamlet in Ipswich. This hub has UPS and generator back-up power supplies but in the event of a hardware catastrophe or planned maintenance there is a dedicated EDF Energy Networks' disaster recovery hub at the Satlynx facility in Germany (connected via 99.999% available C&W redundant communications circuits) which can be brought into action within two hours, although in tests the operation has taken approximately 20 minutes. In addition, the GPRS back up network can still be used during outages of the UK satellite Hub.
Collaborative Partners	
R&D Provider	Satlynx



4. Individual IFI Projects

(Projects ordered by expenditure)

- Online Condition Monitoring
- Vulnerable Customer UPS
- Bankside Heat transfer
- Improved Fluid-Filled Cable Leak Location System
- AURA NMS
- Transformer Design for FR3
- Vacuum Tap Changer
- Vegetation Management
- Distribution System State Estimation
- DG Connection Planner
- Flexible Electricity Networks to Integrate the expected 'energy evolution' FENIX
- Optimal Transformer Utilisation Model
- Impacts of Climate Change on the UK Energy Industry
- RTU Local Display Facility
- Composite Insulators
- OHL Electrical Performance
- Transformer Damping
- Application of Storage and DSM
- Network Risk Management
- Supergen V Amperes
- Wood pole disposal
- LV underground cable fault management
- 33kV Voltage Control
- Collaborative ENA R&D programme
- Activ Project
- · Recycling Excavated Material
- Grid Transformer Monitoring
- Earthing Information system
- Electrical Energy Harvesting from Vibrations
- Transformer Temperature Fibre Optic Monitoring
- Power Networks Research Academy
- Supergen 1 FlexNet

EATL Strategic Technology Programme

- STP Module 2 : Overhead Network
- STP Module 3 : Cable Networks
- STP Module 4 : Substations
- STP Module 5 : Networks for Distributed Energy Resources

As most DNOs subscribe to all four Strategic Technology Programme Modules, these four reports have been written by EA Technology Ltd to provide consistent reporting.



4.1 On-line condition monitoring

4.1 On-line condition	on monitoring							
Description of project	The use of partial discharge measurement has been a well known method of checking the condition of electrical insulation. Over the past nine years, EDF Energy Networks has been actively involved in the development of online partial discharge monitoring and mapping techniques. Opportunities to improve the existing technology have been identified. This project has taken the laboratory into the distribution network to monitor underground cables and switchgear.							
	unuerground captes and switchigear.							
Expenditure for financial	EPN LPN SPN							
year	External	£24,423	3 :	£626,863	£162,822			
	Internal	£2,324	£59,642		£15,492			
	Total	£26,747	7	£686,505	£178,314			
	The costs have be	en allocated in prop	ortion to th	ie length o	f installed HV			
	cable that is direct	tly earthed.						
F 19 '	External	£892,032						
Expenditure in previous	Internal	£ 85,102						
(IFI) financial years	Total	£977,134						
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 2M	costs for	Projected 2008/09 costs for EDF Energy Networks		£ 500k £ 43k £ 543k			
Technological area and/or issue addressed by project	 The issues being investigated by the project are: Online fault detection and location; Pre-emptive fault repairs; Cable replacement and maintenance strategy; and Quality of supply improvement. 							
Type(s) of innovation involved	Radical	Project Benefits Project R Radical Rating Ris			Overall Project Score			
Expected Benefits of Project	 The expected benefits include: Ability to target the replacement of cable; and Ability to identify faults (cable and switchgear) before they occur, carry out a repair and reduce the number of customer interruptions. 							
Expected Timescale to adoption	Year 2010	Duration of l		20 years				
Probability of Success	75%	Benefits – P	Probability of 4.8M					
Potential for achieving expected benefits	Although there is still much research work to be done in terms of understanding failure modes, the programme is progressing according to plan and benefits are being delivered.							



Project Progress	The number of feeders monitored across the EDF Energy Networks' area has increased to approximately 1000 (40 substations equipped). Sensors used to monitor both cables and switchgear include current transformers, airborne acoustics and capacitive couplers. The following stages have been completed: • Hardware development - permanent and portable versions of the Advanced Substation Monitor (ASM), Partial Discharge (PD) location/mapping equipment; • Cable analysis health index software - an analysis tool that combines cable information (length, date of installation, etc.) with condition information to inform asset management decisions; • Installation of equipment - the data collected is being used to build an extensive database of network events (partial discharges, noise, etc.) that can be exploited for research purposes; and • Development of a web-based cable sample analysis database. The technology is delivering benefits now (remote monitoring of substations, detection and location of incipient defect). Several cable faults have been identified and are awaiting cable replacements. However, much work is left to do in order to fully benefit from the on-line condition monitoring techniques.
· -	do in order to fully benefit from the on-line condition monitoring techniques.
March 2008	The following stages are surrently in progress.
	 Research is currently taking place in the following areas: time to failure prediction, noise reduction, partial discharge trend analysis and recognition, defect type classification, cable degradation process analysis, failure modes and improved sensor development; Complete solution validation: desk study, spot testing, monitoring, mapping and repairs; Integration with network control system (demonstration); Integration of network information to manage risks (cable type, number of customers, automation, etc.); and Development of ring main unit mini PD monitor to extend the detection range of the system. Selected list of publications: Transmission and Distribution World article (Oct 2007): "EDF Energy identifies high-risk cable sections", Matthieu Michel; and Journal publication: "Second Generation Wavelet Transform in PD Measurement and De-noising". IEEE Transactions on Dielectrics and
	Electrical Insulation. December 2007, Vol. 14, No.6.
Collaborative Partners	
R&D Providers	IPEC Ltd, ERA Technology, EDF R&D (France), PPA Energy, IPEC HV and Glasgow Caledonian University.



4.2 Vulnerable Customers UPS

4.2 Vullierable Custo						
Description of project	This project aims to develop solutions that provide continuity of electrical power to vulnerable customers - those who are classified as needing a combination of lights, appliances, electronics and medical equipment to remain operational in the event of a power failure. Ceres Power has developed the capabilities and specialist expertise to deliver a fuel cell solution.					
Expenditure for		EPN	N	LPN		SPN
financial year	External		£197,89	2 £	125,931	£125,931
,	Internal		£19,04		£12,119	
	Total		£216,93	5 £	138,050	£138,050
	The costs have be in each licence a		llocated in p	roportion to	o the num	nber of customers
Expenditure in	External	£0				
previous (IFI) financial	Internal	£5,	390			
years	Total	£5.	390			
Total Project Costs (Collaborative + external + EDF Energy Networks)	Frojected 2008/09 costs for EDF Energy Networks			External £ 179,000 Internal £ 5,000 Total £ 184,000		
Technological area and/or issue addressed by project	Hybrid fuel cell – battery for customers medically dependent on electricity.					
			Project Re		esidual	Overall Project
Type(s) of innovation involved	Radical	Bene	efits Rating	Risl	<	Score
Expected Benefits of Project	The expected benefits include a means of reassuring vulnerable customers that the effects of a power cut are reduced.					
Expected Timescale to adoption	Year 2012 Duration of ben once achieved				20 years	S
Probability of Success	25%		Project NPV (Present Benefits – Present Costs) x Probability of Success		£ 200,0	00



Potential for achieving expected benefits	At the end of the project, in December 2008, we expect a prototype to be delivered. The prototype/engineering demonstrator which will be delivered at the end of the project comprises two parts: • The internal battery component that provides the continuous supply of energy following an interruption for a period of approximately two hours, dependent on energy usage; and • The external fuel cell module that provides the extended supply of energy dependent on the size of the gas bottle. During the development, calculations showed that the fuel cell module could not be stored indoors as oxygen in a room used by the module is depleted in a number of hours.
Project Progress March 2008	The following phases have been completed: • Phase 1 feasibility study; and • Phase 2 battery UPS. The current phase 3 fuel cell UPS is on target with the following tasks completed: • Design of fuel cell UPS; • Test of key fuel cell module components; and • Build of core fuel cell module. In addition, concept designs have been generated to show what a final customer product would look like.
Collaborative Partners	
R&D Provider	CeresPower



4.3 Bankside Heat Transfer

4.3 Bankside Heat Tr	anster					
Description of project	Substation transformers produce waste heat which is usually lost to the environment. The re-planted substation at Bankside, adjacent to the Tate Modern, will use transformers with water cooled heat exchangers. It is proposed that the waste heat from the transformers will be used by the Tate Modern to assist with its building heating process. This will benefit EDF Energy Networks, as less energy will need to be expended within cooler fans at the substation, and lower maintenance and replacement of cooler fans will be incurred.					
Expenditure for		EPI	N	LPN		SPN
financial year	External		£) £	397,192	f0
	Internal		£	0	£44,201	f0
	Total		£		441,393	£0
	The costs have I Bankside subst			PN as the t	rial is beir	ng carried out at
Expenditure in	External	£4	6,477			
previous (IFI) financial	Internal		8,743			
years	Total		5,220			
Total Project Costs (Collaborative + external + EDF Energy Networks)	£700,500 Projected 2008/09 costs for EDF Energy Networks			External Internal Total	£250,000 £ 4,500 £254,500	
Technological area and/or issue addressed by project	Environmentally friendly cooling of transformers					
			Project	Project Re	esidual	Overall Project
Type(s) of innovation involved	Significant	Ben	efits Rating	Risl	k	Score
Expected Benefits of Project	The expected benefits include: • Waste heat will be used by a third party; • Fewer maintenance interventions for cooling; • Less auxiliary electricity consumption; and • Lower noise level from coolers.					
Expected Timescale to adoption	Year 2010	Duration of benefit once achieved			20 years	5
Probability of Success	75%		Project NPV (Present Benefits – Present Costs) x Probability of Success		£200k	



Potential for achieving expected benefits	The analysis of the system and discussions with the Tate suggest that a quantity of heat will be taken by the existing Tate Modern - the engineering for the project does not give any cause for concern that the system will provide heat. The next phase of the Tate Modern project will be designed to extract additional heat from the system.
Project Progress March 2008	The mechanical hardware has been installed, including four transformers, pipework, fans and pumps. The secondary heat exchanger system is in the process of final design and will be installed in July 2008. The control systems have been designed and are in the process of manufacture.
Collaborative Partners	
R&D Provider	Wilson Transformers



4.4 Improved Fluid-Filled Cable Leak Location System

Description of project	This project is to evaluate the suitability of using PFT tracer technology to determine fluid-filled cable leak locations and reduce the number of excavations required. The technology was originally developed by NASA.					
Expenditure for		EPI	V	LPN		SPN
financial year	External		£126,34	8 £	126,348	£108,299
	Internal		£13,83	4	£13,834	£11,858
	Total		£140,18	2 £	140,182	£120,157
	The costs have be fluid-filled cable		llocated in p	roportion t	o the exis	ting lengths of
Expenditure in	External	£48	80,306			
previous (IFI) financial	Internal	£	84,111			
years	Total		64,417			
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 1.1M	Projected 2008/09 External £90,000				£15,000
Technological area and/or issue addressed by project	PFT tracer technology to determine cable leak location and reduce the number of excavations required. Develop and field trial methods of mixing PFT compounds into cable fluid.					
Type(s) of innovation involved	Radical	Project Proje Benefits Rating		Project Re Ris		Overall Project Score
Expected Benefits of Project	 The expected benefits include: Faster and more accurate oil leak locations; Operational cost savings with fewer and smaller excavations; Positive impact on environment; Improved relationship with Environmental Agency through demonstration of a pro-active and world's best practice leak location techniques; Reduction in Network Risk because the process can be used without switching out the leaking circuit; and Better Asset Management of fluid-filled cable condition monitoring associated with the leak location process. 					
Expected Timescale to adoption	Year 2010	Duration of benefit once achieved			20 years	S
Probability of Success	75%		Project NPV (Pre Benefits – Prese Costs) x Probabi of Success		£5M	



Potential for achieving expected benefits	Assuming the system can be successfully introduced into Customer Operations, there is a very high probability of achieving the expected benefits, especially when the cost of carrying out the work is under continuous inflationary pressure.
Project Progress March 2008	Improvements have been made to the sensitivity of the detection equipment supplied by Femtotrace. Further work is still required to achieve the sensitivity required for carrying out true "drive by" detection of leaking fluid-filled cables. Progress has also been made on the methods of introducing PFT tagged fluid into leaking fluid-filled cable circuits, with the design and procurement of bespoke mixing and tagging equipment from two external suppliers.
Collaborative Partners	Con Edison
R&D Provider	Femtotrace Inc. Prochem H&R Chempharm Ltd



4.5 AURA NMS – Autonomous Regional Active Network Management System

7.5 7.6 1.7 111115	Autonomous Re				•		
Description of project	 The objective of this project is to develop a distributed control system to deliver: Realtime automated reconfiguration, initially to a regional network of up to four primary substations; Economically, efficiently and effectively integrate large amounts of small scale distributed generation, taking into account legacy infrastructure and renewal programmes; and Network optimisation, taking into account DG and electrical energy storage. 						
Expenditure for		EPN	LPN		SPN		
financial year	External	£158,4	448	£62,719	£108,933		
	Internal	£15,5	523	£6,145	£10,672		
	Total	£173,9	971	£68,864	£119,605		
	The costs have be connected.	en allocated in p	roportion t	o the amount of	distributed generation		
Expenditure in	External	£1,265,520					
previous (IFI) financial	Internal	f 111,371					
years	Total	£1,376,891					
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 5,760,000	Projected 2008/09 External £ 800,000 costs for Internal £ 200,000 Total £1,000,000					
Technological area and/or issue addressed by project	 The scoping and development of three major areas: DG and demand side management to facilitate the connection of DG to the network; Develop a controller that will monitor electricity networks, isolate faults quickly and allow DG to remain connected and operating; and Optimise the network with respect to losses. 						
Type(s) of innovation involved	Radical	Project Benefits Rating	Project Re Ris	1 ()\/	erall Project Score		
Expected Benefits of Project	The expected benefits include: • Maximisation of the contribution of DG to the electricity network; • Reduction in carbon emissions and help towards the UK government's climate change targets; • Reduction in network losses by having the source of generation close to the load; • Improvement in quality and security of supply; • Improvement in network resilience; and • Reducing the current market failures to increase network capacity for DG.						
Expected Timescale to adoption	Year 2015	Duration of once achie		20 years			



			T			
Probability of Success	25%	Project NPV (Present Benefits – Present Costs) x Probability of Success	This project is expected to deliver benefits in the order of millions of pounds. As part of the project the real value will be calculated.			
Potential for achieving expected benefits	The software development has, from the start, targeted a realistic substation hardware platform. It has been written using high level tools with a view to easy integration with other elements of substation automation, and an extensive and progressive system of testing has been specified. Various control functions have been written as modules that can stand alone when required. Assessment of communication opportunities and limitations has run in parallel with control development. There will be meaningful tests, completed by the end of the research phase, which will enable a full appraisal to be made and a decision to be taken on what pilot deployment could be undertaken. There is strong reason to believe that a substantial fraction of the technology will go on to have a meaningful deployment.					
Project Progress March 2008	case study network a generation, instrument work package 0 has of the network and the factor outages on various feather be supplemented by design this have been have been cross-refer work package 1 has factor be developed and concontrol, thermal consulgorithms on the targether data models and designed. The system	reas identified and descriptation and communicated developed a basic real-tificity steps taken to integrate to subject the controller reders that exercise the care communications emulation undertaken. The electric renced in readiness for infinalised a functional specification and sugget hardware have been the communications with	me (quasi-steady state) simulation of rate this with the controller hardware. to load and generation profiles and control functions. This test facility is to ator and the preparatory studies to rical and communication networks integrating these two emulations. ecification of the control functions to of core functions within voltage upply restoration. The first trials of conducted. The software to manage h network equipment has been functions has been considered and			
	networking within the communication patter communications have carried out. The mod generic simulation. Tapproach against the parameters to the generate of adding not work package 3 studing oin reducing custom is in development and	e SCADA system, as well rns experienced during see been identified, and melling is in the form of a the specific network simple existing communication existing communication ew functionality to the network for an improved the interruptions. Softward further analysis of customers	on of communication equipment and as obtaining information on system operation. Constraints on odelling of the systems has been specific network simulation, and a ulation has been used to verify the as network, and is to be used to supply unication technologies with the etwork have been explored. automation restoration scheme could are to illustrate this, with case studies, comer minutes lost is under way.			



	capacity for distributed generation has been revisited and applied to one of the case study areas for a detailed assessment of additional capacity realised. Work is in progress to build a cost benefit assessment.
Collaborative Partners	This is a Strategic Partnership between the EPSRC, ABB, EDF Energy Networks and ScottishPower Energy Networks.
R&D Providers	Aura NMS is led by Imperial College London and supported by the Universities of Bath, Cardiff, Durham, Edinburgh, Loughborough, Manchester and Strathclyde.



4.6 Transformer Design for FR3

Description of project	This project will design and build a transformer that will be filled with FR3 vegetable oil manufactured by Coopers Power Systems. This requires considerable design work and evaluation of the various components used in the manufacture of the transformer. Techniques to manage a clean up, should a spill of FR3 occur, will also be developed.					
Expenditure for		EPN	١	LPN		SPN
financial year	External		£194,21	0	£0	£0
	Internal		£18,69	7	£0	£0
	Total		£212,90	7	£0	£0
	The costs have be installed in the E			EPN as this	transform	er will be
Expenditure in	External	£88	32,300			
previous (IFI) financial	Internal	£ 7	77,324			
years	Total		59,624			
Total Project Costs (Collaborative + external + EDF Energy Networks)	Projected 2008/09 External £ 0 f 1.2M costs for Internal £ 0 EDF Energy Networks Total £ 0				£0	
Technological area and/or issue addressed by project	 Evaluate the possibility of the use of FR3 as the initial fluid to be used in a transformer with 132kV as the primary voltage; Assess the reaction of the components used in the manufacture of a transformer with the fluid; and In particular, assess the fluid use in the tap-changer and other components. The transformer will be equipped with a comprehensive monitoring system to enable data to be obtained regarding the performance of the transformer and compare with another similar transformer filled with mineral oil. 					
Type(s) of innovation involved	Technological substitution		Project efits Rating	Project Re Risl		Overall Project Score
Expected Benefits of Project	The expected benefits include: • Longer life of the transformer; • Lower disposal costs for the fluid; • Higher rating from the same transformer; and • The fluid is highly biodegradable.					
Expected Timescale to adoption	Year 2009		Duration of once achie		20 years	S
Probability of Success	75%	Project NPV (Benefits – Pr Costs) x Prob of Success		Present obability	£ 1.5M	



Potential for achieving expected benefits	The materials tests and research on the characteristic of the fluid suggest that the transformers will operate satisfactorily.
Project Progress March 2008	A 33/11kV transformer has been in service for several months in Guildford and is giving satisfactory service. The fluid characteristics will be monitored as well as the winding temperatures. A 132/33kV transformer has been installed in Luton and is being commissioned. It is expected to go live by the end of August 2008.
Collaborative Partners	
R&D Provider	Areva T&D University of Manchester Coopers Power Systems



4.7 Vacuum Tap Changer

4.7 Vacuum Tap Chai	1ger								
Description of project	The project will develop a vacuum bolt-on type tap changer based on the design of the ATL - AT type. A conceptual design is already in place. It will include the design, manufacture, KEMA type testing and fitting of a prototype on a new transformer for field service. The tap changer will be based on the AT type design; a proven reliable product with many advantages over the in-tank type. In essence, the existing DNO transformer design should remain unchanged. It is also envisaged the tap changer could be retro-fitted to old transformers.								
Expenditure for		EPN LPN SPN							
financial year	External		£93,840)	£38,640	£51,520			
	Internal		£9,710)	£3,998	£5,331			
	Total		£103,550)	£42,638	£56,851			
	The costs have b	een a	llocated in p	roportion to	o the num	ber of primary			
	transformers su	oplyin	g the distrib	ution netwo	rk.				
Expenditure in previous (IFI) financial years	This project was not reported in the 06/07 activity report.								
Total Project Costs (Collaborative + external + EDF Energy Networks)	£870,000		Projected 2008/09 costs for EDF Energy Networks			f 150,000 f 15,000 f 165,000			
Technological area and/or issue addressed by project	Bolt-on type vacuum insulated on-load tap changer for a power transformer.								
Type(s) of innovation involved	Technological substitution		Project efits Rating	Project Re Risi		Overall Project Score			
Expected Benefits of Project	The expected benefits include the following: It is maintenance free; and Provides an alternative to in-tank type tap changers.								
Expected Timescale to adoption	Year 2014		Duration of benefit once achieved		20 years				
Probability of Success	25%	Project NPV (Present Benefits – Present Costs) x Probability of Success F100k							
Potential for achieving expected benefits	The work so far using modelling techniques and part prototypes suggests that it will be possible to design and manufacture a "bolt-on" vacuum tap changer.								



Project Progress March 2008	Modelling is ongoing and some part prototypes have been built to examine the action of the mechanism. A number of changes have been made in the light of these tests. It is predicted that a working prototype will be available for testing in the early part of 2009.
Collaborative Partners	
R&D Provider	Brush Transformers



4.8 Vegetation Management

4.8 Vegetation Mana		nnses	to:				
Description of project	 Monitor vegetation growth at 1,650 sites across the UK network; and Develop a software model which will take account of factors such as tree species, bioclimatic area and the effect of climate change, in order to estimate the speed of vegetation growth at different sites. 						
Expenditure for		EPI	N	LPN		SPN	
financial year	External					£48,160	
,	Internal		£13,360		£0	_	
	Total		£137,20		£0	£53,355	
	The costs have be overhead line.	een a	llocated in p	roportion t	o the leng	gth of 11kV	
Expenditure in previous (IFI) financial years	This project was	not re	eported in th	e 06/07 ac	tivity repo	ort.	
Total Project Costs (Collaborative + external + EDF Energy Networks)	Frojected 2008/09 costs for EDF Energy Networks			Externa Internal Total	f 3,000 f 3,000		
Technological area and/or issue addressed by project	Rate of vegetation growth						
Type(s) of innovation involved	Incremental			Project Re Ris		Overall Project Score	
Expected Benefits of Project	The expected benefits include a software tool, that will enable EDF Energy Networks and other DNOs to predict whether areas are high or low growth, and hence allow two-fold savings: In high growth areas, proactive cutting can be carried out, thus reducing the number of outages (by cutting before the vegetation enters the live zone) and cost to DNOs; and Simultaneously, cutting cycles in low growth areas will be extended, resulting in fewer spans being cut each year.						
Expected Timescale to adoption	Year 2011		Duration of benefit once achieved		20 years		
Probability of Success	50%		Project NP\ Benefits - Costs) x Pro	Present	£400k		
Potential for achieving expected benefits		The project is progressing in accordance with the project plan and is expected to deliver the initial results in December 2008.					



Project Progress March 2008	The project is being delivered in line with the project plan. Sample sites have been set up for EDF Energy Networks, National Grid, ScottishPower Energy Networks and Central Networks. Consents to use the sites for research for the next four years have been obtained and the initial measurements have been made.
Collaborative Partners	Electricity North West, ScottishPower Energy Networks, Central Networks and National Grid.
R&D Provider	ADAS



4.9 Distribution System State Estimation

Description of project	To develop prototype algorithms for distribution system state estimation (DSSE), taking into account the greater use of active components in future distribution networks. The effectiveness of the new algorithms will be evaluated using a suitable section of EDF Energy Networks' network model, providing a useful demonstration of the algorithms' ability to facilitate new approaches for the operation and control strategies of future active distribution networks.					
Expenditure for		EPI	N	LPN		SPN
financial year	External		£69,360		£28,560	
,	Internal	f6,599 f2,717 f				
	Total	£75,959 £31,277 £				
	The costs have b	he costs have been allocated in proportion to the number of primary				
	transformers supplying the distribution network.					
Expenditure in	External	£18	34,000			
previous (IFI) financial	Internal £ 14,147					
years	Total £198,147					
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 396,000 costs for Internal £			l f 136,000 l f 10,000 f 146,000		
Technological area and/or issue addressed by project	The overall research streams, to be convill focus on DSS issues.	omple	ted in a coo	rdinated ma	nner. O	
			Project	Project Re	esidual	Overall Project
Type(s) of innovation involved	Radical	Ben	efits Rating	Risl	(Score
Expected Benefits of Project	 Establishing the difference between the investment reinforcement costs associated with traditional, passive network operation based solutions and the costs of the system within the context of an active distribution network operation that uses DSSE. It can be expected that a DSSE will play a similar role to the state estimators used in transmission systems, enabling the release of untapped network capacity and the provision of network services such as fast flow control and voltage support. 					
Expected Timescale to adoption	Year 2009		Duration of once achie		20 year	S



Probability of Success	25%	Project NPV (Present Benefits – Present Costs) x Probability of Success	£800,000				
Potential for achieving expected benefits	It is hoped that the results of this project will be used in the AURA NMS controller. There are also plans to use the outputs in a proposed project to consider network losses. AURA NMS controller will act upon receiving information about the state estimates from the estimator that is being developed in this project. The state estimator will provide information about limit violation and extent of loss across the network, which will enable the AURA decision making engine to reconfigure the network, and control voltage to minimise loss and maximise DG injection without violating limits.						
Project Progress March 2008	The benefit, in terms of having increased DG MW connected from the knowledge of improved state estimate has been demonstrated. There is an established correlation between state estimation accuracy, the number of real-time measurements and the size of generation that can be accommodated. Optimisation-based modelling of pseudo measurements (Loads) is carried out to demonstrate the quality, consistency and performance of the state estimator algorithm. Placement of meters, based on estimation error minimisation through a stochastic optimisation approach, is demonstrated in UKGDS network model. The current work involves developing an algorithm for choosing the most effective measurements and locations in EDF Energy Networks' Hartley and Ninfield 33kV grid substations.						
Collaborative Partners	-						
R&D Provider	Imperial College Lond	Imperial College London					



4.10 DG Connection Planner

4.10 DG Connection I	Planner						
Description of project	This project is to build on the work reported in "Internet Services for Planning Distributed Generation Connections" funded by BERR, to provide DG developers with access to suitable connection locations and estimated connection costs. The system uses an OS map background to allow users to position a proposed generator connection, DNO Long Term Development Statement (LTDS) data to derive suitable connection scenarios and costing information for the provision of budget estimates.						
Expenditure for		EPI	N	LPN		SPN	
financial year	External					£39,897	
,	Internal		£5,52		£22,971 £2,186	£3,796	
	Total		£63,55		£25,157	£43,693	
	The costs have to		llocated in p			unt of connected	
Expenditure in	External		5,908				
previous (IFI) financial	Internal		2,968				
years	Total		-,,, 				
Total Project Costs (Collaborative + external + EDF Energy Networks)	Projected 2008/09 External £ 26,000 Internal £ 3,000 EDF Energy Networks Total £ 29,000				£ 3,000		
Technological area and/or issue addressed by project	Areas where cost-efficient DG connections can be realised; visualisation of connection costs and network capacity; and visualisation of DG activity.						
Type(s) of innovation involved	Incremental		Project efits Rating			Overall Project Score	
Expected Benefits of Project	Areas where the network is likely to be sufficiently robust to support generation connections can be identified by developers prior to making formal contact with the DNO. The DG developer may be prepared to accept a lower accuracy on costs and be more interested in assessing the engineering feasibility. This is likely to be particularly true if the applicant has a number of sites under consideration and wants to eliminate those that are in locations which are going to be difficult to connect. This could reduce the need for significant reinforcement in support of generation connections, by providing visibility of the more suitable locations.						
Expected Timescale to adoption	Year 2011		Duration o		20 years	5	



	T-				
Probability of Success	25%	Project NPV (Present Benefits – Present Costs) x Probability of Success	£ 167,000		
Potential for achieving expected benefits	There is excellent potential for achieving the expected benefits. Cost and capacity maps, that provide an overview of connection opportunities, have been developed for the web portal, demonstrating the feasibility of providing this information through a web-browser. Comments may also be added to the maps for specific areas where there may be connection opportunities or problems. An activity map that provides the DNO with feedback regarding connection activity also shows good potential.				
Project Progress March 2008	Cost and capacity maps have been developed and demonstrated. Activity maps have been demonstrated, although there is still work outstanding to complete the development. The ability to add comments to the map has been demonstrated. An overview map has been developed for primary circuits and substations within the EPN area.				
Collaborative Partners					
R&D Provider	IMASS Ltd and Econnect Ventures Ltd				



4.11 Flexible Electricity Networks to Integrate the eXpected 'energy evolution' FENIX

Description of project	The objective of FENIX is to boost Distributed Energy Resources (DER) by maximising their contribution to the electric power system, through aggregation into Large Scale Virtual Power Plants (LSVPP) and decentralised management. The project is organised in three phases: • Analysis of the DER contribution to the electrical system, assessed in two future scenarios (Northern and Southern) with realistic DER penetration; • Development of a layered communication and control solution validated for a comprehensive set of network use cases, including normal and abnormal operation, as well as recommendations to adapt international power standards; and • Validation through two large field deployments, one focused on domestic CHP aggregation, and the second aggregating large DER in LSVPPs (wind farms, industrial cogeneration), integrated with global network management and markets.						
Expenditure for		EPN LPN SPN					
financial year	External		£38,37		£15,188	£26,380	
,	Internal		£12,25	1	£4,849		
		een a				£34,802 Dunt of connected	
	distributed gene			noportion t	o the anne	Junt of conficeted	
Expenditure in	External	f	980				
previous (IFI) financial	Internal		6,360				
years							
	Total	±1,	7,340	2000/00			
Total Project Costs (Collaborative + external + EDF Energy Networks)	14.7M€		Projected 2 costs for EDF Energy			f 25,000 l f 100,000 f 125,000	
Technological area and/or issue addressed by project	To conceptualise, design and demonstrate a technical architecture and commercial framework that would enable DER based systems to become the solution for a future, cost efficient, secure and sustainable EU electricity supply system.						
Type(s) of innovation involved	Radical		Project Project Residual efits Rating Risk			Overall Project Score	
Expected Benefits of Project	The expected benefits include: • Maximising the contribution of DG to the electricity network; • Reducing carbon emissions and help towards the UK Government's climate change targets; and • Reducing network losses through having the source of generation close to the load.						



	1	1					
Expected Timescale to adoption	Year 2015	Duration of benefit once achieved	20 years				
Probability of Success	25%	Project NPV (Present Benefits – Present Costs) x Probability of Success	£2M. The estimate will be refined in the WP3 to assess the economic impact of this architecture.				
Potential for achieving expected benefits	well. Various stakeho the CIRED Smart Grids	The two scenarios demonstrating the FENIX benefits, are proceeding well. Various stakeholders have been contacted and will be invited to the CIRED Smart Grids' workshop in Frankfurt. ADDRESS, a FP7 funded project, will build on the developments of FENIX.					
Project Progress March 2008	through LSVPP", has a characterisation of the tools and market interwith the wider system project, this WP has a of FENIX terms and de interactions (in partner consortium). The key deliverables he of the demand side in for the participation of provision of system a details the characteristand dynamic characteristand dynamic characteristand dynamic characteristand of the demand service implications for system that originate from VP existing tools available market interfaces currenergy and ancillary sis undertaken to identify required to incorporate the VPP. WP2, "Electrical and in presence of LSVPP", heeded in order to ad A general architecture and A general a	focused on the development of the VPP, and development of the services to allow interactions. In response to the first lso focused on identifications and agreement of the sership with WP2, and in the demand side in VP of the FENIX concept, and of the demand side in VP of the sership with WPP, looking the sership with the VPP, looking of the VPP, looking of the VPP, looking of the VPP port of the sership with the vPP port of the vPP port o	ment of the VPP concept, to of the various software on of the VPP (and DER) to year review of the FENIX ation of a common glossary to no core FENIX terms and discussion with the wider. One report details the role develops novel algorithms of portfolios, and in the vices. The other reporting at both the steady state folio, identifying the oy the VPP, and the mmercial market operation ble goes on to identify the ptimisation of DER and the coess to the wholesale echanisms. A gap analysis ptation and evolution is specific characteristics of itecture adapted to the functions that would be tools, delivering: In opean country such as: In opean country such as: In of the VPP (and DER) Itecture adapted to the functions that would be tools, delivering:				



- In Spain, the installation of a Node Management
 Mechanism operated by the distribution system operator
 (DSO).
- Optimises the changes in the business of the energy supplier and DSO by introducing the new functionalities of the Technical VPP (TVPP). The objectives were to:
 - Optimise the impact on the existing information systems; and
 - Optimise the number of interactions between the different actors.

An orchestration of actions that enable DER units to offer services to energy markets and to the DSO. These actions were described:

- One day ahead to validate the generation schedules; and
- In realtime in order to adjust the DER outputs.

<u>WP3, "Commercial framework for operation and control of power</u> <u>systems with LSVPPs"</u>, has accomplished, during the second year, four different tasks:

- Description of the Northern and Southern Scenarios aimed at illustrating the progress to date of the local scenario definitions for field demonstrations of the FENIX concept;
- Definition of alternative business models of VPP concepts from the perspectives of a typical distribution system operator, incumbent electricity supplier and independent DER aggregator respectively;
- Assessment and description of the aspects of the regulatory framework that are considered critical to the development of flexible networks, with significant contribution from distributed energy resources; and
- Description of contract models that will need to be developed between the various parties in a LSVPP framework.

In <u>WP4, "Demonstration of LSVPP concept feasibility"</u> real networks have been selected for the demonstrations. The main lines of the specifications of the physical demonstrations are well defined and equipment has been acquired.

The main characteristics anticipated for field and lab demonstrators are being drafted in an internal working paper. It also identifies all the necessary tasks to perform the demonstrations and proposes a roadmap for this.

In <u>WP5, "Stakeholders Advisory Group, Dissemination and Training"</u>, a series of newsletters has been conceived, and the first of these released, as the FENIX bulletin. Upcoming newsletters are scheduled for issue roughly every three months in parallel with emerging project results and completion of deliverables.



	The consortium has delivered a large number of presentations on FENIX results at International Conferences (CIRED, IEEE Powertech, etc.). The role of the Strategic Advisory Group in the project has also been readapted and rescheduled. A new meetings timetable has been proposed for forthcoming years, as well as a tentative schedule for national seminars. A seminar will be held in the UK.
Collaborative Partners	FENIX is an Integrated Project and is supported by the European Commission under the sixth framework programme. www.fenix-project.org
R&D Providers	Iberdrola SA, Electricité de France, EDF Energy Networks, Red Eléctrica de España SA, National Grid Transco, SIEMENS Aktien-gesellschaft Österreich PSE, Korona Inzeniring DD, Areva T&D Energy Management Europe, ZIV PmasC SL, ScalAgent Distributed Technologies, ECRO SRL, Pöyry Energy Consulting, Fundación LABEIN, Energy Research Centre of the Netherlands, Groupment pour inventer la distribution électrique de l'avenir, Institut für solare energieversorgungstechnik verein an der universität Kassel E.V. (ISET), The University of Manchester, Vrije Universiteit Amsterdam, Imperial Collage London and Gamesa Innovation and Technology.



4.12 Optimal Transformer Utilisation Model

4.12 Optimat mansio	טווופו טנונוסמנוט	11 1410	uei				
Description of project	EDF Energy Networks currently models emergency/cyclic ratings of power transformers by using a method based on formulae described in CP1010 / BS7735 (a loading guide for oil immersed transformers). This model allows the load-related risk on a substation to be quantified in order to prioritise network reinforcement expenditure. The model predicts the temperature rise within the transformer, in order to determine a maximum rating on a daily basis which each transformer can sustain. It has become apparent by comparing the output of the EDF Energy Networks' model with the temperatures observed in practice, that there are some differences. The main causes for differences in modelled and observed temperature are over-simplifications in the model, and the absence of effective data for transformer and heat exchanger parameters. The Cambridge University Engineering Department, in particular the EPEC group, has particular expertise in computer modelling and will be able to significantly improve the EDF Energy Networks' model; this will take the form of a new model for the transformer and a comparison of output with that observed in practice. By using numerical methods, unknown transformer parameters (which cannot easily be measured in practice on an operational transformer) will be determined to produce a model which accurately reflects transformer behaviour. The parameters will be used in the EDF Energy Networks' model, or the Cambridge Model will be						
	used in the EDF					idge Model will be	
	used in its entire			arate results			
Expenditure for		EPI	N	LPN		SPN	
financial year	External		£43,84		£18,054		
	Internal		£4,34		£1,788		
	Total		£48,18		£19,842	· · · · · · · · · · · · · · · · · · ·	
	primary transfor		llocated in p	roportion to	o tne nur	nber of installed	
Expenditure in previous (IFI) financial years	This project was not reported in the 06/07 activity report.						
Total Project Costs (Collaborative + external + EDF Energy Networks)	f 150,000 Projected 2008/09 costs for EDF Energy Networks External f 21,500 Internal f 3,000 Total f 24,500						
Technological area and/or issue addressed by project	Emergency/cycl	Emergency/cyclic ratings of power transformers					
Type(s) of innovation	Incremental		Project efits Rating	Project Residual Risk		Overall Project Score	
involved		11.2		-1		12.2	



Expected Benefits of Project	 Accurate assessment of load-related risk on a substation will allow EDF Energy Networks to confidently predict whether there is an unacceptable risk to supplies; and Optimum timing of reinforcement work programmes (ability to defer spending where appropriate). 				
Expected Timescale to adoption	Year 2014	Duration of benefit once achieved	20 years		
Probability of Success	50%	Project NPV (Present Benefits – Present Costs) x Probability of Success	£ 660k		
Potential for achieving expected benefits	The model developed is expected to give the improved representation of hot spot temperatures.				
Project Progress March 2008	The work so far has included the measurement of dimensions of the transformer. Drawings of the outside of the transformer have been obtained, but sourcing detailed drawings of the windings is proving difficult. The next stage (currently in progress) is to validate the thermal characteristic parameters for exponential equations. An initial simulation has been completed but more accurate dimensions of the windings are required. A two-dimensional model has been chosen. Temperature measurements of a real transformer have been taken using thermal pictures of the outside of a transformer. These thermal pictures have been compared with the loading profile for that day, but ambient temperature data is being sought to improve the tool. A demonstration of the "At Risk Evaluation" tool, to calculate the hot spot temperature profile, has been carried out so comparisons can be made.				
Collaborative Partners					
R&D Provider	Cambridge University Engineering Department				



4.13 Impact of Climate Change on the UK Energy Industry

4.13 Impact of Clima	te Change on the	UI	Lileigy illu	ustry		
Description of project	In 2006 the Met Office carried out a scoping study on the impacts of climate change on the UK energy industry. The report was the result of collaboration between E.ON UK, EDF Energy Networks, National Grid and the Met Office Hadley Centre to scope the impacts of climate change on the UK energy industry. This Phase 2 project was industry-funded; it involved 11 UK energy companies and was undertaken by the Met Office. It focused on the priorities identified by the previous study. During the project, new tools and methods, required to understand the impact of climate change on the energy industry will be developed, and new data resources will be designed to address gaps in underpinning information.					
Expenditure for		EPI	J	LPN		SPN
financial year	External	LII	£23,277		£14,813	£14,813
	Internal		£2,215		£1,409	£1,409
	Total		£25,492		£16,222	£16,222
	The costs have be customers.	en a				
Expenditure in previous (IFI) financial years	This project was not reported in previous IFI activity reports.					
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 554,000		Projected 2008/09 costs for EDF Energy Networks		External Internal Total	
Technological area and/or issue addressed by project	£ 554,000 costs for Internal £ 0,0					



	-	l .		.			
Type(s) of innovation	Technological		Project efits Rating	Project Re Risl		Overall Project Score	
involved	substitution	Delle	13.6	-2.0		15.6	
Expected Benefits of Project	 The expected benefits include: For the elements assessed, an understanding of the sensitivity to climate change and key meteorological drivers of the impacts. This will highlight priorities for adaptation; New models for projecting impacts suitable for inclusion in climate models or for application to climate model output; Guidance on the application of climate models to energy industry applications, which should result in appropriate use of climate information by Networks; and New information on urban heat islands and climatologies for the next 10 years to assist infrastructure design and planning. 						
Expected Timescale to adoption	Year 2011		Duration of benefit once achieved		20 yea	rs	
Probability of Success	50%		Project NPV (Present Benefits – Present Costs) x Probability of Success		£ 100,0	000	
Potential for achieving expected benefits	There is a good chance of achieving the expected benefits. This was a year long project that finished at the end of May 2008 on time and to budget and specification. Project outputs and reports are now available via the project website. The project has highlighted some areas of Networks where no change to						
Project Progress March 2008	In March 2008 the status of the project work packages was as follows. WP1 - complete WP2 - 50% complete WP3 - complete WP4 - 90% complete WP6 - 90% complete WP7 - 50% complete WP8 - 80% complete Overall the project was 75% complete.						
Collaborative Partners	All the network operators and most energy supply businesses.						
R&D Provider	Met Office	-			· · ·		



4.14 RTU Local Display Facility

Description of project	This project will enhance a Remote Terminal Unit (RTU) to allow local touch screen facilities to be installed in the door of each RTU cubicle.						
Expenditure for		EPI	١		LPN		SPN
financial year	External		£	0		£39,170	£0
	Internal		£	0		£6,465	£0
	Total		£	0		£45,635	£0
	The costs have b	een a	llocated to I	LPN	l where th	ne RTU is	being modified.
Expenditure in previous (IFI) financial years	This project was	This project was not reported in the 06/07 activity report.					
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 60,000						f 10,000 f 5,000 f 15,000
Technological area and/or issue addressed by project	Local display facility for primary RTUs.						
Type(s) of innovation involved	Incremental		Project R Benefits Rating Ris		Project Re Risk		Overall Project Score
Expected Benefits of Project	 The expected benefits include: Allowing the local on-site engineer to operate controls more safely; Obtaining more detailed information about the plant in the substation; and Having a view of what can be seen at the control centre to assist with fault finding. 						
Expected Timescale to adoption	Year 2009		Duration o once achie			20 Years	S
Probability of Success	50%	Project NPV (Pres Benefits – Preser Costs) x Probabili of Success		esent	£50k		
Potential for achieving expected benefits	This project has delivered a graphical interface for the RTUs in London.						
Project Progress March 2008	A T5500 Configuration Tool has been developed to construct mimic screens via a graphical interface. This is an improvement compared to the existing technique that involves editing a text file.						
Collaborative Partners							
R&D Provider	Converteam						
	•						



4.15 Condition Monitoring of Composite Insulators

4.15 Condition Monit	oring of Compo	<u>osite</u>	Insulators	1		
Description of project	Composite insulators are now deployed throughout the world and are steadily replacing traditional ceramic and glass insulators. Low weight and physical robustness are two properties which have led to an increasing market share for composite insulators over the last 20 years. However, there is concern over the long-term ageing of these insulators. This work will characterise the millimetre-scale arcing activity between water droplets, and develop an experimental knowledge and theoretical understanding of how this leads to macroscopic behaviour. In particular, it will identify the local service conditions on the millimetre scale which cause the ageing of hydrophobic material surfaces.					
Expenditure for		EPI	N	LPN		SPN
financial year	External		£27,07		£0	£10,528
,	Internal		£2,57	1		£1,002
	Total		£29,64			£11,530
	The costs have b	een a				
Expenditure in previous (IFI) financial years	This project was not reported in the 06/07 activity report.					
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 120,000 costs for		Projected 2 costs for EDF Energy	Internal £ 3,0		
Technological area and/or issue addressed by project	Develop reliabili schedules for typ condition monito	oe app	oroval and p	roduct deve	elopment,	and identify
Type(s) of innovation involved	Significant		Project efits Rating	Project Ro Ris		Overall Project Score
Expected Benefits of Project	The expected benefits include: • An improved understanding of insulation ageing; • A better understanding of risk associated with ageing of insulation; • Reduced operational costs through extended times between insulator replacement; • Reduced outages as a result of reduced, unforeseen insulation failure; • Improved methods for testing of new products; and • Stronger management of suppliers.					
Expected Timescale to adoption	Year 2011 Duration of benefit once achieved 20 years					5



r			_				
Probability of Success	25%	Project NPV (Present Benefits – Present Costs) x Probability of Success	£ 100k				
Potential for achieving expected benefits	The project is proceeding well. The probability of success is somewhat higher than when the project started.						
Project Progress March 2008	insulators taken from characterisation to da exposed areas (i.e. conclusion electrical, and is now been conclusive to establish and is now been conclusive to ensure that it is policy is designed of reliability, to optimize and provide information includes the policy will include the important policy will include the important policy will include the important policy will include the policy will be policy will include the policy will include the policy will include the policy will include the policy will be policy will include the policy will be policy will include the policy will be policy wil	mpared to a new sample lectrical tests, in both drompared to a new sample compared to a new sample compared to a new sample from a suitable inland larecovered in 2008. A compared in sulators will the copriate asset managements asset managements of the project end, technological to maintain safety, to ise insulator maintenants on to improve purchasing the project end to maintenants on to improve purchasing the project end to maintenants on to improve purchasing the project end to maintenants on the project end to the project end t	etrieval and insulators in more ation has so far been haracterisation. been carried out and the of the same base material. y and wet conditions, have ple. Some ageing has been ng assessed. ocation have been omparison between the ten be completed. ent policy has been drawn ogy transfer is efficient. ensure an acceptable level ce, inspection, replacement ng and design decisions. cy, maintenance and fault				
Collaborative Partners							
R&D Provider	University of Manches	University of Manchester					



4.16 Improvements in Overhead Line Performance

Description of project	This report covers a number of smaller projects each less than the de minimis level. Each project investigates different aspects that impact the performance of overhead lines.					
Expenditure for		EPI	٧	LPN		SPN
financial year	External		£38,778	3	£0	£15,080
	Internal		£6,21	3	£0	£2,416
	Total		£44,99	1	£0	£17,496
	The costs have b overhead line.	een a	Illocated in p	roportion t	o the leng	rth of 11kV
Expenditure in	External	£10	03,766			
previous (IFI) financial	Internal	£	18,837			
years	Total	£1:	22,603			
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 200,000		Projected 2008/09			f 0 f 0 f 0
Technological area and/or issue addressed by project	Improving ratings of lines, assessing the physical condition of support structures, electrical condition monitoring and wildlife deterrents.					
Type(s) of innovation involved	Incremental -		Project efits Rating	Project Re Ris		Overall Project Score
Expected Benefits of Project	The expected benefits include: • Understanding the benefits of aluminium conductor composite core (ACCC) compared with other technologies like AAAC and ACSR conductors; • Understanding of basic phenomena governing insulator and surge arresters failures; • Visual inspection of support structure, using unmanned helicopter, removes the need to climb the pole or tower; and • Effective methods to prevent roosting on lines that oversail customers' premises.					
Expected Timescale to adoption	Year 2010		Duration of benefit once achieved		20 years	S
Probability of Success	Varies between and 75%	25%	Project NP\ Benefits - Costs) x Pro of Success	Present	£ 1.0M	



Potential for achieving expected benefits	The ACCC conductor may be used for a wind farm connection where high loads are expected. Some audible bird deterrent systems only showed short term benefit. The unmanned helicopter concept will not proceed.
Project Progress March 2008	The project to increase our understanding of the basic phenomena governing insulator and surge arresters failures is now reported as a separate report titled "Condition monitoring of composite insulators." See Section 4.15. A drum of ACCC conductor and fittings was purchased to build a span at the EDF Energy Networks' training establishment to assess construction techniques. A number of bird deterrent systems have been assessed. The unmanned helicopter trial did not proceed as the helicopter could only be flown in good weather conditions.
Collaborative Partners	
R&D Provider	Composite Technology Corporation Runfold Plastics Ltd Scaringbirds.com Ltd Highspy



4.17 Application of Storage and Demand Side Management

Description of project	The project will investigate and quantify the benefits of integration of electricity storage and Demand Side Management (DSM) technologies in the operation and development of active distribution networks.					
Expenditure for		EPI	N	LPN		SPN
financial year	External		£14,40)	£5,700	£9,900
	Internal		£1,37	0	£542	£942
	Total		£15,77	0	£6,242	£10,842
		The costs have been allocated in proportion distributed generation.			o the amo	unt of connected
Expenditure in	External	£10	69,000			
previous (IFI) financial	Internal	£	14,420			
years	Total	£18	33,420			
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 460,000		Projected 2 costs for EDF Energy			£ 35,000 £ 5,000 £ 40,000
Technological area and/or issue addressed by project	 Feasibility assessment of alternative applications of DSM and storage to solve network problems; Development of techniques for optimisation of the operation of active distribution network, including realtime control of storage and load control devices, to manage network voltage and flow profiles in realtime; and Quantification and optimisation of the multiple value streams of various storage applications and load control management. 					
T (-) . f :	Dadiad		Project	Project Re		Overall Project
Type(s) of innovation involved	Radical	Bene	efits Rating	Ris	<	Score
Expected Benefits of Project	 The expected benefits include: Quantification of the value of specific storage and DSM technologies; and A business case showing whether storage and DSM can deliver value in the performance of the network. 					
Expected Timescale to adoption	Year - 2015		Duration of once achie		20 years	5



Probability of Success	75%	Project NPV (Present Benefits – Present Costs) x Probability of Success	Only when the methodology proposed in this project is developed, will it be possible to evaluate financial benefits of storage and DSM across various future development scenarios.		
Potential for achieving expected benefits	Significant progress has been made in the development of the tools to quantify the value of DSM and storage in applications for active distribution network management strategies. Initial findings indicate that application of DSM and storage techniques for active management of distribution networks have most value: In congested urban areas with restrictions on the physical expansion of the system; and When increased amounts of DG need to be integrated in the existing networks. On the basis of the sample networks studied, DSM provides the most cost effective application to these network problems.				
Project Progress March 2008	 Project progress against milestones: Models of responsive demand and storage have been developed and implemented in the United Kingdom Generic Distribution System (UKGDS) network and representative EDF Energy Networks' distribution networks to solve specific problems; Detailed models of heat demand in commercial buildings for use in network management applications have been devised and tested; Techniques and prototype algorithms for congestion management in distribution networks have been developed and tested in the case study network areas; and Identification of the regulatory and commercial barriers for application of storage and DSM in network management strategies. 				
Collaborative Partners	Scottish and Southern Energy				
R&D Provider	Imperial College				



4.18 Network Risk Management

4.18 Network Risk Ma	anagement					
Description of project	The aim of this project is to develop algorithms for calculating the risk, which the continued use of the components of a distribution system pose, to ongoing satisfactory system operation. It will take into account the significant levels of uncertainty that characterise both the condition of the individual assets and the overall operation of the network. The measurement of risk will characterise network performance in the near future, ensuring that it will reflect the anticipated variability in operation of future distribution networks. The outcome of the project will be new methodologies, enabling a formal understanding of the criticality of different operational conditions and the accuracy with which network parameters must be specified. In addition, it will illustrate the value of an explicitly predictive indicator of the suitability of proposed changes in system operation.					
Expenditure for		EPN	LPN		SPN	
financial year	External	£12,650	£8,050		£8,050	
	Internal	f 1,204	£ 766		f 766	
	Total	£13,854	£8,816		£8,816	
	The costs have b	een allocated in p	proportion to	o the nun	nber of connected	
Expenditure in	External	£148,300				
previous (IFI) financial	Internal	f 12,814				
years	Total	£161,114		ı		
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 454,000	costs for	Projected 2008/09 costs for EDF Energy Networks		f 5,000 l f 100,000 f 105,000	
Technological area and/or issue addressed by project	 This project will address: The formulation and implementation of algorithms to provide, in near-realtime, an assessment of the risk or vulnerability of a section of EDF Energy Networks' distribution system in the near future; What parameters have most influence on the calculated measure of network risk; and Provide a comprehensive demonstration of the value of a measure of risk for guiding network operation. 					
Type(s) of innovation involved	Significant	Project Benefits Rating	Project Re Risl		Overall Project Score	
Expected Benefits of Project	Benefits are expected to include: Development tools that will allow the DNO to take into account the explicit uncertainty involved in the distribution system operation; and Methodologies and tools that can be applied in active distribution networks to optimise the utilisation of the existing					



	network capacity, through the introduction of new devices and/or the modification of network operation strategies in a more informed manner.						
Expected Timescale to adoption	Year 2010	Duration of benefit once achieved	20 years				
Probability of Success	75%	Project NPV (Present Benefits – Present Costs) x Probability of Success	£ 200,000				
Potential for achieving expected benefits	To date, 20% of the work has been completed. At this comparatively early stage, reasonable progress has been made, as reflected by the detailed examination of the progress towards deliverables detailed below. Nonetheless, careful monitoring will be required in the following year to ensure continued satisfactory progress.						
Project Progress	The team's progress towards the nominated deliverables is: WP 1 - risk assessment algorithm. The theoretical distinction between risk and reliability has been defined, ensuring that any developed algorithms will generate unique information. Techniques have been developed for identifying network conditions when an operational measure of network vulnerability provides distinct information. Work on the precise risk assessment algorithm is still ongoing.						
	WP 2 - algorithm for formalised, continuous refinement of operational parameters. Work has confirmed the need for such a process and has shown that suitable resources exist within EDF Energy Networks' data collections. These are complemented by the results of a scoping study which has identified realistic bounds for parameters such as asset failure likelihoods, stochastic models used to describe restoration and repair processes and the effectiveness of network operational processes.						
March 2008	WP 3 - suite of system/feeder risk representations. Progress has been confined to consideration of the techniques needed to communicate a measure of network risk.						
	WP 4 - medium-term projection of risk evolution. The techniques developed as part of WP1 provide indications of the network conditions in which a longer term measure of risk will contain unique information. Future work can be focused on the relevant network conditions where a medium to long-term risk projection will have the most value.						
	WP 5 - approximate analytical models for risk assessment. The completion of a data survey providing bounds on: the range of asset failure likelihoods; the effectiveness of operational processes and the nature of repair and restoration processes, will help to ensure that numerical studies consider only appropriate degrees of variability. In						



	addition, sensitivity studies have been completed to show how variability in operational parameters will affect different measures of risk. WP 6 - identification of high risk assets. Only limited progress has been made towards this deliverable.
Collaborative Partners	
R&D Provider	Imperial College London



4.19 Supergen V - AMPerES

(Asset Management and Performance of Energy Systems)

(ASSE	t Management and	ı Per	formance of	Ellergy Sy	/stems)			
Description of project	This is a four year, major, multi-party collaborative project. The research programme is split into six work packages and 25 activities. Most of the research will be carried out by universities. An EDF Energy Networks representative has been identified for each work package so that research can be steered towards delivering benefits to the DNOs.							
Expenditure for		EPI	N	LPN		SPN		
financial year	External	1	£ 11,000		£ 7,000	£ 7,000		
,	Internal		£ 1,047		f 666			
	Total		£ 12,047		£ 7,666			
	The costs have bee	en all						
Expenditure in	External	£ 5	0,000					
previous (IFI)	Internal	£	4,172					
financial years	Total		4,172					
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 2,800,000	Projected 2008/09 External £ 25,000						
Technological area and/or issue addressed by project	WP 1: Programme delivery, outreach and implementation; WP 2: Enhanced network performance and planning; WP 3: New protection and control techniques that adapt to changing networks; WP 4: Infrastructure for reducing environmental impact; WP 5: Ageing mechanisms; and WP 6: Condition monitoring techniques.							
Type(s) of innovation involved	Radical -		Project efits Rating	Project Re Risl		Overall Project Score		
Expected Benefits of Project	 The expected aims of the project are: To deliver a suite of intelligent, diagnostic tools for plant; To provide platform technologies for integrated network planning and asset management; To progress plans to develop and implement improved and reduced environmental impact networks; and To develop models and recommendations for network operation and management. 							
Expected Timescale to adoption	Year 2013	Duration of benefit once achieved 20 years						



Probability of Success	25%	Project NPV (Present Benefits – Present Costs) x Probability of Success	£150k				
Potential for achieving expected benefits	Asset management is core to the business. The appropriate use of the emerging opportunities for condition monitoring is key to optimising performance, both financially and in terms of quality of supply. A number of technologies are being developed as part of this programme; however, it also gives a broader window to the global research community. Through demonstration, the true value of condition monitoring will be identified, enabling appropriate business decisions on adoption of technologies.						
Project Progress March 2008	number of demonstrator ahead of schedule. The high-level work to dexpansion methodologis this project should become agreed by the Steering of at both distribution and techniques is complete selected for implemental underpin the more apply with development of more developed. To date, 14 work. Technical documents provided by the Steering of Mains internet protocological interim report with synchronical first report on networks; First report on networks; Final report on Report on ICSE Report on literal and Condition more	rs have been identified levelop optimal asset re es is progressing well, ome a demonstrator; th Group. More physical of transmission substation and machine learning to ation. work on ageing of plant ied activities, is also prethods to characterise a reports and 38 publicate roduced: Detection and Ameliorate detection by differentiate col; on protection and control ous islands; Environmental Impact of use of high temperatur high temperature low so 2 2007; ature on non-power free nitoring - state of the art	which is necessary to ogressing according to plan, ageing plants being ations have arisen from this ation on Networks; al ROCOF Protection using rol of distribution networks felectrical Plant - Annual e conductors on distribution sag conductors; quency ageing in dielectrics;				



	 Technology and trials The following demonstrator projects are presently being implemented in both transmission (due to finish mid-June) and distribution substations: Monitoring of two 275/132kV National Grid transformers; Monitoring of six Scottish Power substations; and Processing of partial discharge data from EDF Energy Networks' substations.
	These will be used to prove data acquisition technology and develop interpretation tools.
	National Grid ScottishPower Energy Networks
	Scottish and Southern Electric
Collaborative	Electricity North West Western Power Distribution
Partners	Central Networks
Turmers	CE Electric UK
	Northern Ireland Electricity and
	Advantica
	Universities of Edinburgh
	Liverpool
	Manchester
R&D Provider	Queens (Belfast)
	Southampton and
	Strathclyde



4.20 Wood pole disposal

4.20 Wood pole dispo	osai							
		The majority of poles are currently sent to landfill with the rest being used for barter with landowners.						
Description of project	Waste disposal is becoming an increasing issue for EDF Energy Networks and the Environmental Agency. As with the recycling of excavated material, the cost of landfill is increasing and the number of poles being replaced is also rising. There is, therefore, a need to find a sustainable alternative to landfill. The disposal of wood pole is an aspect of the distribution system asset management (decommissioning). This project is done in collaboration with the Forestry Commission to carry out a small scale trial of burning redundant poles to produce charcoal, and to provide feedstock for electricity generation. The theory has been proved in a laboratory experiment and now needs to be scaled up to evaluate the potential for commercial charcoal production and electricity generation, by building and running a small pilot plant. The work involves the burning of contaminated wood at temperatures to drive off and collect volatile gases to be used for generation of electricity, and to recover the charred wood as a charcoal product. The project will also develop tests to characterise the poles in respect of age, to determine the amount of potential pollutants left in the wood.							
Expenditure for		EPI	N	LPN		SPN		
financial year	External		£14,40	0	£0	£5,600		
	Internal		£1,37	0	£0	£533		
	Total		£15,77	0	£0	£6,133		
	The costs have b	een a	llocated pro	portion to t	he length	of 11kV overhead		
Expenditure in	External	£1,	000					
previous (IFI) financial	Internal	£2,	494					
years	Total	£3,	494					
Total Project Costs (Collaborative + external + EDF Energy Networks)	Total £3,494 Projected 2008/09 External £ 20,000 costs for Internal £ 2,000 EDF Energy Networks Total £ 22,000							
Technological area and/or issue addressed by project	The technical issue being addressed by this project is to develop an environmental process for the disposal of wood poles. The collection of the volatile gases to be used for generation of electricity and production of charcoal is an innovative method for the disposal of wood poles.							
Type(s) of innovation involved	Significant	Significant Project Project Residual Overall Project Residual Score						



Expected Benefits of Project	The diversion of the poles from landfill has a financial benefit and helps the Company meet its objective of achieving the 60% recycling target. The project will support EDF Energy Networks' environmental aspirations.						
Expected Timescale to adoption	Year 2014 Duration of benefit once achieved 20 years						
Probability of Success	75%	£ 250k					
Potential for achieving expected benefits	The process to recover the volatile gases has proved difficult. A new method of charcoaling the recovered wood pole is creating interest.						
Project Progress March 2008	The discovery of a patent on a similar technique to recover the distillate has slowed progress. The increased level of biomass generation has changed the direction of the project to convert the recovered wood poles into a suitable fuel.						
Collaborative Partners							
R&D Provider	Forestry Commission						



4.21 LV Underground Cable Fault Management

4.21 LV Underground	Cable Fault Ma	ınag	ement					
Description of project	EDF Energy Networks has identified opportunities from intermittent fault detection and location on LV underground cables. This project combines the use of an intermittent cable fault location device (T-P22) with an improved re-energisation device (REZAP Fault Master) so that LV intermittent faults can be better managed and customer interruptions reduced. The project is also supporting the development of a "modular REZAP".							
Expenditure for		EPI	N	LPN		SPN		
financial year	External		£7,66		£4,000	£5,000		
,	Internal		£72		£381			
	Total		£8,39		£4,381	£5,476		
		een a	•		•	gth of installed LV		
Expenditure in	External	£2	90,085					
previous (IFI) financial	Internal	£ 2	27,709					
years	Total		17,794					
Total Project Costs (Collaborative + external + EDF Energy Networks)	Projected 2008/09 External £45,000 costs for Internal £ 5,000 EDF Energy Networks Total £50,000							
Technological area and/or issue addressed by project	 The project is developing the following techniques: Time reflection to determine fault location; Transient impedance fault location; Travelling wave fault location; and An auto-reclosing device. 							
Type(s) of innovation involved	Radical	Proje Bene	ect efits Rating	Project Re Risk	sidual	Overall Project Score		
Expected Benefits of Project	Benefits are expected to include: Reduction in number of site visits to replace fuses; Reduction in repeated customer interruptions due to intermittent faults being re-energised; Reduction in customer minutes lost; and Reduction in worst served customers.							
Expected Timescale to adoption	Year 2008 Duration of benefit once achieved 20 years					S		
Probability of Success	75%	Project NPV (Present Benefits – Present Costs) x Probability of Success		£ 1.2M				



Potential for achieving expected benefits	Work is currently on-going to modify EDF Energy Networks' LV fault management strategy to formally approve the use of the equipment developed as part of this project.
Project Progress March 2008	 T-P22 (Intermittent fault location equipment) Following successful trials of the device, EDF Energy Networks has purchased a number of T-P22 equipment and is currently finalising details for a company wide deployment. The following developments were carried out: Migration to GPRS communication has been completed successfully and is ready to be rolled out to other T-P22 units; and; Auto download of data has been completed and can be accessed via the iHost webserver. REZAP Fault Master (LV auto-reclosing equipment) The trial of the REZAP Fault Master devices has been delayed due to operational restrictions on the EDF Energy Networks' LV network. The following developments are progressing according to plan:
Collaborative Partners	Electricity North West and ScottishPower Energy Networks
R&D Provider	Kehui Ltd, Kelman Ltd and Nortech Management Ltd



4.22 33kV Voltage Control

4.22 33kV Voltage Co	ontrol						
Description of project Expenditure for	This project proposes a study to evaluate active voltage control and reactive power flow management of interconnected 33kV systems (via SCADA), to minimise losses whilst accommodating embedded generation. With the provision of real and reactive power measurements, generator outputs and tap changer positions, the project will develop voltage control strategies taking into the account DG contributions and coordination with various EDF Energy Networks and National Grid strategies.						
financial year	External		£10,59	4	£0	£5,458	
	Internal		£1,00	8	£0	£519	
	Total		£11,60	2	£0	£5,977	
	The costs have the transformers who beneficial.		-	-			
Expenditure in previous (IFI) financial years		External £ 6000 Internal £ 1007 Total £ 7007					
Total Project Costs (Collaborative + external + EDF Energy Networks)	f 118,000 Projected 2008/09 External £ 6000 costs for Internal £ 1007 EDF Energy Networks Total £ 7007					£ 1007	
Technological area and/or issue addressed by project	Co-ordinated 33 contributions.	kV vo	ltage control	strategies	taking int	o account DG	
Type(s) of innovation involved	Significant		Project efits Rating	Project Re Ris		Overall Project Score	
Expected Benefits of Project	The expected benefits are: • Enhanced software tools and techniques for mathematical modelling and analysis of AVC schemes in distribution networks; • Increased headroom to allow more DG to connect to lower voltage networks; and • Reduced network losses caused by reactive power flow.						
Expected Timescale to adoption	Year 2013 Duration of benefit once achieved 20 years				5		
Probability of Success	25%		Project NPV (Present Benefits – Present Costs) x Probability of Success		£ 100,000		



Potential for achieving expected benefits	Based upon the progress to March 2008 there is considerable potential for achieving expected benefits. The major benefits close to realisation are: • Increased headroom to allow more DG to connect to lower voltage networks; and • Software assessment tool for SuperTAPP n+ relay operation and settings.
Project Progress March 2008	 Progress to date includes: Rigorous investigation, implementation, testing and comparison of existing modelling and analysis tools for AVC schemes in distribution networks; Theoretical demonstration of benefits of SuperTAPP AVC scheme in distribution networks using enhanced software tools and techniques; Practical demonstration of potential benefits of SuperTAPP AVC scheme using EDF Energy Networks' network case study and data; and The acceptance of three technical papers at international conferences: UPEC 2007, PSCC 2008 and UPEC 2008.
Collaborative Partners	Fundamentals Ltd
R&D Provider	Brunel University



4.23 Collaborative ENA R&D Programme

4.23 Collaborative El			CNA) rapro	anta all I	IV DNOs Thosa				
Description of project	The Energy Networks Association (ENA) represents all UK DNOs. These								
Description of project	projects listed below have been initiated by the ENA R&D Working Group								
Fun an ditura far	and have been funded through the IFI.								
Expenditure for	F	EPN	LPN	6 2.002	SPN				
financial year	External	£7,268		£2,993	£3,990				
	Internal	£691		£285	£380				
	Total	£7,959	•	£3,278	£4,370				
	The costs have be transformers.	een allocated in p	roportion t	o the num	ber of primary				
Expenditure in	External	£17,875							
previous (IFI) financial	Internal	f 1,393							
years	Total	£19,268							
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 215,000	Projected 2 costs for EDF Energy			£ 5,000 £ 1,000 £ 6,000				
Technological area and/or issue addressed by project	 SG12 Fault I and establish disturbance operation, etrue network information SG14 Earthi impact of low zones' and the earth system 	and establish the network source impedance from small-scale disturbances/perturbations resulting from transformer tap changer operation, etc. This impedance can be accurately correlated to a true network fault level for that location, providing near-realtime information to network control and planning engineers alike.							
	Incremental	Project	Project Re		Overall Project				
_	and	Benefits Rating	Ris	k	Score				
Type(s) of innovation	Significant								
involved	innovation								
	types are								
	involved.								
	The developed unit will allow the DNOs to accurately assess fault								
	"infeed" levels and design distribution networks appropriately. The								
	particular benefits of Fault Level Monitor project are seen to be:								
E		ig a realtime and c							
Expected Benefits of		ely taking into acc	ount all cor	nnected no	etwork elements				
Project	(e.g. Mo		6.11						
		ing the connection		_	•				
	•	ng a standardised	methodolo	gy for the	assessment of				
	network fault levels;								
	 Enabling an ongoing assessment of the effects of connected 								



	 distributed generation to be made; and Providing reassurance to generator developers that decisions to upgrade networks are not subjective but based on objective measurement. 					
	 The Earthing project will: Deliver a clear rationale describing the correct location of LV earth electrodes with respect to HV earth electrodes. This will have potential benefits in improving understanding of the safety of the earth installations. ESQC Regulation 8(2) (b) requires that HV electrodes are installed and used in such a manner so as to prevent danger in the LV network due to a fault in the HV network; Consider the effects of touch and step potentials under fault conditions in all designs for earthing systems. However, the quantity of concern is actually the current flowing through a human body when in contact with metalwork subject to this potential and the time the current flows for. An electrode simply sited in soil, which has a surface potential, cannot be regarded as presenting the same hazard as metalwork with a direct metallic connection to the earth fault current return path; and Determine these effects and provide a means to obtain cost effective safe earthing systems without the need for extensive separations between HV and LV electrodes which, in a PME system, may be impractical to achieve and maintain. 					
Expected Timescale to adoption	Year 2008 - 2015	Duration of benefit once achieved	10 – 20 years			
Probability of Success	25 - 75%	Project NPV (Present Benefits – Present Costs) x Probability of Success	£ 500,000			
Potential for achieving expected benefits	To progress to stage 2 of Fault Level Monitor project as originally defined, the results obtained from stage 1 had to support a statement that it was technically feasible to develop a Fault Level Measuring Instrument capable of deriving answers within ±5% of the actual Source and Motor Infeed values. The Algorithm validation work has cast some doubt over the achievability of that goal. The verification of results between the existing Fault Level Monitor with expected values does, however, offer some signs that the results obtained in the algorithm validation phase are not clear. The proposed testing of the existing Fault Level Monitor, within a defined third party test network, has not been pursued at this time. Although this might provide further data supporting the instrument's capabilities, it would not answer the question as to why the differences exist between					



the apparent capability of the existing instrument and the performance of the algorithms implemented in Matlab.

As the results of Stage 1 do not support an unambiguous statement that it is technically feasible to develop a Fault Level Monitor with the required degree of accuracy, this project will conclude at Stage 1.

Proposals are being prepared for consideration to carry out further work to resolve questions about the apparent differences in performance of the existing Fault Level Monitor and the Fault Level Monitor algorithms implemented in Matlab.

The **Earthing Project** results from tests and simulations can be used to propose a recommended procedure for measuring transfer potential between HV and LV systems.

A number of activities have been pursued by both EA Technology and the University of Strathclyde in the progression of **Fault Level Monitor project**. These are summarised as:

- Experiment and Laboratory Investigation the performance of the previous Fault Level Monitor was tested against the known parameters of the University of Strathclyde's microgrid. In general a reasonable level of agreement was achieved.
- Algorithm Validation the algorithms from the Fault Level
 Monitor, coded within Matlab, were tested using a network
 model in Matlab/Simulink to provide the sampled data to the
 algorithm. The results were compared to values of source infeed
 and motor infeed calculated directly from the parameters of the
 disturbances used. This resulted in an assessment of the
 potential accuracy of the instrument under a variety of load and
 disturbance conditions. At the power factor and load
 disturbance conditions, which were most likely to be
 experienced in a real power system, the results were not within
 the required accuracy band.
- Comparison of Real Site in contrast to the results obtained under the algorithm validation section, comparison of measurements made on a real network with the Fault Level Monitor exhibited a much closer agreement with the expected results.

The Earthing project is complete. It has revealed the previously unknown effect that the LV electrode system can have on the shape of the HV voltage contours in the soil, that results in a lower than predicted average transfer potential on the LV neutral/earth. This has important consequences for distribution system design and could result in a reduction in the required HV:LV separation distances. For example, it means that new installations could be situated closer to an HV site than previously thought. It also goes some way towards explaining why there are far fewer reports of damage on LV networks co-incident with an HV

Project Progress March 2008



	fault, when their earthing systems are separate, but not by the 3m to 9m distance required in DNO policies.
Collaborative Partners	National Grid ScottishPower Energy Networks Scottish and Southern Electricity North West Western Power Distribution Central Networks and CE Electric UK
R&D Providers	EA Technology Ltd Strategy and Solutions Ltd University of Strathclyde



4.24 Activ Project

4.24 Activ Project							
Description of project	This project will investigate active voltage control in order to increase the efficiency of the network and facilitate the connection of distributed generation. More specifically, it will undertake field trials of the "Fundamentals" SuperTAPP n+ automatic voltage control (AVC) relay and develop associated modelling criteria for network planners.						
Expenditure for		EPI		LPN		SPN	
financial year	External		£3,31		£1,312		
,	Internal		£41		£162		
	Total		£3,72	5	£1,474		
	The costs have be distributed gener		•	proportion t	o the amo	ount of connected	
Expenditure in previous (IFI) financial years	This project was	starte	ed in this rep	orting year.			
Total Project Costs (Collaborative + external + EDF Energy Networks)	£254,206	Frojected 200 costs for EDF Energy N		•	External £ 47,000 Internal £ 10,000 S Total £ 57,000		
Technological area and/or issue addressed by project	To investigate the performance of the Fundamentals SuperTAPP n+ AVC relay to regulate voltage on 33kV and 11kV network feeders with load and generation present.						
Type(s) of innovation involved	Incremental			Project Re Risk	sidual	Overall Project Score	
Expected Benefits of Project	The expected benefits of the project are: • Enabling the connection of distributed generation using a simple solution which requires minimal network modification; • Improving the voltage profile of supply; • Reducing the requirement for network extensions or reinforcement and increasing the capacity for the connection of distributed generation; and • Reducing the risk of voltage being outside statutory limits and thus damaging equipment and injuring personnel.						
Expected Timescale to adoption	Year 2010	Duration of ber once achieved			10 years	S	
Probability of Success	75%	Project NI Benefits - Costs) x F of Succes		obability	£ 223k		
Potential for achieving expected benefits	With one trial site installed (with promising initial results) and a further two identified, there is a high probability that the expected benefits will be achieved.						



Project Progress March 2008	The relay and monitoring equipment were installed at the first site in Elland (part of CE Electric UK's network) between the 17 and 19 March. The site has two transformers, presently using a master/follower system, and a landfill generator is connected on one feeder that is also supplying load. The relay has been installed open loop initially. The following values have been recorded: • Real and reactive current and voltage from the generator; • Real and reactive current and voltage through one transformer; • Real and reactive current on the feeder; • Real and reactive generator current estimated by the relay; • Tap change events; • Tap change signals from the relay; and • Voltage at the remote end of the feeder with the greatest voltage drop. The project was started in December 2007 and is currently on schedule. Initial results show that the estimation follows the generator output closely (for a landfill gas generator with a steady output).				
Collaborative Partners	CE Electric UK Central Networks ScottishPower Energy Networks and Electricity North West				
R&D Provider	EA Technology Ltd Fundamentals Ltd				



4.25 Recycling Excavated Material

w pi m in sy	which occurs as poroject work, can naterials can be nstallation of un ystem asset mai ligible IFI projec	part of the reconnage manage dergro nagem	EDF Energy cycled and h ged both int und cables	Networks' now the cha ernally and is an aspec	jointing, ange to th with loca	maintenance and ne use of recycled al authorities. The	
Description of project la	This project will identify ways in which excavated ground works material, which occurs as part of EDF Energy Networks' jointing, maintenance and project work, can be recycled and how the change to the use of recycled materials can be managed both internally and with local authorities. The installation of underground cables is an aspect of the distribution system asset management (construction) that meets the definition of an eligible IFI project. Currently, over 500,000 tonnes/annum of excavated material are sent to landfill. Disposal costs are rising and are in the order of £20/tonne. Equal amounts of aggregate (approximately £16/tonne) are excavated to produce virgin type one material required by the Highways Authorities to backfill utility excavations. The impact of sending excavated material to landfill sites is not sustainable and demonstrates that EDF Energy Networks takes the challenge of corporate responsibility seriously.						
Expenditure for		EPN		LPN		SPN	
·	xternal	LIIV	£765		£425	£510	
· · · · · · · · · · · · · · · · · · ·	nternal		£1,720		£956		
	otal		£2,485		£1,381	£1,657	
Th	he costs have be inderground cab			•			
Expenditure in Ex	xternal	£24,	681				
·	nternal	f 6,	,463				
years To	otal	£31,					
Total Project Costs (Collaborative + external + EDF Energy Networks)	80,000		Projected 2 costs for EDF Energy			f 24,681 f 8,000 f 32,681	
Technological area and/or issue addressed by project All (c	The innovative part of this project is to show that the recycled material can meet the requirements of the Highway Authorities and can be approved as an alternative to virgin type one material. It will also contribute to achieving the "45% of material recycled" government target. This will be carried out alongside a full product and process life cycle analysis. Any recommendations will be backed up by scientific evidence (comparison between recycled material properties and reinstatement specification) and a cost benefit analysis. All findings will be shared across all utility industries.						
Type(s) of innovation involved	Radical –		roject its Rating	Project Re Risk		Overall Project Score	



Expected Benefits of Project	 Benefits are expected to include: Reduction in the amount of material sent to landfill by 136,000 tonnes/year; Reduction in excavated virgin material from around the world by 136,000 tonnes; Less vehicle movement to landfill sites and gravel yards; and Less pollution on roads caused by vehicle movement. 					
Expected Timescale to adoption	Year 2014 Duration of benefit once achieved 20 years					
Probability of Success	75%	£1.9M				
Potential for achieving expected benefits	There is a high probability that the objectives will be met as a number of authorities are already allowing use of recycled materials.					
Project Progress March 2008	Although there was an initial reluctance to use the suggested recycled material, local authorities are now much more receptive and many trials have taken place. A sustainability group has been set up between a number of local authorities, other utility companies and their contractors in order to share experiences. Work supported by the University of Sussex has commenced on a sustainability life cycle model. Lastly, members of the project team have been asked to speak at national and local events on sustainability relating to street works.					
Collaborative Partners						
R&D Provider	University of Surrey					



4.26 Grid Transformer Monitoring

4.26 Grid Transforme	er Monitoring						
Description of project	This project will evaluate the benefits of deploying the Intellix MO150 transformer monitoring system. Devices will be installed on four typical grid transformers at two sites. Full installation involves the integration of alarms/monitoring data with existing EDF Energy Networks' SCADA (ENMAC and possibly one CORGIS site) and historic data acquisition into LIMES data historian for strategic analysis.						
Expenditure for		EPN LPN SPN					
financial year	External		£2,34	6	£966	£1,288	
	Internal		£22:	3	£92	£123	
	Total		£2,56	9	£1,058	£1,411	
	The costs have b	een a	llocated in p	roportion to	o the nun	nber of primary	
	transformers sup	oplyin	g the distrib	ution netwo	ork.		
Expenditure in	External	£	94,000				
previous (IFI) financial	Internal	£	7,327				
years	Total		01,327				
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 170,000	,	Projected 2008/09 costs for EDF Energy Networks			l f61,000 l f 2,400 f63,400	
Technological area and/or issue addressed by project	Grid transformer monitoring						
Type(s) of innovation involved	Incremental		Project efits Rating	Project Re Risl		Overall Project Score	
Expected Benefits of Project	The expected benefits include the following: Optimisation of the lifespan of power transformers; Monitoring and performing realtime, online transformer diagnostics can help reduce the risk of unexpected and sometimes catastrophic failures, thus avoiding expensive replacement, clean-up costs and unplanned downtime; and Permit short time overloading with online realtime monitoring.						
Expected Timescale to adoption	Year 2009 Duration of benefit once achieved 20 years					S	
Probability of Success	50%		Project NPV (Present Benefits – Present Costs) x Probability of Success				
Potential for achieving expected benefits	The system has been installed at one site and the local monitoring is operating satisfactorily.						



Project Progress March 2008	The monitoring systems have been installed on two transformers. These are operating satisfactorily on a local basis. The communication channels have been installed to this site and are currently undergoing test (This will enable remote communication with the equipment).
Collaborative Partners	
R&D Provider	GE Energy and MW Test Equipment Ltd



4.27 Earthing Information System

4.27 Earthing Inform	ation System					
Description of project	The project will develop a GIS Information System to assist the installation of rural ground earthing systems, by providing a graphical presentation of ground conditions and the likelihood of a suitable earthing resistance being met. Earthing rural substations can be very labour intensive, as there is sometimes a need to drive earthing rods into the ground to a depth of 12					
	metres (in order to achieve the necessary 10 ohm resistance). Usually rods are driven by pneumatic tools or by hand. Where hard ground restricts the depth of installation, an array of rods are installed at shallower depths, or an earthing system is installed some distance from the substation to achieve the required resistance.					
Expenditure for		EPI	١	LPN		SPN
financial year	External		£	0	£0	£0
	Internal		£1,17	3	£483	£644
	Total		£1,17	3	£483	£644
	The costs have be distribution sub			roportion t	o the num	nber of
Expenditure in previous (IFI) financial years	This project was not reported in the 06/07 activity report.					
Total Project Costs (Collaborative + external + EDF Energy Networks)	Projected 2008/09 External £ 225,000 costs for Internal £ 10,000 EDF Energy Networks Total £ 235,000					f 10,000
Technological area and/or issue addressed by project	A network-wide information system that will help improve planning and costing of new and replacement earthing installations.					
			Project	Project Re	esidual	Overall Project
Type(s) of innovation involved	Significant	Ben	efits Rating	Ris	k	Score
Expected Benefits of Project	The expected benefits are: • Accurate estimation of the cost of installation of rural ground earthing systems; • Advice on the number and technique of installation; and • Employee safety.					
Expected Timescale to adoption	Year 2012 Duration of benefit once achieved 20 years					5
Probability of Success	50%		Project NPV Benefits – Costs) x Pro of Success	Present obability	£ 110k	



Potential for achieving expected benefits	This collaboration with Central Networks is proceeding well. Regular meetings have ensured issues are resolved with the minimum of delay.
Project Progress March 2008	Ease of Installation The British Geological Survey has collated all available engineering properties for the two test areas to allocate strength values to DIGMAP, and a first-pass working layer of engineering properties has been established. Cranfield University has mapped the areas with rock close to the surface, as well as soil with either impermeable horizon, excess of gravel in the profile or soils which have been established over gravel indicating areas in which installation will require heavier equipment. Electrical Resistivity BGS has collated all available data for the test areas from resistivity sounding databases and Cranfield University has collated all relevant soil properties and developed a model to generate worst case scenarios for both soil moisture and soil temperature related changes in soil resistivity. Next steps The integration of the relevant datasets for both the Ease of Installation and the Electrical Resistivity assessment.
Collaborative Partners	Central Networks
R&D Provider	British Geological Survey and Cranfield University



4.28 Electrical Energy Harvesting from Vibrations

4.28 Electrical Energy	y Harvesting fro	om v	brations				
Description of project	In 2005 The Facility Architects Ltd won an international design competition which sought creative architectural ideas for restoring the 1,000 railway arches in London. Included in The Facility's proposal was the intention to use 'power harvesting' generators to capture some of the ambient energy in the arch (e.g. vibrational energy transferred through the arch by trains passing overhead, kinetic energy lost into the ground by pedestrians as they walk through the arch) and convert it into electrical energy that could be used to power electrical devices such as low power LED lights. The project has been restructured into four phases: • Technical feasibility and system integration; • Economic feasibility; • Pilot project; and • Business Development.						
Expenditure for		EPI	V	LPN		SPN	
financial year	External	£0		£0		£0	
,	Internal	£0		£0		£0	
	Total	£0		£0		£0	
	The costs have be customers.	The costs have been allocated in proportion to the number of connected					
Expenditure in	External	£10	0,000				
previous (IFI) financial	Internal	£	779				
years	Total	£10	0,779				
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 200,000		Projected 2 costs for EDF Energy			l f 10,000 l f 1,000 f 11,000	
Technological area and/or issue addressed by project	Electrical Energy	Harve	esting from v	ibrations a	nd footst	eps.	
Type(s) of innovation involved	Radical	Radical Project Project Residual Overall Project Residual Overall Project Residual Score					
Expected Benefits of Project	 Benefits are expected to include: Being able to provide lighting in areas where cable installation is problematic or exposed to vandalism; An energy harvesting floor system; The resulting device could power remote sensors on primary equipment to provide condition monitoring facilities; and The technology may be capable of transfer to other network assets that vibrate as a form of noise reduction. 						
Expected Timescale to adoption	Year 2014		Duration of once achie		20 year	rs	



Probability of Success	25%	Project NPV (Present Benefits – Present Costs) x Probability of Success	£20k			
Potential for achieving expected benefits	This project is at a very early stage of development. The PACEsetter project has aroused the interest of several private and public organisations.					
Project Progress March 2008	A new project manager has been appointed full time and the work schedule has been updated to accommodate a number of feasibility studies (technical and economic). Contractual issues on the use of IP needed to be resolved. Energy Harvesting using Vibrations: Permissions have been granted by Network Rail for 15 accelerometer positions to be tested ranging from the rails through to the structure of the viaduct itself. There were delays in gaining vibration data from railway arches, but railway sleepers may provide greater interest. Energy Harvesting from footsteps: Calculations of the potential energy from footsteps available for capture, and the potential energy available for conversion from gym equipment have been carried out. A visit to TechnoGym Italy who is interested in sharing knowledge on footstep outputs from walking and running.					
Collaborative Partners	Phillips Lighting and Scott Wilson Engineering					
R&D Provider	Facility Innovate Hull University and Perpetuum based at the University of Southampton					



4.29 Transformer Temperature Fibre Optic Monitoring

Description of project	It is proposed that fibre optic temperature monitoring will be fitted to one of the new 30MVA transformers to be installed at Barnes substation. The monitoring will be installed in addition to the conventional electromechanical winding temperature instruments so that the performance of the two instruments can be compared.						
Expenditure for		EPI	١	LPN		SPN	
financial year	External	External £0 £0				£0	
	Internal	£0		£0		£0	
	Total	f0 f0			£0		
	The costs have to primary transfor		llocated in p	proportion to	o the nur	nber of installed	
Expenditure in	External	£47	7,250				
previous (IFI) financial	Internal	£	4,491				
years	Total	£5:	1,741				
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 52,000	Projected 2008/09				l f10,000 l f 2,000 f12,000	
Technological area and/or issue addressed by project	Temperature Monitoring using Fibre Optics						
Type(s) of innovation involved	Incremental	ental Project Project Renefits Rating Ris				Overall Project Score	
Expected Benefits of Project	Assessi	ation o	include: If the tradition of seasonal r ings of powe	atings; and		ature;	
Expected Timescale to adoption	Year 2010		Duration of once achie		20 yea	20 years	
Probability of Success	75%	Project NPV (Present Benefits - Present Costs) x Probability of Success					
Potential for achieving expected benefits	Final completion software to enab		pendent on	Siemens pr			
Project Progress March 2008	The equipment is fitted and in operation. Some of the data can be viewed from a website.						
		Siemens/EBG					



4.30 Power Networks Research Academy

4.30 Power Networks	Research Acad	Leniy						
Description of project	Power Networks Research Academy has been established through a strategic partnership agreement between the Engineering and Physical Sciences Research Council (EPSRC), Network operators and electricity supply industry related manufacturers and consultants. They will fund PhD researchers in power industry-related projects, help maintain, as well as improve, the research and teaching capacity in power engineering subjects.							
Expenditure for		EPN LPN SPN						
financial year	External	£0	f0	£0				
imancial year	Internal	£0	f0	f0				
	Total	£0	f0	£0				
		een allocated in p	proportion to the nu	I .				
Expenditure in previous (IFI) financial years	The Academy ha	s not been reporte	ed in previous years					
Total Project Costs (Collaborative + external + EDF Energy Networks)				al £57,000 ll £ 3,000 £60,000				
Technological area and/or issue addressed by project	 The projects for the first cohort of Academy scholars are: Overhead Lines Measurement System; System Impacts and Opportunities of HVDC Upgrades; Application of Artificial Immune System Algorithm to Distribution Networks; and Circuit Breaker Condition Monitoring. 							
Type(s) of innovation	Significant, Technological	Project Benefits Rating	Project Residual Risk	Overall Project Score				
involved	substitution and Radical innovations	9.4	0.0	9.4				
Expected Benefits of Project	It is expected that the Academy will: Promote a stronger, more active and robust R&D environment in power networks disciplines at UK universities; Provide capacity and capability to undertake the specialist research needed by industry and wider stakeholders; Strengthen the teaching capability at those institutions; Focus on building the health of discipline across a number of power research universities; Facilitate a resource of trained engineering staff with academic capability, who will be capable of tackling electrical power engineering challenges; and Deliver research output that is industrially relevant.							



	T			
Expected Timescale to adoption	Year 2012 onwards	Duration of benefit once achieved	20 years	
Probability of Success	25%	Project NPV (Present Benefits – Present Costs) x Probability of Success	£200,000	
Potential for achieving expected benefits	The scholars will start their research topics in September 2008. It is therefore too early to predict the potential for achieving expected benefits. However each project has been allocated an industrial champion who will support and ensure that the project maintains its industrial relevance.			
Project Progress March 2008	The scholars start their research topics in September 2008.			
Collaborative Partners	EPSRC National Grid Scottish and Southern Central Networks			
R&D Providers	Universities of Cardiff Manchester Queens (Belfast) Southampton Strathclyde Imperial College Lond			



4.31 Supergen I – FlexNet

4.31 Supergen I – Fle	exnet						
Description of project	FlexNet will put in place a substantial body of work that will build on the achievements of FutureNet and lay out the major steps, technical, economic, market design, public acceptance and others, that will lead to flexible networks, including starting to showcase these so that they can be taken up by the commercial sector, government and regulators for practical implementation.						
Expenditure for		EPN LPN SPN					
financial year	External	£0	£0		£0		
	Internal	£0	£0		f0		
	Total	£0	£0		£0		
	The costs will be each licensed no	allocated in propetwork.	ortion to the	e numbei	r of customers in		
Expenditure in previous (IFI) financial years	The programme	started in this regu	ulatory year	•			
Total Project Costs (Collaborative + external + EDF Energy Networks)	f 7.6M Projected 2008/09 costs for EDF Energy Networks External £ 20,00 Internal £ 3,000 Total £ 23,000						
Technological area and/or issue addressed by project	 How car How mumargin controll What coaccepta 	ions to be address In we judge the deg In flexibility be ach Ich flexibility shou and how much from ability? and Instrains or encount ble and what ecor flexibility at the le	gree of flexil ieved? Id come fro m secondar rages flexib nomic frame	m primar y plant g ility, wha	ry plant giving iving enhanced at technologies are and public policies		
	Significant,	Project	Project Re	esidual	Overall Project		
Type(s) of innovation	Technological	Benefits Rating	Risl	k	Score		
involved	substitution and Radical innovations	7.2	-2		9.2		
	Each work stream	m is expected to d	eliver bene	fits.			
Expected Benefits of Project	 build or Markets issues of Power S of power result in voltage Smart, If underst 	and Size of Future on the FutureNet scenario and Investments of the electricity may stem Electronics or losses and concompower electronic control. Elexible Controls wand the benefits ophy and the requirements of the second control.	enarios. will investigarket. will investigerns over losystems cu vill help networts changing	gate som gate why cal netwo rrently be work ope the netw	e of the economic capital cost, cost ork integration eing restricted to rators to ork operation		



	 Customers, Citizens and Loads will analyse potential contributions that customers and responsive demand can make towards enabling a more flexible energy system, to identify barriers to this participation and their possible remedies, and to analyse the place-related factors shaping public acceptance of a more flexible network infrastructure. Validation and Showcase will provide the basis for testing the research outcomes in a representative environment and demonstrating their effectiveness in addressing problems central to the realisation of flexible power networks. Future Energy Mix will consider possible changes in (UK) energy systems to 2050 and examine the impact of these changes on energy transportation networks. Future LV Networks will investigate losses through auditing and analysing the relative impact of load profile, sharing, imbalance and sag on losses. Education, Deliberative Engagement and Public Acceptance of Future Networks will inform many of the social issues and engagement. 				
Expected Timescale to adoption	Year 2012 onwards	Duration of benefit once achieved	20 years		
Probability of Success	25%	£2M			
Potential for achieving expected benefits	I - FutureNet are contir the quality of work wil	nuing to participate in Fl	ced the results of Supergen lexNet. It is expected that the industrial partners will experiences.		
Project Progress March 2008	The project started on 1 October 2007. Since then the academic partners have recruited PhD students and research assistants to undertake the research. The project management and steering groups have been established to manage and govern the progress of the project. Some of the workstreams are already producing some useful results.				
Collaborative Partners	EPSRC, National Grid, Scottish and Southern Energy, Central Networks, ScottishPower Energy Networks, CE Electric UK, Electricity North West and Rolls-Royce plc.				
R&D Provider		irmingham, Cambridge, de and Imperial College	=		



4.32 Strategic Technology Programme Overhead Network Module

Description of project	The STP overhead network programme for the 2007/8 regulatory year aimed to reduce costs and improve performance of overhead networks by increasing understanding of issues that have a negative impact on costs and performance.					
Expenditure for		EPI	N	LPN		SPN
financial year	External		£36,327		£0	£10,851
	Internal		£ 3,928		£0	£ 1,173
	Total		£40,255		£0	£12,024
	The costs have be overhead line.	en a	llocated in pro	portion to	o the leng	th of installed
Expenditure in	External	£	94,272			
previous (IFI) financial	Internal	£	10,617			
years	Total	£10	04,889			
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 344,079 annua	lly	Projected 200 costs for EDF Energy N	•		f 50,000 f 4,000 f 54,000
Technological area and/or issue addressed by project	have been identif significant and what the projects within S2126_3 temperat S2126_4 two trials S2136_3 727: Mean Structure S2140_2 foundation S2143_2 degradat S2146_2 for composition S2148_1 S2150_1 using act S2151_1 S2152_1 severe were severe were severe sever	e is also expected to have a positive impact on safety and performance. The projects all address real problems that atified by the module steering group members as which require technical investigation and development. This thin the programme aimed to: 23 – Complete long-term monitoring of conductor rature by obtaining and analysing 12 months' trial data; 4 – Monitoring overhead line conductor temperature at all sites at constant current; 3 – Continue participation in European Project COST deasuring and forecasting atmospheric icing on ares; 2 – Carry out field trials of techniques for checking the ations of newly installed poles; 2 – Conduct a feasibility study to detect in-situred dation of aluminium overhead line conductors; 2 – Undertake torsion testing to evaluate possible limits inposite tension insulators; 4 – Re-appraise ACE104 methodology; 1 – Evaluate TDR for assessment of tower foundations actual field data; 1 – Investigate alternatives to wood poles; 1 – Evaluate performance of ice recording solution at the weather test site; 1 – Investigate ice loading of novel conductors; and all – Examine comparative performance of available poles.				onductor nths' trial data; r temperature at Project COST ting on or checking the t in-situ ctors; possible limits r foundations les; ng solution at ductors; and



- () 51	Technological	Project	Project Residual	Overall Project		
Type(s) of innovation involved	substitution, Radical	Benefits Rating	Risk	Score		
Expected Benefits of Project	Due to the age profile of system equipment it is inevitable that, unless significant new technology is used to extend asset life, CAPEX and possibly OPEX will need to increase significantly to maintain the present level of network reliability and safety. If these projects are technically successful, and the findings and recommendations from the projects are implemented, then the projects will potentially enable each DNO member of the programme to gain benefits including: • Avoiding redesign, reconstruction or refurbishment of overhead lines where this is driven by a perceived need to increase ratings or strengthen lines, and is required to conform with existing standards but which may be unnecessary; • Reducing levels of premature failure of assets; • Providing more cost effective and early identification of damaged insulators and discharging components, which if not addressed would result in faults; • Confidently extending the service life of towers and reducing potential levels of tower failures; • Reducing lifetime costs by the appropriate use of alternative materials.					
Expected Timescale to adoption	Range 1-5 years dependent on project	Duration o once achie	0	3-7 years – dent on project		
Probability of Success	Range 2-50% – dependent on project	Project NP Benefits – Costs) x Pr of Success	Present f 85,9	017		
Potential for achieving expected benefits	Some projects within the programme are at an early stage, whilst others are complete. Issues have been identified relating to both operational and capital expenditure which, if successfully addressed, would enable the expected benefits to be achieved.					
Project Progress March 2008	The second phase of monitoring overhead conductor temperatures at steady rated current was carried out during the year. The data has yet to be analysed. In contrast to the first phase, when four different types of conductor, all with similar ratings, were monitored at a single location, phase two monitored two different-sized conductors of the same type (so different design temperatures for the same current) simultaneously at two very different locations; one near sea level and one high up in the Scottish Highlands. Phase 1 found that day time ratings could probably be increased. Hopefully analysis of the Phase 2 data will provide confirmation of this and possibly find other location-dependent benefits. An experimental investigation of live-line jumper cutting was carried out					



	little difference in ice loads but big differences in creep between the three conductors. At the same time, two ice meters have been tested, one as a stand-alone STP2 project and the other as part of a European project on conductor icing. The former performed very well and could provide DNOs with realtime information on ice build-up on exposed
	A non-destructive device, for detecting defects in concrete, has been
	assessed for its applicability to HV tower foundations. Subsequent excavations of the tested foundations indicated that the device is a useful and sufficiently accurate tool for assessing foundation integrity. Its use could result in significant time and cost savings for DNOs.
	A study of alternatives to wood poles for HV OH lines, looking at the advantages and disadvantages, and the practical applicability within UK DNOs, indicated there were significant benefits to be gained from using concrete poles in certain situations. A test rig has been designed to investigate the practical problems of erecting and working on lines mounted on concrete poles.
Collaborative Partners	CE Electric Scottish and Southern Energy Central Networks ScottishPower Energy Networks Electricity North West Northern Ireland Electricity and
R&D Provider	Western Power Distribution EA Technology Ltd



4.33 Strategic Technology Programme Cable Networks Module

4.33 Strategic recini	ology i rogrami	iic c	able Helw	orks Mou	att	
Description of project	The STP cable networks programme for the 2007/8 regulatory year aimed at identifying and developing opportunities to reduce the costs of owning cable networks. The reduction of whole life cost, through greater reliability and improved performance of cables and associated accessories, falls within the remit of Module 3. Where appropriate, Module 3 worked with other modules to achieve common goals.					
Expenditure for		EPN	N	LPN		SPN
financial year	External		£21,70	2	£11,323	£14,154
	Internal		£ 2,34		£ 1,224	
	Total		£24,04		£12,547	
	The costs have bunderground cal		llocated in p	proportion to	the leng	gth of installed
Expenditure in	External	£10	05,172			
previous (IFI) financial	Internal		10,253			
years	Total					
Total Project Costs (Collaborative + external + EDF Energy Networks)		Total £115,425				
Technological area and/or issue addressed by project	The projects undertaken within the programme during 2006-07 aimed to: S3132_10 – Further develop cable ratings to address gas compression cables; S3132_12 – Further develop cable ratings; S3140_3 – Develop best practice for the installation of Ducted Cable systems; S3144_2 and 3 – Compare processes for the treatment of redundant fluid-filled cables; S3151_1, 2 and 3 – Aid understanding and control of thermomechanical forces in cable systems; S4152 – Examine separable connectors and cable compartments in 11kV switchgear; S3159_1 – Investigate current ratings of triplexed cable in plastic ducts; and S3157_1 – Carry out PD testing of MV cable systems to provide asset risk management data.					
Type(s) of innovation involved	Technological substitution, Radical Project Residual Overall Project Residual Score Risk Score					
Expected Benefits of Project	If the projects are technically successful, and the findings and recommendations from the projects are implemented, then the projects will potentially enable each DNO member of the programme to gain the following benefits, including: • Offsetting future increases in CAPEX and OPEX; • Achieving CI/CML savings per connected customer; and • Increasing the safety of staff and the public by reducing the number of accidents/incidents.					



		_	<u>, </u>				
Expected Timescale to adoption	Range 1-3 years – dependent on project	Duration of benefit once achieved	Range 3-5 years – dependent on project				
Probability of Success	Range 2-50% – dependent on project	Project NPV (Present Benefits – Present Costs) x Probability of Success	f 82,068				
Potential for achieving expected benefits	are complete. Issues and capital expenditu	Some projects within the programme are at an early stage, whilst others are complete. Issues have been identified relating to both operational and capital expenditure which if successfully addressed would enable the expected benefits to be achieved.					
Project Progress March 2008	ratings of crossing cal (S3132_10) and dyna creation of a compreh designers and cable esolving difficult multi-overloading the circuit. The cable rating work calculation of technic delivered a tool for cobonding of MV polymenergy losses, as well elementary section leenvironmental impact programme. Work is ongoing to as plastic ducts (S3155) out within the STP to the Electricity Industry collapse in the future. Trials have been arrar processes for the treat (S3144) on oil removas uitable sites and perhave now been resolved to select the best and term impact on the emminimised. Significant progress is system (on-line and o	bles (S3132_7), gas continuing (S3132_12) tensive suite of cable ratengineers. The outputs a crircuit problems. Withouts. is being extended to the all losses in cable networking the merits of creatic cable systems, includes as current ratings, circuing the Further work on the standard of the series of losses is continuing the sess the mechanical and the sess the sess the mechanical and the sess the	ting tools for network are of particular benefit in but them there are risks of e accurate modelling and orks. The S3148 project has ross-bonding and solid uding outputs of annualised ulating currents and he economic and g in the 2008/09 STP d thermal integrity of its experimental work carried ication, vital to ensure that ous problem of duct ectiveness of three different at end-of-life. This work difficulties in obtaining ke part, but the problems project should allow DNOs cess, ensuring that long to oil filled cables is				



Collaborative Partners	CE Electric Scottish and Southern Energy Central Networks Scottish Power Energy Networks Electricity North West ESB Networks and Western Power Distribution
R&D Provider	EA Technology Ltd



4.34 Strategic Technology Programme Substation Module

4.34 Strategic Techno	ology Frogramm	ie 3	upstation M	vuule		
Description of project	Issues with the age profile of substation assets within the UK electricity distribution system are well known. Also, both regulatory and shareholder pressures preclude substantial investments of the large scale that was seen in the 1950s to 1970s. The challenge is to constantly review and innovate new solutions to monitor and define asset condition, thereby allowing risks to be clearly defined and sound investment decisions to be taken The programme of projects which were approved for funding from the STP substations module budget and undertaken in 2007/08 encompasses the development of new innovative asset management processes and practices and developing innovative diagnostic techniques. The aim is to develop already well established themes such as: life extension of aged assets within legal and heath and safety constraints; examination of new technologies; developing an understanding of and innovative solutions for the impact on substation assets of increasing levels of distributed generation on networks; and condition monitoring techniques.					
Typonditure for	EPN LPN SPN				SPN	
Expenditure for financial year	External	EPI	£21,702	LPN	£11,323	£14,154
illialiciat year	Internal		£ 2,347		f 1,224	£ 1,531
	Total	£24,049			£12,547	£15,685
	The costs have be	en a		•		•
	substations.		, , , , , , , , , , , , , , , , , , ,			,
Expenditure in	External	£	94,272			
previous (IFI) financial	Internal	£	8,386			
years	Total	£10	02,658			
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 304,648 annua	lly	Projected 200 costs for EDF Energy N			f 50,000 f 4,000 f 54,000
Technological area and/or issue addressed by project	Eighteen new projects were approved during the year. They are: • S4164_4 – On load tap changer monitor – develop and install trial systems; • S4176_3 – Assessment and inspection of substation earthing systems • S4181_2 – Transformer Post Mortems • S4185_2 – AM Forum membership; • S4212_1 – Dissemination Seminar to ensure wider appreciation of STP module outputs; • S4219_1 – Management of substation batteries; • S4220_1 – Management of 145kV Disconnectors; • S4221_1 – Investigate Out of Phase Switching; • S4222_1 – Explore Alternatives to ENATS 35-1 Transformers; • S4223_1 – Review of Underground Substation design; • S4225_1 – Assessment of BS148 and IEC60296 Insulating					



	Oils;				
	S4228_1 – Investigate Alternative Measuring Techniques for				
	Insulation Materials; and				
	 S4234_1 –Exploration of Ferroresonance Issues. 				
	Incremental,	Project	Project Re	sidual	Overall Project
Type(s) of innovation involved	Significant,	Benefits Rating	Risk	(Score
	Technological				
	substitution,				
	Radical				
Expected Benefits of Project	Due to the age profile of the current system assets it is inevitable that, unless significant new technology is used to extend asset life, CAPEX and possibly OPEX will need to increase significantly to maintain the present level of network reliability and safety. If the projects are technically successful, and the findings and recommendations from the projects are implemented, then the projects will potentially enable each DNO member of the programme to gain the benefits including: Offsetting future increases in CAPEX and OPEX; Increasing the safety of staff and the public by reducing the number of accidents/incidents; and Both preventing disruptive failures of oil-filled equipment to reduce land contamination and avoiding unnecessary scrapping of serviceable components, to alleviate environmental impact.				
Expected Timescale to adoption	Range 1-2 years dependent on project			_	l-10 years – lent on project
Probability of Success	Range 5-50% – dependent on project	Project NP\ Benefits - Costs) x Pro of Success	Present obability	£ 63,64	.9
Potential for achieving expected benefits	Some projects within the programme are at an early stage, whilst others are complete. Issues have been identified relating to both operational and capital expenditure which, if successfully addressed, would enable the expected benefits to be achieved.				



R&D Provider	EA Technology Ltd
Collaborative Partners	CE Electric Scottish and Southern Energy Central Networks ScottishPower Energy Networks Electricity North West ESB Networks and Western Power Distribution
Project Progress March 2008	The wide ranging projects intended to provide numerous benefits, both in terms of safety, knowledge sharing, network performance, mitigation of risks to plant and minimising effects to the environment. The majority of projects have not only resulted in essential knowledge transfer, they have enabled skills to be developed between STP 4 Members and also European partners. Key examples of this were the participation in the AM Forum, (S4185_3), the sponsoring of the Ferro-Resonance Seminar, (S4234_1), the Out Of Phase Workshop, (S4221_1) and the Substation Maintenance Seminar, (S4212_1). Each of these has contributed significantly to developing better understanding of electrical plant, its application, utilisation, performance and life cycle. These projects have resulted in the creation of further supplementary projects for 2008/2009. Additional key development and technical projects have also been undertaken. The On–Load Tap Changer Monitor, (S4164_4) and the Programme of Transformer Post Mortems, (S4181_2), for instance, could each lead to a reduction in potential multiple transformer failures, together providing mitigation of multiple potential incidents. Condition based monitoring and the prediction of end of life of plant, will lead to an improvement in network performance, providing a clearer understanding of degradation and the failure processes, which will provide the ability to identify and predict end of life, providing many years benefit. This will enable assets to be replaced in a controlled manner, within agreed timescales, minimise disruptive failures and the implications associated with them, in terms of safety, cost, Cl's and CML's.



4.35 Strategic Technology Programme Networks for Distributed Energy Resources Module

Module						
Description of project	The projects undertaken during the 2007/8 regulatory year were aimed at enabling cost effective connections and ensuring techniques are in place to plan, operate and manage networks with significant amounts of generation. Most projects also had positive impacts on safety and environmental performance. The projects all addressed real problems that were identified as being significant by the module steering group members. This resulted in technical investigation and development.					
Expenditure for	EPN LPN SPN			SPN		
financial year	External		£22,646		£8,964	£15,569
	Internal		£2,449		£969	£1,684
	Total		£25,095		£9,933	£17,253
	The costs have been allocated in proportion to the amount of installed distributed generation.					
Expenditure in	External	£ 94	4,272			
previous (IFI) financial	Internal £		8,270			
years	Total	£10	2,542		T	
Total Project Costs (Collaborative + external + EDF Energy Networks)	£ 371,475 annually		Projected 2008/09 costs for EDF Energy Networks		Internal Total	f 50,000 f 4,000 f 54,000
Technological area and/or issue addressed by project						



	ı				
	connected demands;				
	 S5174_1 – Assess the potential for DSM from small 				
	customers;				
	 S5176_1 – Assess the impact of high penetrations of micro- 				
	generation on cable networks;				
	 S5182_1 – Examine treatment of distribution network losses; 				
	 S5185_1 – Assess the potential for DSM from larger 				
	customers; and				
	 S5186_1/2 – Investigate effects on network of proposed ban 				
	on incandescent light bulbs				
	Incremental,	Project	Project Re	sidual	Overall Project
Type(s) of innovation	Significant,	Benefits Rating	Risk		Score
involved	Technological				
	substitution				
	With governmen	t policy driving sig	nificant incr	reases ir	n generation
		stribution network			
	innovative solut	ions to connectior	and networ	rk opera	tion issues that are
	cost effective an	d which maintain	the present	level of	network reliability
	and safety.		•		
	·				
	If the findings ar	nd recommendatio	ns from the	projects	are implemented,
	the projects will potentially enable each DNO member of the programme				
	to gain benefits	including:			
	Reducing the probability of voltage supply limit excursions				
	resulting from increased distributed generation;				
	Improving quality of supply and reducing the risk of				
Expected Benefits of	component failure (by understanding the effect and optimising				
Project	use of impedance in the system);				
	A better understanding of the risk presented by the				
	distribution assets when considered as a network rather than				
	discrete components;				
	Greater use of distributed generators to meet current DNO				
	obligations (by assessing, from a DNO perspective, the				
	implications of pending Distribution Code provisions relating				
	to distributed generation); and				
	Reducing the amount of reinforcement needed (by using				
	dynamic ratings to allow network components to be used to				
	their full capability) - the use of dynamic circuit ratings is a				
	vital step in the move towards active management of				
	networks.				
	Range 1-5 years	- 5	Duration of benefit		1.40
Expected Timescale to	dependent on	Duration of			1-10 years –
adoption	project	once achie	eved	depend	lent on project
		Project NP	V (Present		
	Range 10-30% -	Benefits –			
Probability of Success	dependent on	Costs) x Pr		£ 80,74	44
	project	of Success			
<u> </u>	l				



Potential for achieving expected benefits	Some projects within the programme are at an early stage, whilst others are complete. Issues have been identified relating to both operational and capital expenditure which, if successfully addressed would enable the expected benefits to be achieved.
	During 2007/08, Northern Ireland Electricity joined the Module, bringing the number of full members to eight. A total of thirteen reports and briefing papers were delivered during the year, including a review of CIRED 2007 for all Modules; this was an efficient and cost-effective means of disseminating information and trends from the event, enabling STP members to identify areas of future research and development relevant to the UK context.
Project Progress March 2008	The year also saw the completion of twelve months' monitoring of the microgenerator cluster in Manchester, a network with a high penetration of microgeneration where the houses are new build (i.e. well insulated with a relatively low heating requirement). Laboratory tests on compact fluorescent light bulbs were undertaken to examine the network effects of the proposed ban on incandescent bulbs and a follow-on stage was approved to monitor whole house performance under typical mixed loads with measurements concentrating on the harmonic effects.
Collaborative Partners	CE Electric Scottish and Southern Energy Central Networks ScottishPower Energy Networks Electricity North West ESB Networks Manx Electricity Authority and Northern Ireland Electricity
R&D Provider	EA Technology Ltd



5. Steyning Primary RPZ

Description of project and technical details	Following the successful trial of GenAVC at Martham Primary in North Norfolk (the EDF Energy Networks (EPN) plc RPZ), Econnect Ventures Limited was asked to develop an assessment tool to determine whether GenAVC would be an appropriate solution to voltage rise problems in the early stages of DG connection process. A landfill gas generation site suffers nuisance tripping due to high volts during periods of light load throughout the summer months. The generator operator also has a greater supply of landfill gas than it can utilise to generate energy. Excess gas cannot be stored and needs to be flared into the environment. The generator operator wishes to install an additional 1.5MW unit at his site. To validate the assessment tool, EDF Energy Networks installed GenAVC at Steyning Primary. The results of the system are being monitored.
Expenditure for financial year	Expenditure is detailed in the GenAVC Assessment tool IFI project report contained in section 3.2 of this report.
Type(s) of innovation involved	The assessment tool did show that GenAVC is an appropriate solution to a voltage rise problem. GenAVC takes into account the voltage contribution from DG connected to the network and biases the target voltage of the primary substation tap changers to allow additional generation to be connected and the output of the generators to be maximised.
Status (planned, under construction, operational) and operational starting year	Operational
Connection cost	Connection costs using GenAVC were reduced when compared to the traditional network reinforcement methods which would have involved the installation of 4.5km of underground cable.
Benefit to customers compared to those envisage when project was registered	This RPZ was registered to allow the generator operator to be able to utilise its additional gas supply to generate energy, as opposed to flaring the excess gas into the environment. It already operates two 1MW of landfill gas generators connected to distribution network supplied from Steyning Primary substation. The assessment tool estimated that approximately 1.5MW of additional generation could be connected without infringing statutory voltage or power flow limits. All connected customers benefit from improved voltage control especially during periods of light load when higher volts were experienced.