


Serving the South West and Wales

Report on 2008/09 work undertaken under Ofgem Innovation Funding Incentive



Western Power Distribution (South West) plc Western Power Distribution (South Wales) plc

WESTERN POWER DISTRIBUTION

CONTENTS

1.0	Introduction	1
2.0	Outline of Ofgem Innovation Funding Incentive	1
3.0	Western Power Distribution approach to R&D	3
4.0	2008/9 projects	4
5.0	Commentary on previous IFI projects	10
6.0	Forward view of 2009/10 projects	10
7.0	Pro-forma reports	11
8.0	Note on net present values	43

Page

(Cover page - slide from presentation by Robin Mortimer - Director Adapting to Climate Change Programme - DEFRA July 2009)

1.0 INTRODUCTION

- 1.1 Western Power Distribution (South Wales) plc and Western Power Distribution (South West) plc hold electricity distribution licences issued by Ofgem under the Electricity Act (as amended). For brevity, "WPD" is used to refer to both licenced areas in this report.
- 1.2 During 2004, the Energy Regulator, Ofgem introduced an "Innovation Funding Incentive" (IFI) to encourage Distribution Network Operators (DNOs) to apply innovation in the way they pursue the technical development of their networks. This report describes WPD's IFI activities in 2008/9 and provides additional comments on use of previous research & development (R&D). WPD are required under the IFI scheme to complete a number of pro-forma report sheets, and these are included in Section 7 of this report.

2.0 OFGEM INNOVATION FUNDING INCENTIVE

- 2.1 The introduction of the Ofgem IFI mechanism in 2004 recognised that the risk/reward balance for research, development and innovation, differed from that applying to normal Distribution Network Operator (DNO) core business. IFI funded projects had to meet eligibility rules set out in Ofgem / DNO agreed documents.
- 2.2 Qualifying IFI projects have to meet criteria set out in the Ofgem IFI Regulatory Instructions and Guidance (RIG) and a Good Practice Guide which had to be developed by IFI parties and agreed by Ofgem. IFI work is partially funded, on a reducing sliding scale. Whilst DNOs could submit their own individual GPGs, there has been collaboration between DNOs in consultation with Ofgem, and a common GPG produced, as Energy Networks Association Engineering Recommendation G85, which received Ofgem agreement.
- 2.3 Building on experience gained during these initial projects, the RIGs and GPG were revised, and issue 2 of Engineering Recommendation G85 was issued in December 2007. As a consequence, of this, we have projects in 2008/9 which were commenced under different GPGs, with different definitions and reporting requirements.
- 2.4 The RIGs published by Ofgem and applicable to the 2006/7 financial year provided the following definition of an Eligible IFI Project:

A project will qualify as an eligible IFI project provided that it is designed to enhance the technical development of distribution networks (up to and including 132kV). Eligible IFI projects will embrace all aspects of distribution system asset management from design through to construction, commissioning, operation, maintenance and decommissioning.

2.5 The definition of technical development contained in the initial GPG, is as follows -

" In this context:

- "Technical" means "Being of a scientific and/or engineering nature and benefiting the design, construction, commissioning, operation, maintenance and decommissioning of the primary plant and equipment employed in the distribution of electrical energy and/or of the secondary plant and equipment employed to control, protect and maintain such Primary plant and equipment"
- "primary" means "heavy current equipment that carries power currents at voltages from LV up to and including 132kV"
- 2.6 In Issue 2 of "G85" the definition of "technical" was revised as follows -
 - "Technical" means "Being of a scientific and/or engineering nature and benefiting the design, construction, commissioning, operation, maintenance and decommissioning and/or improving the direct environmental interactions of the Primary plant and equipment employed in the distribution of electrical energy, transmission or electrical energy and transmission of gas and/or the secondary plant and equipment employed to control, protect and maintain such Primary plant and equipment"

2.7 Ofgem have -

- established new RIGs with a rolling 5 year commitment to IFI,
- introduced a constant % support rather than a sliding scale reduction
- 2.8 This 2008/9 WPD IFI report uses the relevant GPG depending on date the project was initiated.

3.0 WPD's APPROACH TO RESEARCH AND DEVELOPMENT

- 3.1 Having regard to the need for prudent investment and use of resource, WPD's approach is to undertake targeted research on a range of short to medium term projects not having a high cost / high risk profile, normally through collaborative projects or programmes to gain added value and However, it is sometimes the case that collaboration in more aearina. speculative and blue sky research is pursued where the programme content is appropriate and there is very high gearing. The Supergen V EPSRC funded Amperes programme and Meteorological Office lead research on climate change impacts are examples. It is worthy of note that the Amperes programme was established under different EPSRC gualifying criteria than are now in place. Currently EPSRC focus is on Technology Readiness Levels (TRL) 1-3 where 1 is effectively "blue sky research" with no target development. The current GPG comments that Blue Sky research projects would not normally be considered eligible for IFI unless it can be demonstrated that there is an extremely good potential case and leverage from other funding is sufficiently great that it reduces the risk to the Network Operator to an acceptable and attractive level.
- 3.2 WPD have, in common with other DNOs, a long association of collaborative research working with EA Technology, Capenhurst, arising from the former Electricity Council Research Centre and the establishment of areas of UK expertise in specific and pertinent spheres of electricity distribution which are of relevance to WPD. Collaborative working has been undertaken with other UK DNOs and overseas partners in Strategic Technology Programme (STP) modules on substation, overhead line and underground cable subject areas. The costs of these are well below the de-minimis £80k per licence holder group as set in the GPG (section 5) for reporting at individual project level; programme level reporting is required.
- 3.3 In addition to work with EATL, WPD has previously engaged ERA Leatherhead and a wide range of other providers including Universities to undertake specific research work. Since April 2005, WPD has committed to supporting a large research proposal to EPSCR on Enhanced Management and Performance for a Sustainable UK Energy Infrastructure (Supergen V Amperes project), which would be heavily geared and involve collaboration with the Universities of Edinburgh, Liverpool, Manchester, Queens Belfast, Southampton and Strathclyde together with Industrial partners and other UK DNOs and transmission companies.

- 3.4 WPD recognises that it is sometimes valuable to commission research to provide a platform to facilitate debate on major issues. A current example has been the environmental life cycle research project with the University of Bath to provide data in support of network loss reduction issues, described more fully below. Under previous IFI work, WPD engaged in research on charging methodologies.
- 3.5 It is recognised that whilst research can often lead in the long term to real financial benefits, there are also significant benefits to the wider community through -
 - network performance improved reliability and resilience
 - environmental emissions, waste, visual impact etc
 - safety to employees and public
 - external risk mitigation
 - knowledge transfer acquisition and dissemination of knowledge,
 - enhancing the quality and relevance of research through direct linkage with industry, development of the available "pool" of expertise, greater exposure of own staff to direct engagement with research activity

4.0 2008/9 PROJECTS

4.1 WPD's 2008/9 IFI Programme contained the following projects -

EATL STP Module 2 - Overhead Networks EATL STP Module 3 - Cable Networks EATL STP Module 4 - Substations Supergen V Amperes - extensive EPSRC joint funded programme ENA - Fault Level Monitor & Earthing projects ENA - harmonic modelling Met Office - climate change impact on energy networks Met Office - climate change impacts on network resilience University of Bath - life cycle assessment 11kV overhead line and underground cable University of Strathclyde - Radiometric arc fault location Elimpus - Helicopter mounted partial discharge locator ADAS / Bartlett - Use of Tree Growth Retardant WPD - Smart networks trial

Reports on these have been provided by research providers, collaborator partners and WPD, and are included in section 7 below. Additional comments and links to research partner web-sites are provided in the following paragraphs.

4.2 <u>EATL STP</u> web site <u>www.eatechnology.com/STP_LearnMore.asp</u>

4.3 <u>Supergen Amperes</u> <u>www.Supergen.amperes.org.uk</u>

SUPERGEN is an initiative managed and led by UK research councils and the Carbon Trust to support strategically important research in power engineering. It aims to help the UK meet its environmental emissions targets through a radical improvement in the sustainability of power generation and supply. The Energy Infrastructure Programme, one of 14 within SUPERGEN, is known as AMPerES (Asset Management and Performance of Electrical Systems).

The UK has a need to maintain reliability of energy supply at minimum cost in the context of ageing plant and a drive to deploy renewable and distributed generation. New forms of generation are changing loading characteristics of plant and system load flows. Increased use of power electronics will also change the nature of the waveforms that plant needs to cope with. The need to load particular parts of the system to maximise renewable output will also change the logistics of maintenance outages. To cope with this, a more rigorous view of risk is required which links individual items of plant, system requirements and system performance. In addition there is a need to address the environmental impact of transmission and distribution networks.

All the major UK Electricity network operators are involved in the project and in addition to their technical knowledge and network data, are contributing financial support. The Universities involved are those of Manchester, Southampton, Edinburgh, Liverpool, Strathclyde, and Queens University Belfast.

The two key aims of the project are; firstly to provide platform technologies and tools for integrated network planning and asset management; and secondly to identify methods to develop and implement networks with reduced environmental impact.

Core to the structure of this project is the integrated use of demonstration sites and activities. This provides a path of vertical integration through the project, bringing together the people working on the areas of material ageing, plant modelling, data acquisition and interpretation and optimal decision making. These demonstrators will pull together the world class research being carried out in the laboratories and allow the true value of condition monitoring to be identified, enabling appropriate business decisions on adoption of technologies.

The four-year project started in 2006 and is now fully resourced in all the universities. The project is on schedule to end in January 2010. A bid for renewal of the project for four further years is with EPSRC, and further details can be obtained from the project manager.

Many of the technologies being developed in this programme are likely to be utilised, however equally important is the broader window this work gives UK utilities to the global research community. In addition utilities and universities are learning to work in partnership, and developing young engineers who will provide the necessary skills base for the future.

4.4 Met Office research into climate change impacts on energy

www.metoffice.gov.uk/climatechange/buisinesses/casestudies/energy.html www.metoffice.gov.uk/climatechange/science/projections/

also

http://ukcp09.defra.gov.uk

This work has provided a "state of art" view of forward climate impacts on the electricity networks and establishes a solid basis for reporting under the Adaptation Reporting Power in the Climate Change Act 2008 - see

www.defra.gov.uk/adaptation

Climate change Businesses Case studies

Impacts on Energy

The Met Office has been working closely with UK energy companies on EP2, an innovative project looking at the effects of climate change on the energy industry. This project is the first of its kind, being sponsored by an entire sector. It has resulted in companies across the industry forming a new energy and climate change group where they will share knowledge, experiences and best practice.

Energy project background

In 2006 the Met Office and three leading energy companies launched a pioneering scoping study into climate change and its potential impacts on the UK energy industry. The study was the first nationwide attempt to identify how climate change will affect energy generation; distribution and transmission, and demand. As well as initial indications on how climate change could impact the industry over the next century, it also identified areas where further research was required.

Following the scoping study an industry-funded project (EP2) was set up, involving 11 UK energy companies, focusing on the priorities identified by the earlier study.

Supported by climate scientists, experts from the industry worked together to understand their precise requirements and developed practical applications and business strategies for a changing world.

Energy project developments

So far EP2 has:

- Developed innovative new techniques that apply climate models to energy applications so that the industry is better placed to adapt to climate change
- Investigated future wind resource, enabling the industry to understand the continued uncertainty of future wind power. This will assist risk management and investment decisions
- Modelled future soil conditions and their impact on cables. This has helped companies understand the cost and benefits of installing cables for a more resilient future network
- Built a tool to enable UK coastal and marine sites of interest to be screened to assess if sea level rise should be considered in more detail
- Investigated how the urban heat island effect may change in the future, so that network companies can develop plans for their infrastructure in cities
- Produced guidance to help make best use of public information on climate change, such as the United Kingdom Climate Impacts Programme new scenarios of climate change
- Delivered new site-specific climatologies of temperature, wind speed and solar radiation that account for climate change, so that decisions can be based on realistic climate expectations
- Examined the relationship between historic weather patterns and network fault performance, with a view to developing a tool to predict future network resilience.

Energy project findings

Among the findings from the project were:

- With a few exceptions, such as the thermal ratings of equipment and apparatus, there is currently no evidence to support adjusting network design standards. For example, existing design standards for overhead line conductors do not require change
- The type of risk to transformers will be affected. Temperature thresholds will be exceeded more often and there will be more hot nights in cities
- Soil conditions will change higher temperatures and seasonal differences in soil moisture are expected. Future conditions could be included in cable rating studies by increasing average summer soil temperatures in the models by approximately 0.5 °C per decade

- The output of thermal power stations (and in particular combined cycle gas turbines) could be suppressed, with higher air temperature meaning lower air density and lower mass flow. Conditions at each location should be considered, especially during redesign or new build and, if appropriate, adaptation planned
- Historical climatologies are no longer valid because climate is not stationary. The new climatologies that take account of climate change are already being adopted and will improve demand forecasting and planning out to 10 years ahead
- Wind resource is uncertain and understanding future resource represents a significant challenge. Although we don't yet have the answers, this project has highlighted possible strategies for improving our knowledge.

Energy project next steps

An energy and climate change industry group is to be set up. This group will:

- Share the latest science and its application to business
- Meet to discuss latest innovations and developments in climate science with leading experts
- Share thoughts and ideas on areas of common interest as companies work to adapt to climate change.

4.5 WPD Smart Network trial

The modification of existing pole and ground mounted HV/LV distribution s/s to capture the core electrical measurement parameters and communicate these back to central WPD server(s), including WPD ENMAC scada system, provides a platform for roll out of active network management or so called Smart Grids.

UK Government (and Opposition) envisage rapid need for evolution into such Smart Grids; the most recent being the announcements by Energy Minister, Ed Milliband on 15th July 2009, and the launch of the Low Carbon Transition Plan -

www.decc.gov.uk/en/content/cms/publications/lc_tran_plpan/lc_trans_plan.aspx

An extract from the report is shown below -

Box 10 Key elements of a UK smart grid

- Improved information for electricity consumers, notably through smart meters, to allow them to manage their energy use (and hence energy bills) more effectively.
- Facilitating demand management, providing data to technologies in homes and buildings that can regulate electricity use (e.g. encouraging electric cars to recharge when there is "surplus electricity" available on the system).
- Enabling individuals and businesses to sell electricity into the network as well as buying from it, through microgeneration and on-site technologies.
- Enhanced monitoring and information flows for network operators, allowing them to make more efficient decisions about where energy flows across the network on a real time basis. This is likely to be particularly important

with increasing levels of intermittent renewable generation on the system. A greater use of energy storage would also increase the need for smarter information flows for network operators on energy storage supply and timing of its use.

- Use of a range of technologies including advanced communications and information management systems, intelligent metering, demand side management, and storage. Many of the technologies to enable such capability are already available, but have not yet been integrated together in large scale demonstrations and the actual mix that is deployed will depend on their feasibility.
- More optimal usage of the whole network in meeting demand, which could limit the need for more reinforcement of the grid.

5.0 COMMENATARY ON PREVIOUS PROJECTS

- 5.1 In respect of previous EATL STP projects, examples of WPD adoption of outputs include -
 - Use of new conductors for overhead lines (case study reported last year)
 - Alternatives to wood poles study was used to inform response to EU Biocides Directive
 - Long rod polymeric insulators used in WPD specification
 - Surge arrester study used in WPD specification
 - High resolution imaging of tower lines WPD policy revised to use technique as part of Condition Based Risk Management, which is allied to future Ofgem condition reporting requirements
 - COST 727 ice loading study will inform future o/h line design requirements
- 5.2 There have been very many outputs from the Supergen work, and a few recent topical examples are -
 - "machine learning" to identify equipment health degradation patterns from within multiple data streams that individually do not clearly indicate a trend, and chromatic analysis techniques.
 - Findings on the impact of power quality harmonic content of measured partial discharge activity
 - Tapchanger degradation measurement techniques
 - Maintenance of synchronism of islanded generation
 - Early identification of leaks from fluid filled cables
 - Partial discharge sensor development
 - Insulation paper degradation on power transformers

For a fuller list of papers - please see the Supergen Amperes website

www.Supergen.amperes.org.uk

6.0 FORWARD VIEW OF 2009/10 PROJECTS

- 6.1 In addition to existing committed projects from 2008/9 that run into 2009/10 WPD currently anticipate engagement in collaborative projects -
 - Met Office research on climate change impacts on network resilience
 - ADAS/ Bartlett research on use of tree growth retardants (already widely used on fruit trees but not elsewhere)
 - Work by the Centre for Sustainable Electricity and Distributed Generation
- 6.2 Proposals are being developed for a Supergen renewal bid to EPSRC, and WPD will consider participation when EPSRC make a decision and the content is more fully determined.

7.0 PRO-FORMA REPORTS

WPD South West Summary report of IFI Project activities year ending March 31st 2009

Number of active IFI projects	13
NPV of costs and anticipated benefits from committed IFI projects	NPV of costs - £ 256,972 NPV of benefits - £ 640,247 Positive NPV - £ 383,275 (rounded from information on following sheets)
Summary of other benefits anticipated from active IFI projects	Enhanced asset health condition knowledge to inform future safety, reliability and replacement policy. Provision of timely expert information on lifetime carbon impact of overhead line and underground cable to inform current DPCR5 debate on loss reduction and carbon footprints. Provision of timely expert information on climate change impacts on electricity network assets to inform forward investment planning and debate, and respond to UK Government Adaptation Reporting requirements. Reductions in CMLs through improved reliability, resilience and speed Maintaining or improving safety to the public and staff. Reduction of environmental risk of oil loss from plant and cables. Move to roll out of widespread active network management capability on HV/LV substations in support of UK Government low carbon policy.
Total expenditure to date on IFI projects	£0.726 M up to end March 2009
Benefits actually achieved from IFI projects to date	Estimated £2.5M avoided capital cost through use of a novel overhead line conductor, deployed for the first time at 132kV, and, following tower strength assessments to BS EN 50341, needing minimal structural strengthening of existing towers. Knowledge on life cycle assessment carbon impact of 11kV o/h line and u/g cable has already proved valuable in DPCR5 discussion with Ofgem in EWG. The Climate Change impact collaborative Met Office project has provided an authoritative, fundamental, consistent industry wide basis for assessing future network rating impacts on the basis of best available forward projections. This work now facilitates debate on future investment planning. Economic Charging Method for Electricity Distribution Networks completed - Ofgem consulted and approved and now in use. Remote updating of switching schedules rolled out and delivering anticipated benefits in switching time. Changes to equipment specification. Use of high resolution imaging for tower health indices adopted into policy. Knowledge acquisition and transfer. Development of muti-mode condition monitoring techniques.

Regulatory report for DG incentive, RPZs and IFI Reporting year 2008/09 Western Power Distribution - South West			
Innovation Funding Incentive £M			
IFI carry forward (£m) 0.525			
Eligible IFI expenditure (£m) * 0.154			
Eligible IFI internal expenditure (£m) 0.039			
Combined distribution network revenue (£m) 207.7			
* includes internal expenditure			

WPD Wales Summary report of IFI Project activities Year ending March 31st 2009

Number of active IFI projects	13
NPV of costs and anticipated benefits from committed IFI projects	NPV of costs - £ 256,972 NPV of benefits - £ 640,247 Positive NPV - £ 383,275 (rounded from information on following sheets)
Summary of other benefits anticipated from active IFI projects	Enhanced asset health condition knowledge to inform future safety, reliability and replacement policy. Provision of timely expert information on lifetime carbon impact of overhead line and underground cable to inform current DPCR5 debate on loss reduction and carbon footprints. Provision of timely expert information on climate change impacts on electricity network assets to inform forward investment planning and debate, and respond to UK Government Adaptation Reporting requirements. Reductions in CMLs through improved reliability, resilience and speed Maintaining or improving safety to the public and staff. Reduction of environmental risk of oil loss from plant and cables. Move to roll out of widespread active network management capability on HV/.
Total expenditure to date on IFI projects	£0.726 M up to end March 2009
Benefits actually achieved from IFI projects to date	Knowledge on life cycle assessment carbon impact of 11kV o/h line and u/g cable has already proved valuable in DPCR5 discussion with Ofgem in EWG. The Climate Change impact collaborative Met Office project has provided an authoritative, fundamental, consistent industry wide basis for assessing future network rating impacts on the basis of best available forward projections. This work now facilitates debate on future investment planning. Economic Charging Method for Electricity Distribution Networks completed - Ofgem consulted and approved and now in use. Remote updating of switching schedules rolled out and delivering anticipated benefits in switching time. Changes to equipment specification. Use of high resolution imaging for tower health indices adopted into policy. Knowledge acquisition and transfer. Development of muti-mode condition monitoring techniques.

Regulatory report for DG incentive, RPZs and IFI Reporting year 2008/09 Western Power Distribution - South Wales			
Innovation Funding Incentive £M			
IFI carry forward (£m)	0.428		
Eligible IFI expenditure (£m) * 0.154			
Eligible IFI internal expenditure (£m) 0.039			
Combined distribution network revenue (£m) 169.5			
* includes internal expenditure			

Eligible IFI Internal costs

The 08/09 IFI year has an abnormal % of internal costs for the following reasons -

 The current, large, Amperes Supergen project external costs were fully paid prior to the start of the IFI year, but the project has continued with a number of meetings and seminars. WPD have taken a lead role in being one of three network representatives

(WPD, NG and SPPS) on the Project Executive behalf of the other participating network operators

- WPD have taken Chair of EATL STP Module 4, resulting in increased internal costs representing other DNO partners
- Costs have been met in 08/09 on agreed projects on resilience impacts of climate change and use of tree growth retardants, in advance of the external charges arising in the 09/10 IFI year.
- The smart networks trail was undertaken very rapidly to determine if a larger project proposal should be made to Ofgem during the DPCR5 submissions. It utilised WPD resource.

The overall internal / total IFI % from 2004/05 to 2008/9 inclusive, encompassing the above, is 16%.

Individual project reports on the following pages

Please note that the financial data stated in the following pages are the totals for WPD South West and WPD South Wales. This data has been apportioned 50/50 in the above summary sheets.

Project Title	Strategic Technology Programme Overhead Network Module 2			
Description of project	A DNO research & development collaboration hosted by EA Technology			
Expenditure for financial year	Internal £5,357 External £43010 Total £48,367	Expenditure in previous (IFI) financial years	Internal £2,736 External £43,010 Total £45746* NB only some of the projects span both 07/8 and 08/9	
Project Cost (Collaborative + external + [DNO])	£310,102 + DNO Projected 09/10 costs		Internal £2,800 External £45,629 Total £48429	
Technological area and / or issue addressed by project	07/8 and 08/9 £310,102 + DNO Projected 09/10 costs Internal £2,800			

S2154_1 Experimental investigation of novel conductors - Stage 1: Icing;				
	S2156_1 Build Three Prototype Field Pole Leakage Current Detectors;			
	S2159_1 LV shrouding - review of current practices and standards			
	S2139_1 LV shibiding - review of current practices and standards			
	Projects Still In Progress (March 09):-			
	S2110_4 Extend OHRAT to include User Defined Covered Conductor			
	S2136_4 & 4A European Project COST 727: Measuring and forecasting atmospheric icing on structures, including Czech ice meter trial;			
	S2143_3 Develop in-situ degradation monitor for AI OHL conductors - Stage 3 Instrument Development;			
	S2147_2 Increa single Hi-mass S		of CCs to 20%UTS u	sing multiple std or
	Ū		es - Stage 2: Erection	and fitting trials on
	-		on of novel conductors	at Deadwater Fell
	Ū		kV wood pole lines;	
	Updated information can be found at:- https://www.stp.uk.net			
				Overall Project
Type(s) of innovation	e.g. Incremental,	Project Benefits Rating	Project Residual Risk	Score
involved	Tech Transfer, Significant, Radical	15	-9	24
	Projects in this r	nodule will significa	antly increase the safe	ety and reliability of
	-	C C	asset life may also be e	
			,	
	If these projects are technically successful and the findings and			
	recommendations from the projects are implemented, then the projects will			
	potentially enable each DNO member of the programme to gain benefits			
Expected Benefits of	including:			
Project	_	Cost effective and early identification of damaged insulators and		
			which if not address	0
	faults;	3 3 4 1 1 1		
		e levels of prematu	ure failure of assets a	nd so avoid of risk
			damage to property a	
		ad lines;		
		,		

	Avoid redesign, reconstruction or refurbishment of overhead lines		
	where this is driven by a perceived need to increase ratings or		
	strengthen lines, and is required to conform with existing		
	standards but which may be unnecessary;		
	Co-operation between European countries in the development of		
	forecasting methods of atmospheric icing and for the exchange of		
	forecasting tools;		
	Comparison of new covered conductor with known performance of		
	older types		
	• Extend the service life of towers and reduce potential levels of		
	tower failures;		
	Review alternatives to wood poles;		
	Reduce lifetime costs by the appropriate use of alternative		
	materials;		
	Give Members a better understanding of novel conductors for		
	new-build or re-conductoring 132kV wood pole lines that gives		
	lower capital cost, minimum visual impact, environmental		
	acceptance than other methods of improving power transfer.		
Expected Timescale to	Range 2-5 years - Duration of benefit Range 2-10 years -		
adoption	dependent on project once achieved dependent on project		
	Project NPV = (PV		
Probability of Success	Range 10-50% - Benefits – PV Costs) £64,624		
	dependent on project x Probability of Success		
	A number of STP Projects are at an early stage and the project cost may		
Potential for achieving	not always reflect the likely full costs of implementation. These will be		
expected benefits	identified providing the outcome of the early stage is positive. However, STP has delivered a number of notable innovations since its inception.		
	· · · · ·		
Project Progress toMost projects or project stages started in the module during 08March 09been completed, but some projects span more than one year.			
Collaborative Partners	Other DNOs		
R&D Providers	EA Technology		
l	1		

Project Title	Strategic Technology Programme: Cables Module 3. (2008/09)			
Description of project	A DNO research & development collaboration hosted by EA Technology			
Expenditure for financial year	Internal £2210 Expenditure in External £53,681 previous (IFI) fina Total £55 891 years		Internal £2142 External £52116 Total £54258* NB only some of the projects span both 07/8 and 08/9	
Project Cost (Collaborative + external + [DNO])	£375,767 + DNO Projected 09/10 costs:		Internal £,2,300 External £55,291 Total £57591	
Technological area and / or issue addressed by project	07/8 and 08/9 £375,767 + DNO Projected 09/10 costs: External £55,291			

	 Projects Still In Progress (March 09):- S3132_16: CRATER annotation; S3144_2: Comparison of processes for the treatment of redundant fluid filled cables: Comparative field trials; S3151_2 & 3 Understanding and controlling thermo-mechanical forces in cables systems: Modelling of thermo-mechanical forces in cable systems; S3155_1 Trial testing of triplexed cable in plastic ducts; S3157_1 Partial discharge testing of MV cable systems to provide asset risk management data; S3164_1: Develop fluid filled cable design tool; S3165_1: Performance ageing tests on polymeric terminations S3166_1 & 2: Performance of cold- and heat-applied accessories under resin: Assessing interaction between resin and semi-conducting layer; 			
Type(s) of innovation involved	e.g. Incremental, Tech Transfer, Significant, Radical	Project Benefits Rating 13	Project Residual Risk -8	Overall Project Score 21
Expected Benefits of Project	Radical 13 13 10 21 If the projects are technically successful and the findings and recommendations from the projects are implemented, then the projects will potentially enable each DNO Member of the programme to gain the following benefits, including: offset future increases in CAPEX and OPEX; CI/CML savings per connected customer; Reliable, safe and easy to use method of detecting excess moisture in paper insulation of cables; Reduce excavation required in locating leaks from fluid-filled cables, reduce the times and costs of leak location, and also reducing outage times; Reduce cable purchase costs; Reduce design costs. Increased safety of staff and public by reducing the number of accidents / incidents. 			

Expected Timescale to adoption	Range 1-3 years - dependent on project	Duration of benefit once achieved	Range 2-10 years - dependent on project
Probability of Success Range 15-50% - dependent on project		Project NPV = (PV Benefits – PV Costs) x Probability of Success	£87,318
Potential for achieving expected benefits	A number of STP Projects are at an early stage and the project cost may not always reflect the likely full costs of implementation. These will be identified providing the outcome of the early stage is positive. However, STP has delivered a number of notable innovations since its inception.		
Project Progress to March 08Most projects or project stages started in the module been completed, but some projects span more than one			
Collaborative Partners	Other DNOs		
R&D Providers	EA Technology		

Project Title	Strategic Technology Programme: Substations Module 4. (2008/09)			
Description of project	ct A DNO research & development collaboration hosted by EA Technol			
Expenditure for financial year	Internal £ 5698 External £39,223 Total £ 44921 Expenditure in previous (IFI) financial years External some span		Internal £ 5880 External £38080 Total £ NB only some of the projects span both 07/8 and 08/9	
Project Cost (Collaborative + external + [DNO])	£313,784 (08/09) Projected 09/10 costs: Internal £6,000 £323,200 External £40,400		External £40,400	
Technological area and / or issue addressed by project	£313,784 (08/09) Projected 09/10 costs: External £40,400			

	Projects Still In Progress (March 09):- S4164_5: Tap changer monitor stage 5; S4178_2: Impedance Testing of Substation Batteries; S4185_4: European AM Forum Membership 08/09; S4221_2: Out Of Phase Modelling Report; S4224_1: X/R Extrapolation of 12kV Vacuum circuit Breakers; S4226_1: Environmental Corrosion, Specification, Testing of Plant & Equipment; S4230_1: Optimisation of Operational Support and Response for Electrical Plant & Equipment; S4236_1: Aquagen recombination system; S4245_1: Switchgear - Effect of Low Power Factor Switching. (Joint Investigation with STP5: S5181_1).						
	Updated informa	ation can be	found	at:- https://www.s	tp.uk.	net	
Type(s) of innovation	e.g. Incremental, Tech Transfer,	Project Be Ratin		Project Residu Risk	ıal	Overall Project Score	
involved	Significant, Radical 14			-9		23	
Expected Benefits of Project	 If the projects are technically successful and the findings and recommendations from the projects are implemented, then the projects will potentially enable each DNO Member of the programme to gain the following benefits, including: offset future increases in CAPEX and OPEX; CI/CML savings per connected customer; Preventing disruptive failures of oil-filled equipment, tapchangers, earth switches increasing safety and avoid unnecessary scrapping of serviceable components will alleviate environmental impact. Liaison with European Utilities to share new technology and failure modes; Increased safety of staff and public by reducing the number of accidents / incidents. 						
Expected Timescale to adoption	Range 1-5 ye dependent on			ation of benefit ice achieved		ange 2-8 years - endent on project	

Probability of Success	Range 10-100% - dependent on project	Project NPV = (PV Benefits – PV Costs) x Probability of Success	£67,777			
Potential for achieving expected benefits	A number of STP Projects are at an early stage and the project cost may not always reflect the likely full costs of implementation. These will be identified providing the outcome of the early stage is positive. However, STP has delivered a number of notable innovations since its inception.					
Project Progress to March 08	Most projects or project stages started in the module during 08/09 have been completed, but some projects span more than one year.					
Collaborative Partners	Other DNOs					
R&D Providers	EA Technology					

ENA R&D Programme 2008-09

The Energy Networks Association (ENA) represents all UK DNOs & National Grid. The project listed below has been initiated by the ENA R&D Working Group and has been funded through the IFI.

Description of project	Further investigation into the potential impacts of climate change on network resilience - Feasibility Phase							
Expenditure for	External	£ nil in 0						
financial year	Internal £ 445							
,	Total	£ 445						
Expenditure in	External	£						
previous (IFI) financial	Internal	£						
years	Total	£ Nil						
Total Project Costs (Collaborative + External + Company)	External (nil to £ 445	Projected 2009/10 External £ 33						
Technological area and / or issue addressed by project	Future reliability of the distribution and transmission network is important to ensure continuity of service and to minimise unforeseen costs. This work will investigate the potential impacts of a changing climate on future network fault numbers.							
Type(s) of innovation	Incremental and Significant	Project Benefits Rating		Project Residu Risk	al Overall Project Score			
involved	innovation types are 12 involved.			-9	21			
Expected Benefits of Project	The result of this work would inform Licensee's strategy with regard to IIP performance incentives which impact on Price Controls, system planning studies and operational preparedness for extreme weather events. For example, the benefits of intervention options such as tree cutting and installation of equipment such as lightning arrestors will be influenced by how fault numbers are expected to change. The study will also inform a debate as to whether the industry Security and Quality of Supply Standards should be adjusted to accommodate climate change.							
Expected Timescale to adoption	2012			tion of benefit achieved	20 years			
Probability of Success	75%		Project NPV (Present Benefits - Present Costs) x Probability of Success		£ 8,000			
Potential for achieving expected benefits								

Project Progress March 2009	 The first workshop was held on the 22nd April 2009 with representatives from each energy company, the Met Office and the ENA to discuss and agree how the industry would utilise and benefit from further network resilience research. To facilitate this discussion a number of questions were provided and each was considered on 3 different timescales: 5 days, up to 10 years and up to 50 years. Using the information obtained during the workshop, we outline the optimum user requirements for each time scale below. <u>5 days:</u> An operational fault risk alert system, including high spatial resolution (license/county level at minimum), and at least 3 days warning with 6 hourly updates. Up to 10 years & 50 years: A report and interactive tool including changes in number of days where fault numbers are less than the exceptional event threshold, information provided seasonally at a license/county level, and all associated uncertainties quantified. The user requirements for the two longer time scales (up to 10 and 50 years) were found to be very similar and have consequently been combined. The time scales will, however, be dealt with separately when considering whether the requirements can be met since differences and allow a standardised UK representation to be analysed. During May and June 2009 months work will be undertaken to carry out the feasibility study. During this time we will carry out a literature review distantive scale availability for fault and climate variables and determine how the user requirements. Literature review of similar work. Data availability (for both fault and climate). Assessment of the Met Office's capabilities and how the user requirements. Literature review of similar work. Data availability (for both fault and climate). Assessment of the Met Office's capabilities and how the user requirements could be met. Particular fo
Collaborative Partners	National Grid, Scottish Power Energy Networks, Scottish and Southern, ENW, Western Power Distribution, Central Networks, CE Electric & EDF Energy Networks.
R&D Providers	Met Office

ENA R&D Programme 2008-09

The Energy Networks Association (ENA) represents all UK DNOs & National Grid. The project listed below has been initiated by the ENA R&D Working Group and has been funded through the IFI.

					act of lower voltage	
Description of project				age 'hot zones', ion earth system	and to measure the s.	
Expenditure for	External	£ 2250		,		
financial year	Internal	£ 392				
	Total	£ 2642				
Expenditure in	External	£ 4074				
previous (IFI) financial	Internal	nal £				
years	Total	£				
Total Project Costs (Collaborative + External + Company)	External £ 27,00	00	costs	ected 2009/10 s for pany's	External £ 7125 (Proposal only) Internal £ Total £0.00	
Technological area and / or issue addressed by project	All designs for earthing systems consider the effects of touch and step potentials under fault conditions. However the quantity of concern is actually the current flowing through a human body when in contact with metalwork subject to this potential and the time the current flows for. An electrode simply sited in soil which has a surface potential cannot be regarded as presenting the same hazard as metalwork with a direct metallic connection to the earth fault current return path. However there exists at this time no methodology for assessing the either the hazard posed by such an earth electrode or the possible effects of the earth when connected to a distributed system on the ROEP contours. This project will if successful determine these effects and provide a means to provide cost effective safe earthing systems without the need for extensive separations between HV and LV electrodes which in a PME system may be impractical to achieve and maintain.					
Type(s) of innovation	Incremental and Significant	Projec Benefi Rating	ts	Project Residu Risk	al Overall Project Score	
involved	innovation types are involved.	8		-5	13	
Expected Benefits of Project	The project will determine the effects of LV earth systems on HV systems. The results of this should determine the means to provide cost effective, safe earthing systems without the need for extensive separations between HV and LV electrodes which in a PME system may be impractical and costly to achieve and maintain.					
Expected Timescale to adoption	2 years		Duration of benefit once achieved 10 years			

Probability of Success	50%	Project NPV (Present Benefits – Present Costs) x Probability of Success	*				
	High. The results from tests and simulations can be used to propose a recommended procedure for measuring transfer potential between HV and LV systems, suitable for inclusion in a DNO policy document.						
Potential for achieving expected benefits	No NPV benefits are currently claimed by WPD in the light of European debate over related EN Standard, the consequence of which would be to increase separation, not decrease it. However the outputs of this research will be used to influence those EN proposals, as mentioned below in the ENA comment.						
	During the first four phase project team were able to (including analysis at two system interacts with the electrically separated HV new and help to explain w LV equipment when there close by. It was possible measured results at the two considerably ore complicaterms of their earthing requ	o confirm by calculation o live substations) the external potentials creations installation. The find why there is so little events is an HV earth fault to quite closely match wo live test substations the that the vast major	on and measurement at the LV electrode eated by a close, but lings are completely idence of damage to c on equipment quite h the theoretical and s but they were each				
Project Progress March 2009	 Because the finding are so new and unexpected there is a need to carry out the following: (1) Theoretical and practical measurements at a simple substation whose earthing arrangements match what is or should be done at the majority of sites throughout the UK. (2) Use computer models of similar and improved earthing arrangements for the same type of substation to develop several case study examples. These will consider changes to the electrode orientations, separation distances, electrode depths etc. Not only will these help explain the effects, but they will also be used to develop more appropriate earthing strategies rules and support equations. The case studies will be documented in a manner that permits publication. (3) Make the findings known in the UK, Europe and Internationally. The main reason for this is to ensure that the new practices become established and for this they must be reflected in the standards that are presently being developed. (4) Prepare text describing a method for calculating the transfer potential for inclusion in ENA TS 41-24 						
	The work set out above for phase 5 is anticipated to take 15 months to complete.						
Collaborative Partners	Scottish Power Energy Western Power Distribution Energy Networks.						
R&D Providers	Strategy & Solutions						

ENA R&D Programme 2008-09

The Energy Networks Association (ENA) represents all UK DNOs & National Grid. The project listed below has been initiated by the ENA R&D Working Group and has been funded through the IFI.

Description of project				velop guidance f	or long	g underground
Expenditure for	cable harmonic External	£ 8997	e mode	elling.		
financial year	Internal	£0997				
interioral your	Total	£ 8997				
Expenditure in	External	£				
previous (IFI) financial	Internal	£				
years	Total	£ 0.00				
Total Project Costs (Collaborative + External + Company)	External £62982.23 (Exc	Projected 2009/10 External £				
Technological area and / or issue addressed by project	The report covers the detailed modelling of cable and overhead line components. Particular attention is paid to cable models appropriate for distribution networks, as this is was the initial objective of the project and literature on modelling of cables is not as widespread as that for other items of equipment.					
Type(s) of innovation involved	Incremental and Significant innovation	Benefi Rating		Project Residu Risk	al O	overall Project Score
Expected Benefits of Project	types are involved. The study objective is the development of an ETR type guidance note to supplement G5/4 (2001) and help reduce and simplify modelling requirements for relatively small capacity 33kV and 11kV connections					
Expected Timescale to adoption	2 years	Duration of benefit				
Probability of Success	75%		Project NPV (Present Benefits – Present Costs) x £ 6,000 Probability of Success			00
Potential for achieving expected benefits	The frequency dependent behaviour of overhead lines and cables was assessed. A sensitivity analysis has shown that simplified models and power frequency models may be used to represent the harmonic behaviour of a single core conductor overhead line and cable with a reasonable degree of accuracy over the frequency range assessed.					

Project Progress March 2009	An interim report has been issued following the first section of work on the cable modelling which addresses the technical cable modelling issues on the original project brief. The extension to the brief to stage 2.5 as it is called is the focus of the final report which is taking the time and will not be available until the meeting of the working group on the 9 th of July 2009.
Collaborative Partners	ScottishPower Energy Networks, Scottish and Southern, ENW, Western Power Distribution, Central Networks, CE Electric & EDF Energy Networks.
R&D Providers	TNEI

ENA Fault Level Monitor Project

Project Title	Fault Level Monitor Project							
Description of project	An ENA co-ordinated project the objective of which is the development of an on-line instrument that can successfully measure / estimate fault level on a distribution network with repeatability and reliability.							
	Internal £ nil		Evnon	diture in	Interna	al £2,400		
Expenditure for financial year	External £1,225			Expenditure in previous (IFI)		al £8,000		
iniancial year	Total £1225		financi	al years	Total	£10,400		
Project Cost					Interna	al £2,000		
(Collaborative +	£190,000		Project 09/10 (Extern	al £30,550		
external + [DNO])			09/100	20313	Total	£32,550		
Technological area and / or issue addressed by project	The device will connect to the network, and establish the network source impedance from small-scale disturbances / perturbations resulting from transformer tap changer operation, etc. This impedance can accurately be correlated to a true network fault level for that location, providing near real-time information to network control and planning engineers alike.							
Type(s) of	Incremental	Incremental Significant T				Radical		
innovation involved	No	Yes No)	No		
Expected Benefits of Project	 and design distribution network project are seen to be: Provide a real-time and Accurately take into a Motors); Facilitate the connectivistandardised methodolo Enable an ongoing assorbed generation to be made; Provide reassurance to 	 Provide a real-time and consistent estimation of fault level Accurately take into account all connected network elements (e.g. Motors); Facilitate the connection of distributed generation by providing a standardised methodology for the assessment of network fault levels Enable an ongoing assessment of the effects of connected distributed generation to be made; 						
Expected Timescale to adoption	3 years Duration of benefit once achieved					10 years		
Probability of Success	25%							
Project NPV	(Present Benefits x Probability o	of Success	s) - Pres	ent Costs	;	£92,045		

Project Progress to March 09	The results of the tests carried out at NaREC show that the EA Technology Fault Level Monitor is capable of delivering an assessment of both the source and motor infeed elements of fault level. The accuracy of the assessment can be delivered with the tolerance levels (+/- 5%) which were set down by ENA OSG sub-group. However, it should be noted that the instrument is based on a hardware platform which is obsolete and no longer supportable. Stage 2 of the previous work carried out in conjunction with the University of Strathclyde, was intended to develop a new Fault Level Monitor. Consideration should be given to the need to carry out further development of a new platform to collect and analyse the disturbance data.
Potential for achieving expected benefits	The confidence limits in the case of the induction motor infeed assessment were affected by the relatively low number of recorded disturbances and also appear to have been affected by the 'two-stage' nature of many of the disturbances. Further work should be undertaken to examine the effect of the load response of non-linear static loads on the estimate of fault level contribution from induction motors. A PhD studentship at the University of Strathclyde the PNRA to explore this issue is being advertised.
Collaborative Partners	National Grid, Scottish & Southern Energy, CE Electric UK, Electricity North West, Central Networks, Western Power Distribution, EDF-Energy Networks
R&D Providers	University of Strathclyde, EA Technology

Radiometric Arc Fault Location

Project Title	Radiometric Arc Fault Location					
Description of project	Applied research, locations on overh produced from an a	ead lines	from the			
Expenditure for financial year		213 ,950 ,163	Expendit previous financial	(IFI)	Internal Externa Total	l £ £ nil
Project Cost (Collaborative + external + DNO	£292,000		Projected costs		Internal Externa Total	,
Technological area and / or issue addressed by project	 The principle of the technology is: There is a correlation between RF discharges and network faults on overhead lines with the RF signal being picked up by a radio antenna up to around 70km away If antennae are spread across the network, a mesh is formed - in a similar manner to the GSM network If a fault can be accurately clocked, triangulation can be used from a number of base stations to give an approximate geographic location (accuracy ~300m) and linked to GIS / SCADA data to give a more accurate fault location. 					
Type(s) of	Incremental	Signi	ificant	Technolog substituti		Radical
innovation involved	No	Y	es	No	No	
Expected Benefits of Project	If successful, the use fault locations on all					accurately locate
Expected Timescale to adoption	3 Years		uration of b chieved	penefit once		10 Years
Probability of Success			25	%		
Project NPV	(Present Benefits x	Probabilit	y of Succe	ss) – Present	Costs	£45,787
 Project Progress June 09 3 of the 4 monitoring sites have been brought into service: Shotts - Dec 2008; Kirkintilloch and Bellshill Feb 2009, with Dealain House to be brought online in May 2009 (some equipment problems are delaying this last site being commissioned) All 3 are collecting large amounts of radiometric data, A number of correlations have been made between SP fault records and the data collected 						
Potential for achieving expected benefits	The project has achieved a degree of success already and the analysis of the data collected so far is ongoing. As the project has progressed and more 'in the field' experience has been gathered it has become possible to make changes to the equipment setup which allow the sensitivity of the equipment to be increased and data to be gathered more quickly thus increasing the chances of success.					
Collaborative Partners	Western Power Dis Electricity North We	est, CE Ele			ergy, Cer	ntral Networks,
R&D Providers	University of Strath	clyde				

Impact of Climate Change on the UK Energy Industry

Project Title	Impact of climate cl	han	ge on the UK	Energy	Industry	/	
	In 2006 the Met Office carried out a scoping study on the impacts of climate change on the UK energy industry. The report was the result of a collaboration between E.ON UK, EDF Energy, National Grid and the Met Office Hadley Centre to scope the impacts of climate change on the UK energy industry.						
Description of project	This Phase 2 project was industry-funded; it involved 11 UK energy companies and was undertaken by the Met Office. It focussed on the priorities identified by the earlier scoping study.						
	During the project new tools and methods required to understand the impact of climate change on the energy industry were developed and new data resources designed to address gaps in underpinning information were produced.						
Expenditure for			(fully paid in :	2007/8)			
financial year		212 212	-				
Expenditure in previous (IFI) financial years	External £29,306 Internal £ 2,668 Total £31,974						
Total Project Costs (Collaborative + external + EDF Energy)	£ 554,000 Projected 2009/10 costs			9/10	Externa Interna Total		
Technological area and / or issue addressed by project	The project has been run as a series of work packages (WP). Those WPs relevant to distribution and transmission are described below. WP1 - Modelling Energy Impacts. Models created to assess impacts of climate change on Electricity Demand, Conductor Performance, Transformer Performance, Cables, Overhead Network, and Wind Power. WP2 - Guidance for the Energy Industry on the use of the United Kingdom Impacts Programme new scenarios of climate change (UKCIP08). UKCIP08 is planned for released in November 2008. WP3 - Climate Models and Wind Projections. Investigating methods of including estimated of future wind resource in wind farm viability. WP4 - Climate Change and Underground Cable Performance. Modelling future soil conditions to increase understanding of the impacts of climate change on cables. WP6 - Climate change and the Urban Heat Island Effect. Producing information on the urban heat island for use when panning infrastructure in cities. WP7 - Final reporting and presentation of the results to each company.						
	WP8 - Predicted cli Incremental Significant		Project Benefits	Pro	oject idual	Overall Project	
Type(s) of innovation involved	Technological		Rating		isk	Score	
	substitution Radio	cal	13.6	-2	2.0	15.6	

Expected Benefits of Project	 The expected benefits of project are: For the elements assessed an understanding of the sensitivity to climate change and key meteorological drives of the impacts. This will highlight priorities for adaptation. New models for projecting impacts suitable for inclusion in climate models or for application to climate model output. Guidance on the application of climate models to energy industry applications which should results in appropriate use of climate information by Networks. New information on urban heat islands and climatologies for the next 10 years to assist infrastructure design and planning. 				
Expected Timescale to adoption	Year 2011	Duration of benefit once achieved	20 Years		
Probability of Success	50% Project NPV (Present Benefits - Present Costs) x £ 100,000 Probability of Success £ 100,000				
Potential for achieving expected benefits	There is a good chance of achieving the expected benefits. This was a year long project that finished at the end of May on time and to budget and specification. Project outputs and reports are now available via the project website. The project has highlighted some areas of Networks where no change to existing practice is required because of climate change and other areas where adaptation may be beneficial. The new models that have been developed and used in this project will be a useful legacy. The new information produced specifically for the energy industry has been demonstrated to have significant benefits over what was available previously.				
Project Progress March 2008	In March 2008 the status of the project work packages was as follows: WP1 - Complete WP2 - 50% Complete WP3 - Complete WP4 - 90% Complete WP6 - 90% Complete WP7 - 50% Complete WP8 - 80% Complete Overall the project was 75% complete.				
Collaborative Partners	All the network operators and most energy supply businesses				
R&D Provider	Met Office				

SUPERGEN - AMPERES

Project Title	Supergen V - AMPerES							
Description of project	collection This fifth c	Supergen is an EPSRC strategic partnership programme incorporating a collection of projects across a number of UK academic establishments. This fifth call, Supergen V is entitled Asset Management & Performance of Energy Systems (AMPerES).						
	Internal	£6,48	87	Expenditure in		iternal		£13958
Expenditure for financial year	External	£ni	I	previous (IFI)	E	xternal		£100,000
interiolal your	Total	£648	37	financial year	rs T	otal		£113958
Project Cost						iternal		£4,000
(Collaborative + external + SP-	£ 2,80	00,000		Projected 08, costs for WP	D E	xternal		£nil
EN)						otal		£4,000
Technological area and / or issue addressed by project	WP 2: Enh WP 3: Ada WP 4: Infra WP 5: Age	 WP 1: Programme delivery, outreach and implementation WP 2: Enhanced network performance and planning WP 3: Adaptable protection and control techniques WP 4: Infrastructure for reducing environmental impact WP 5: Ageing mechanisms WP 6: Condition monitoring techniques 						
Type(s) of innovation	Radic	RadicalProject Benefits RatingProject Residual RiskOverall Project Score						
involved	involved							
Expected Benefits of Project	 The expected aims of the project are: To deliver a suite of intelligent diagnostic tools for plant To provide platform technologies for integrated network planning and asset management To progress plans to develop and implement improved and reduced environmental impact networks To develop models and recommendations for network operation and management 							
Expected Timescale to adoption	10 :	10 yearsDuration of benefit once achieved20 Ye			/ears			
Probability of Success	25%			Project NPV			£6	62k

Potential for achieving expected benefits	Asset management is core to the business. The appropriate use of the emerging opportunities for condition monitoring is key to optimising performance, both financially and in quality of supply. Some of the technologies being developed in this programme are likely to be utilised, however much more important is the broader window this work gives to the global research community. Through demonstration sites the true value of condition monitoring will be identified, enabling appropriate business decisions on adoption of technologies.
Project Progress June 2009	 Technology & trials: The detection, control and protection synchronous islands have been demonstrated on a 50kVA diesel generator. The demonstration employs a real-time phasor measurement system. An AC optimal power flow method for assessing the maximum distributed generation (DG) penetration in distribution networks has been developed. A novel method of detection of loss of grid techniques is being developed. A low-cost system with internet broadcast capability has also been developed: four are currently in operation. An investigation into how regions of a distribution network can operate during emergency islanded mode conditions is also underway. Optimized design of existing overhead lines of wood pole line, and a lattice tower line. The methodology has been employed to analyse the behaviour of low-sag composite conductors on a 33kV wood-pole structure. The model is now being utilised on a wood-pole line on Scottish Power and a lattice tower line on the National Grid, and may substantially improve the performance of sections of the network without major infrastructure changes. A unique installation for transformer monitoring at National Grid comprising of two 275/132kV, 180MVA transformers, is implementing results of research on condition monitoring architectures, diagnostics and machine learning. Development of condition monitoring architecture for power networks has progressed well and is being implemented on a National Grid transmission transformer. Diagnostic and support modules are included, and exploit a range of ageing models including those developed within this project. Work on ageing has shown that the rate of damage may not be affected by harmonic content, but resulting partial discharge signals change significantly. PP-based alternatives to XLPE cable insulation have been characterised. Additional funding has been secure for the more applied work to develop routes to commer
Collaborative Partners	National Grid, Scottish Power, Scottish and Southern, United Utilities, Western Power Distribution, Central Networks, CE Electric, NIE, Advantica & EDF Energy Networks.
R&D Provider	Universities of Manchester, Southampton, Edinburgh, Liverpool, Strathclyde, Queens (Belfast).

WPD SMART NETWORK TRIAL

Project Title	Smart Netv	vork Trial					
Description of project	To equip all HV/LV pole and ground mounted distribution s/s fed from one 132/66/11 kV primary s/s, with measurement facilities to capture loading information and communicate back into WPD corporate systems including ENMAC scada.						
Expenditure for financial year	Internal External Total	£53,100 £44,000 £97,100	Expenditure previous (IFI financial yea) Externa			
Project Cost (Collaborative + external	£97,	·	Projected 08 costs for WP	/09 External	£53,100		
Technological area and / or issue addressed by project	existing leg to WPD co project wor Sele mon Deve rang be fit Esta Mon Prov Asse	 monitoring, metering, communicating, and housing. Developing risk assessed installation techniques covering a wide range of legacy distribution system assets to which the above will be fitted Establishing communication links to a WPD data server Monitoring meter outputs / communication path continuity 					
Type(s) of innovation involved	Technological substitution from different applicationProject Benefits RatingProject Residual RiskOverall Project Score						
involved			11	0	11		
Expected Benefits of Project	 Enhanced Network Utilisation - savings to Customers Facilitating active network management, to deliver the management of substantially increased intermittency associated with expanded distributed generation, demand side management and wider use of electric vehicles Providing ready connections and comms link for distribution substations to be used as data aggregation hub for two way data collection / control of domestic smart meters. Providing the data required for site specific cost benefit analysis of loss reduction measures, such as early replacement of higher loss distribution transformers Providing monitoring of voltage, power factor and harmonic content, leading to maintenance / improvement of power quality Enhanced speed of outage detection 						

Expected Timescale to adoption	1 year	Duration of benefit once achieved	40 year main equipment, 15 years technology refresh			
Probability of Success	50%	Project NPV	£45k			
Potential for achieving expected benefits	Utilisation and loss reduction benefits already demonstrated. The extent of use of the installations as part of active network management will be influenced by Government decisions on domestic smart meters, and initiatives for management of intermittency, and WPD are actively engaged in this debate.					
Project Progress June 2009	Technology & trials: The project was initiated in December 2008 and installations completed by 5th February 2009 with all data successfully flowing and assessed by 13th March 2009. Data display via Enmac demonstrated. A proposal for wide scale roll out has been developed and a number of presentations and demonstrations have been provided to senior staff of Ofgem and DECC.					
Collaborative Partners	None for this demonstration trial. Discussions on subsequent proposal have taken place with a number of major manufacturers.					
R&D Provider	EATL - work on statistics of CT accuracy					

HELICOPTER MOUNTED PARTIAL DISCHARGE DETECTION - FEASIBILITY TRIAL

Project Title	Helicopter mounted partial discharge detection feasibility trial							
Description of project	The University of Strathclyde and the spin off company Elimpus, have developed ground based systems for locational detection of partial discharges using time of flight systems. One of these utilises an array of aerials contained within a van mounted "roof box"; a size compatible with the aerial separation that might be achieved between the skids of a typical Jet Ranger or Squirrel helicopter employed by DNOs for overhead line patrols. A small feasibility trial was undertaken to asses the viability of a larger IFI project that would entail development of equipment suitable for CAA flight certification.							
	Internal	£51	7	Expenditure i	'n	Internal		£ nil
Expenditure for financial year	External	£639	93	previous (IFI)		External		£ nil
initiational your	Total	£691	10	financial year	S	Total		£ nil
Project Cost						Internal		£ 500
(Collaborative +	£19	,696		Projected 09/ costs	/10	External		£3000
oxtornal	210	,000		00010		Total		£3500
area and / or issue addressed by project Type(s) of innovation	reliably det	Can ground source partial discharges in open terminal substations be reliably detected from a helicopter?System prototype / trialProject Benefits RatingProject Residual RiskOverall Project Score						
involved				10	-7	-7		17
Expected Benefits of Project	If so the project would offer the ability to quickly scan EHV open terminal s/s as part of routine overhead line patrols, offering improved reliability at low incremental patrol cost.							
Expected Timescale to adoption	2 years Duration of benefit 10 years once achieved					/ears		
Probability of Success	2	5%	Project NPV £5k			5k		

Potential for achieving expected benefits	Asset health assessment is key to delivery of network reliability and safety performance. The feasibility trial employed existing technology, but stand off distance and disturbance from the helicopter and its systems, posed potential challenges. A minimal NPV has been included above, as a subsequent project would be needed to deliver a flight certified solution.
Project Progress June 2009	<u>Technology & trials</u> : Flight trial has demonstrated the ability to detect ground based discharge activity. At the time of writing it not yet determined if some other activity was not detected.
Collaborative Partners	Central Networks, Scottish & Southern
R&D Provider	Elimpus / University of Strathclyde

WPD / BATH UNIVERSITY - LIFE CYCLE ASSESSMENT 11kV OVERHEAD LINES AND UNDERGROUND CABLES

Description of project	Life cycle assessment of 11kV overhead line and underground cable -							
Expenditure for financial year 08/09	Total £ 15,000	External £ 15,000	Intern £ nil		Expenditure in previous financial years per WPD	£ 702		
Technological area and / or issue addressed by project	associated installation,	Licence area To gain an understanding of the "embedded" carbon and carbon emission associated with the material extraction, treatment, manufacture, shipping, installation, operation, inspection, maintenance, and end of life action for three ratings of 11kV overhead line and two nearest equivalent ratings of underground cable.						
Type(s) of innovation involved	Incrementa							
Expected Benefits of Project	 The purpose of the project is to inform debate on - Initial sizing of conductor to reduce losses and carbon footprint The merits of early replacement intervention to reduce losses and carbon footprint The merits of amending the current loss incentive mechanism, having regard to carbon 							
Expected Timescale to adoption	1 year							
Estimated Success probability (at start of project)	100% - in providing data, 10% in radical change to loss incentive							
PV of Project Costs	£ 15,700PV of Project Benefits£500,000NPV of Project Project £183,000							
	The above NPV benefit is derived from this work supporting a move to a "holistic" NPV life time assessment view of the treatment of losses. NPV assessments in relation to low loss t/fs and non tapered LV cables has been passed to Ofgem and on these a lifetime NPV saving (using full costed losses) amounts to > \pounds 2M per Licence, or > \pounds 200K if a 10% "success" factor is applied							
R&D Provider	University of Bath							

8.0 NOTE ON NET PRESENT VALUE

- 8.1 There are several approaches to net present value assessments of research type work. One approach is to scale up test discount rates to reflect the "riskiness" of a project whilst another is to employ a standard test discount rate and employ a success probability factor, for example 25, 50, 75%. The latter was described in a report commissioned by Ofgem on Innovation in Electricity Distribution Networks and prepared by Mott MacDonald/BPI in March 2004, and is the approach employed by WPD.
- 8.2 Experience of the typical payback of successful projects undertaken within an STP Module is typically in the range of 6 8 X investment, which success probabilities of the programme projects tends to be at the 25% band. Timescales of individual projects within an STP Module are of the order of 3 years, with break milestones built in. The test discount rate employed is the WPD cost of capital from DPCR4, i.e. 6.9%. The average duration of benefit once a successful project has been achieved has been assessed as 10 years.
- 8.3 Whilst it is possible that the effect of some financial benefits might be taken into account by Ofgem in a subsequent Distribution Price Control Review (DPCR), Customers would continue to receive the benefits of such successful research and so our NPV benefit calculations do not terminate at 2010, the date of the next DPCR.