LCN Fund Full Submission

Supplementary Answer Form

Tick if this answer is Confidential: ☐

Tick if this answer has been provided verbally: ☐

Project code:	SSET206	Question Number	5
Question date	29 August 2013	Answer date	5 September 2013
Submission section question relates to	2: Project Description Early Bilateral		
Topic	Technical		
Question	What metering is currently installed in the secondary substations in the target area?		
Notes on question			
Answer	There is currently no metering equipment installed in any of the secondary substations in the Solent region, however there is basic monitoring equipment installed in the form of Maximum Demand Indicators (MDIs). This is a thermally-operated measuring instrument which is used to size the distribution transformers on historic demand, rather than anticipated demand. The level of information required for the SAVE project requires a level of sophistication far greater than is afforded by the use of MDIs. As a result we will install a low-cost monitoring option in the secondary substations that supply the communities of interest in the Community Coaching trial.		
Attachments			
Verbal Clarifications (Consultants)			