

## **GB Gas Storage Facilities**

## **Overview**

This information is published in fulfilment of Ofgem's obligations under section 19A of the Gas Act. The operational data is correct as at 31 August 2018.

Please note that the following applies to this data:

- All values are reported at standard conditions, and correct as at 31 August 2018.
- All technical information is provided for guidance purposes only actual working gas volume, withdrawal rates, injection rates and durations vary and depend on the operation of each facility.

Facility	Estimated Working gas volume (mcm)	Approx. max. production rate (mcm/d)	Approx. max. injection rate (mcm/d)	Withdrawal duration, from full assuming max. rate (days)	Start date	Owner			
Facilities operating under negotiated Third Party Access (nTPA) rules									
Hornsea	235	12	3	20	1979	SSEHL			
nTPA exempt facilities that are currently operational									
Hatfield Moor	70	2	2	35	2000	Scottish Power			
Humbly Grove <sup>1</sup>	300	7	8	43	2005	Humbly Grove Energy			
Aldborough Phase <sup>2,3</sup>	195	31	29	6	2009	SSEHL / Equinor			
Holford (formerly Byley) <sup>4</sup>	200	22	22	15	2011	Uniper UK Ltd			
Hill Top Farm <sup>5</sup>	20	2	2	10	2011	EDF Energy			
Stublach Phase 1 <sup>6</sup>	220	18	16	12	2014	Storengy			

<sup>&</sup>lt;sup>1</sup> https://epr.ofgem.gov.uk//document/Download/26093

1

 $<sup>^2\ \</sup>underline{\text{https://www.ofgem.gov.uk/ofgem-publications/41230/stuk-revised-final-decision-signed-pdf}}$ 

<sup>&</sup>lt;sup>3</sup> https://www.ofgem.gov.uk/ofgem-publications/41229/sse-revised-final-decision-signed-pdf

<sup>4</sup> https://www.ofgem.gov.uk/ofgem-publications/41305/11074-16605-pdf

<sup>&</sup>lt;sup>5</sup> <a href="https://www.ofgem.gov.uk/ofgem-publications/41182/final-decision-edf-energy-plcs-application-exemption-section-19b-qas-act-1986-pdf">https://www.ofgem.gov.uk/ofgem-publications/41182/final-decision-edf-energy-plcs-application-exemption-section-19b-qas-act-1986-pdf</a>

<sup>6</sup> https://www.ofgem.gov.uk/ofgem-publications/41194/storengydecisiondocfinal-2-pdf



Facility	Estimated Working gas volume (mcm)	Approx. max. production rate (mcm/d)	Approx. max. injection rate (mcm/d)	Withdrawal duration, from full assuming max. rate (days)	Start date	Owner			
nTPA exempt capacity scheduled to become operational									
Hill Top Farm (with HT7 & HT11 commissioned)	56	14	14	4	Expected Sep 2019	EDF Energy			
Stublach Phases 1 & 2	400	30	30	13	Expected Dec 2019	Storengy			